

Volume II

Airport Emergency Plan

Division Director, Miami-Dade Aviation Department, Airside Operations

Chief, Miami-Dade Fire Rescue, Aviation Division

Major, Miami-Dade Police Department, Airport District

Cur. Revision Date: 12/01/20
Prev. Revision: 08/01/19
Original Date: 11/01/04

SECTION 1

Table of Contents

1. INTRODUCTION	1-5
1.1. TERMS AND DEFINITIONS	1-5
1.2. GENERAL	1-9
1.3. PLAN DEVELOPMENT AND MAINTENANCE	1-9
1.4. COMMAND AND CONTROL	1-9
1.4.1. Purpose	1-9
1.4.2. Situation and Assumptions	1-10
1.4.3. Operations	1-10
1.4.3.1. Incident Command Post (ICP)	1-10
1.4.3.2. MDAD Airport Emergency Operations Center (Airport EOC)	1-10
1.4.3.3. Family Room	1-11
1.4.3.4. Reunification Center	1-11
1.4.3.5. Rendezvous Points	1-11
1.4.3.6. MIA Air Traffic Control Tower (ATCT)	1-11
1.4.3.7. Emergency Response Organizations	1-12
1.4.4. Organization and Assignment of Responsibilities	1-12
1.4.4.1. MDAD Aviation Director / Deputy Director / Assistant Director of Operations	1-12
1.4.4.2. Aircraft Rescue and Fire Fighting (ARFF)	1-12
1.4.4.3. Law Enforcement	1-12
1.4.4.4. Public Works	1-13
1.4.4.5. Public Information Officer	1-13
1.4.4.6. Press Coverage Control	1-13
1.4.4.7. Health and Medical Coordinator	1-14
1.4.4.8. Animal Care and Control Agency	1-14
1.4.4.9. Airside Operations	1-14
1.4.5. Administration and Logistics	1-15
1.4.6. Plan Development and Maintenance	1-15
1.5. COMMUNICATIONS	1-15
1.5.1. Purpose	1-15
1.5.2. Situation and Assumptions	1-15
1.5.3. Operations	1-16
1.5.4. Organization and Assignment of Responsibilities	1-16
1.5.4.1. Miami-Dade Aviation Department	1-16
1.5.4.2. Miami-Dade Fire Rescue, Aviation Division	1-16
1.5.4.3. Miami-Dade Police Department, Airport District	1-17
1.5.5. Administration and Logistics	1-17
1.5.6. Plan Development and Maintenance	1-17
1.5.7. Authorities and References	1-17

1.6. ALERT NOTIFICATION AND WARNING	1-17
1.6.1. Purpose	1-17
1.6.2. Situation and Assumptions	1-17
1.6.3. Operations	1-17
1.6.4. Organization and Assignment of Responsibilities	1-18
1.6.4.1. Miami-Dade Fire Rescue, Aviation Division	1-18
1.6.4.2. Miami Air Traffic Control Tower	1-18
1.6.5. Administration and Logistics	1-18
1.6.6. Plan Development and Maintenance	1-18
1.6.7. Authorities and References	1-18
1.7. EMERGENCY PUBLIC INFORMATION (EPI)	1-19
1.7.1. Purpose	1-19
1.7.2. Situation and Assumptions	1-19
1.7.3. Operations	1-19
1.7.4. Organization and Assignment of Responsibilities	1-19
1.7.4.1. MDAD Aviation Director / Deputy Director / Assistant Director of Operations	1-20
1.7.4.2. MDAD Media Relations Manager	1-20
1.7.4.3. All Tasked Organizations	1-20
1.7.5. Administration and Logistics	1-20
1.7.6. Plan Development and Maintenance	1-20
1.7.7. Authorities and References	1-21
1.8. PROTECTIVE ACTIONS	1-21
1.8.1. Purpose	1-21
1.8.2. Situation and Assumptions	1-21
1.8.3. Operations	1-21
1.8.4. Organization and Assignment of Responsibilities	1-22
1.8.4.1. Miami-Dade Police Department, Airport District	1-22
1.8.4.2. MDAD Public Information Officer	1-22
1.8.4.3. All Tasked Organizations	1-22
1.8.5. Administration and Logistics	1-22
1.8.6. Plan Development and Maintenance	1-22
1.8.7. Authorities and References	1-23
1.9. LAW ENFORCEMENT/SECURITY	1-23
1.9.1. Purpose	1-23
1.9.2. Situation and Assumptions	1-23
1.9.3. Operations	1-23
1.9.4. Organization and Assignment of Responsibilities	1-25
1.9.5. Administration and Logistics	1-25
1.9.6. Plan Development and Maintenance	1-26
1.9.7. Authorities and References	1-26
1.10. FIREFIGHTING AND RESCUE	1-26
1.10.1. Purpose	1-26
1.10.2. Situation and Assumptions	1-26
1.10.3. Operations	1-27

1.10.3.1. Mobilization	1-27
1.10.3.2. Phases of Response	1-28
1.10.3.3. Incident Command System	1-28
1.10.4. Organization and Assignment of Responsibilities	1-28
1.10.5. Administration and Logistics	1-29
1.10.6. Plan Development and Maintenance	1-29
1.10.7. Authorities and References	1-29
1.11. HEALTH AND MEDICAL	1-29
1.11.1. Purpose	1-29
1.11.2. Situation and Assumptions	1-29
1.11.3. Operations	1-30
Table 1 Hospital Capabilities Chart	1-33
1.11.4. Organization and Assignment of Responsibilities	1-33
1.11.5. Aircraft Medical Emergencies	1-34
1.11.5.1. Miami-Dade Fire Rescue, Aviation Division	1-34
1.11.5.2. Miami-Dade Aviation Department	1-34
1.11.6. MDRF Medical Operations Manual, Multiple Casualty Incidents	1-34
1.11.6.1. Initial Response Procedures	1-34
1.11.6.2. Command	1-35
1.11.6.3. Triage Group Leader	1-35
1.11.6.4. Treatment Group Leader	1-35
1.11.6.5. Transport Group Leader	1-36
1.11.6.6. Staging Group Leader	1-36
1.11.6.7. MDRF Fire Alarm Office (FAO)	1-37
1.11.7. Administration and Logistics	1-37
1.11.8. Plan Development and Maintenance	1-37
1.11.9. Authorities and References	1-37
1.12. RESOURCE MANAGEMENT	1-37
1.12.1. Purpose	1-37
1.12.2. Situation and Assumptions	1-38
1.12.3. Operations	1-38
1.12.4. Organization and Assignment of Responsibilities	1-39
1.12.5. Administration and Logistics	1-39
1.12.6. Plan Development and Maintenance	1-39
1.12.7. Authorities and References	1-40
1.13. AIRPORT OPERATIONS AND MAINTENANCE	1-40
1.13.1. Purpose	1-40
1.13.2. Situation and Assumptions	1-40
1.13.3. Operations	1-40
1.13.4. Organization and Assignment of Responsibilities	1-40
1.13.4.1. MDAD Aviation Director / Deputy Director / Assistant Director of Operations	1-41
1.13.4.2. MDAD Division Director, Airside Operations	1-41
1.13.4.3. MDAD Maintenance Operations	1-41
1.13.4.4. Miami-Dade Police Department, Airport District	1-42
1.13.4.5. All Other Tasked Organizations	1-42
1.13.5. Administration and Logistics	1-42

1.13.6. Plan Development and maintenance1-42

1.13.7. Authorities and References1-43

1.14. DELEGATION OF AUTHORITY1-43

1.15. EMERGENCY PERSONNEL TRAINING1-43


1.16. ADMINISTRATION AND COORDINATION OF THE EMERGENCY PLAN1-43

EXHIBITS

1A EMERGENCY NOTIFICATION CHART1-45

1B AIRCRAFT ACCIDENT INCIDENT COMMAND SYSTEM LAYOUT1-46

1C MIA EXISTING AIRPORT OPERATIONS MAP1-47



1. INTRODUCTION

1.1. TERMS AND DEFINITIONS

AED

Automated External Defibrillators

A small portable device used on somebody who has suffered a heart attack to restore a regular heartbeat. Units are located throughout the airport and in each MDPD vehicle.

Aircraft Accident

Any occurrence associated with the operation of an aircraft that takes place between the time the person boards the aircraft with the intention of flight and the time such person has disembarked, in which a person suffers death or serious injury as a result of the occurrence or in which the aircraft receives substantial damage.

Aircraft Incident

Any occurrence associated with the operation of an aircraft that is not considered an aircraft accident.

Aircraft Operator

Any person, organization, or enterprise engaged in or offering to engage in, aircraft operations.

Airport EOC

Miami-Dade Aviation Department Airport Emergency Operations Center

Location responsible for the strategic overview of the disaster; collect's, gathers and analyzes data; disseminates information to all concerned agencies and individuals. Responsible for making operational decisions; does not normally control field assets directly, leaving tactical decisions to the incident commander.

AOC

Airport Operations Center

A 24-hour, multi-function operation critical to MDAD's response to emergencies. In the event an emergency occurs, initiates the activation of the Incident Notification Call List (INCL) which contain key and essential organizations and/or personnel to be contacted for various emergencies. (formerly Operations Control Room aka: OCR)

Airside

The movement, non-movement areas, ramps and aprons of an airport, adjacent terrain, and buildings or portions thereof.

Alert I (Local Standby)

An aircraft that is known or suspected to have an operational defect that should not normally cause serious difficulty achieving a safe landing. This is notification only. No response is required. All units involved will be manned and will standby in quarters.

Alert II (Full Emergency)

An aircraft that is known or is suspected to have an operational defect that affects normal flight operations to the extent that there is danger of an accident. All units respond to pre-designated positions.

Alert III (Aircraft Accident)

An aircraft incident/accident has occurred on or in the vicinity of the airport. All designated emergency response units proceed to the scene in accordance with established plans and procedures.

AOA - Air Operations Area

APHIS

Animal and Plant Health Inspection Service.
(Part of USDA)

ARFF - Aircraft Rescue and Fire Fighting

ATCT - MIA Air Traffic Control Tower

CFR - Code of Federal Regulation

County EOC

Miami-Dade County Emergency Operations Center

A protected site from which emergency officials coordinate, monitor, and direct emergency response activities during an emergency. The Miami-Dade County Department of Emergency Management & Homeland Security Office is the EOC for Miami-Dade County.

CP

Command Post

A point where responding agencies are briefed on the situation as they arrive to report and assume control of the individual aspects of the operation.

Disaster

An occurrence of a natural catastrophe, technological accident, or human-caused event that has resulted in severe property damage, deaths, and/or multiple injuries. As used in this Emergency Plan, a large-scale disaster is one that exceeds the capability of the airport and local

communities and requires state, and potentially, federal involvement.

EAS

Emergency Alert System

A digital technology (voice/test) communications system consisting of broadcast stations and interconnecting facilities authorized by the Federal Communication Commission. The system provides the President and other national, state, and local officials the means to broadcast emergency information to the public before, during, and after disasters.

FAA – Federal Aviation Administration

FAO - Fire Alarm Office (MDFR)

GAC - General Aviation Center

HAZMAT

Hazardous Material

Any substance or material that, when involved in an accident and released in sufficient quantities, poses a risk to people(s) health, safety, and/or property. These substances and materials include explosives, radioactive materials, flammable liquids or solids, combustible liquids or solids, poisons, oxidizers, toxins, and corrosive materials.

HCP

Hurricane Command Post

Location responsible for the overview and coordination of airport resources during a hurricane. collects, gathers and analyzes information during the event and disseminates information to all concerned agencies and individuals.

Hurricane

A tropical cyclone, formed in the atmosphere over warm ocean areas, in which wind speeds reach 74 miles per hour or more and blow in a large spiral around a relatively calm center or eye; circulation in counter-clockwise in the Northern Hemisphere and clockwise in the Southern Hemisphere.

IC

Incident Commander

The individual responsible for all incident activities, including the development of strategies and tactics and the ordering and the release of resources. The IC has overall authority and responsibility for conducting incident operations and is responsible for the management of all incident operations at the incident site.

ICP

Incident Command Post

The field location where the primary command functions are performed. The ICP may be co-located with the incident base or other incident facilities.

ICS

Incident Command System

A standardized organizational structure used to command, control, and coordinate the use of resources and personnel that have responded to the scene or an emergency. The concepts and principles for ICS include common terminology, modular organization, integrated communication, unified command structure, consolidated action plan, manageable span of control, designated incident facilities, and comprehensive resource management.

JIC

Joint Information Center

A central point of contact for all news media near the scene of a large-scale disaster. News media representatives are kept informed of activities and events by public information officials who represent all participating agencies that are collected at the JIC.

MDAD - Miami-Dade Aviation Department

MDFR - Miami-Dade Fire Rescue, Aviation Division

MDPD - Miami Dade Police Department, Airport District

MIA - Miami International Airport

Movement Area

The runways, taxiways, and other areas of an airport that aircraft use for taxiing, takeoff, and landing, exclusive of loading ramps and parking areas, and that are under the control of an air traffic control tower.

NFPA

National Fire Protection Association

The NFPA develops, publishes, and disseminates more than 300 consensus codes and standards intended to minimize the possibility and effects of fire and other risks.

NIMS

National Incident Management System

Provides a systematic, proactive approach guiding government agencies at all levels, the private sector, and nongovernmental organizations to

work seamlessly to prepare for, prevent, respond to, recover from, and mitigate the effects of incidents, regardless of cause, size, location, or complexity, in order to reduce the loss of life or property and harm to the environment.

NOAA - National Oceanic and Atmospheric Administration

Non-Movement Area

Taxi-lanes, aprons, and other areas not under the control of air traffic or at airports without an operating airport traffic control tower.

NTSB

National Transportation Safety Board

Responsible for the organization, conduct, and control of all accident investigations involving civil aircraft, or civil and military aircraft, within the United States, its territories and possessions. It is also responsible for investigation of accidents which occur outside the United States, and which involve U.S. civil aircraft, at locations determined to be not in the territory of another state (i.e. in international waters).

NRC - United States Nuclear Regulatory Commission

Penalty Box

A remote area on the airfield designated to isolate aircraft for inspection.

PIO

Public Information Officer

A member of the Command Staff responsible for interfacing with the public and media and/or with other agencies with incident-related information requirements.

Rendezvous Points

Predetermined access point throughout the airport where support response personnel, vehicles and other equipment can be staged to enter the airfield.

Runway Safety Area

A defined surface surrounding the runway prepared or suitable for reducing the risk of damage to airplanes in the event of undershoot, overshoot, or excursion from the runway.

SOP

Standard Operating Procedure

A set of instructions constituting a directive, covering those features of operations which lend themselves to a definite, step-by-step process of accomplishment. SOPs supplement Airport Emergency Plan (AEP) by detailing and specifying how tasks assigned in the AEP are to be carried out.

Significant Body of Water

A body of water or marsh land is significant if the area exceeds one-quarter square mile and cannot be traversed by conventional land rescue vehicles.

Staging Area

A pre-arranged, strategically placed area where support response personnel, vehicles and other equipment can be held in readiness for use during the emergency.

Tornado

A local atmospheric storm, generally of short duration, formed by winds rotating at very high speeds, usually in a counter clockwise direction. The vortex, up to several hundred yards wide, is visible to the observer as a whirlpool-like column of winds rotating about a hollow cavity or funnel. Winds may reach 300 miles per hour or higher.

Triage

Sorting and classification of casualties to determine the order of priority for treatment and transportation by the use of universally recognized triage color code tags.

Black – Expectant (Deceased)

Red – Immediate (Critical)

Yellow – Delayed (Serious)

Green – Minimal (Minor)

USDA - United States Department of Agriculture

UC

Unified Command

An ICS application used when more than one agency has incident jurisdiction or when incidents cross political jurisdictions. Agencies work together through the designated members of the UC, often the senior person from agencies and/or disciplines participating in the UC, to establish a common set of objectives and strategies.

UCP - Unified Command Post

Warning

The alerting of emergency response personnel and the public to the threat of extraordinary danger and the related effects that specific hazards may cause. A warning issued by the National Weather Service (e.g. severe storm warning, tornado warning, tropical storm warning) for a defined area indicates that the particular type of severe weather is imminent in that area.

Watch

Indication by the National Weather Service that, in a defined are, conditions are favorable for the specified type of severe weather (e.g. standing water flood watch, severe thunderstorm watch, tornado watch, or tropical storm watch).

1.2. GENERAL

This Emergency Plan constitutes the Emergency Standard Operating Procedure (SOP) for the Miami-Dade Aviation Department (MDAD), Miami International Airport (MIA), and Miami, Florida.

It is recognized that not all emergency conditions can be anticipated, therefore, if an emergency arises that is not covered by this plan, the Aviation Director or his/her representative, has the authority to modify this plan except where such modification may contravene Federal Aviation Administration (FAA) regulations.

Procedures outlined herein are for the guidance of all Miami-Dade Aviation Department (MDAD) employees, airport tenants, users, and other agencies. They have been designed to establish guidelines and areas of responsibilities in times of emergency, utilizing the National Incident Management System (NIMS) for on-scene control, reference Exhibit 1B, Aircraft Accident Incident Command System Layout.

This emergency plan provides instructions for the actions to be employed in the event of: aircraft incidents and accidents, bomb incidents, structural fires, fuel farm or storage facility fires, natural disasters, sabotage, unlawful interference, hazardous materials incidents, movement area lighting power failure and water rescue responses. The Emergency Plan topics are outlined in the Table of Contents.

The response of all personnel concerned must be directed toward the following actions in order of priority listed:

1. Rescue and lifesaving of persons involved.
2. Safety of persons and equipment not directly involved.
3. Protection of wreckage from disturbance for later investigation by proper authorities.
4. Keeping the unaffected areas of the airport in an operational condition.
5. Returning the airport to normal operating status as soon as possible.
6. Removal of disabled aircraft and contents.
7. Salvage of cargo and equipment.

1.3. PLAN DEVELOPMENT AND MAINTENANCE

Review of this plan is made once every 12 consecutive calendar months through an AEP Annual review and once every 36 consecutive calendar months, through a full-scale airport emergency exercise. Revisions to this Plan shall be maintained by the Division Director, Airside Operations or his/her designee. A true and current copy of this Airport Emergency Plan shall be maintained by the Airside Operations Supervisor, Ramp Control.

1.4. COMMAND AND CONTROL

1.4.1. Purpose

This section provides overview of the mechanisms that MIA utilizes to direct and control initial and sustained emergency response and recovery activities. It provides for

the necessary and critical actions essential to saving lives, protecting property, and restoring the airport during and following emergency situations.

1.4.2. Situation and Assumptions

If an emergency arises which requires MIA response personnel, such as ARFF, Law Enforcement, and or Operations, the National Incident Management System (NIMS) shall be utilized. The management of support resources in the event of emergencies is detailed in the Miami-Dade Aviation Department, Continuity of Operations Plan (COOP), revised annually. This plan establishes a framework for MDAD to prepare for, respond to, mitigate the impacts of, and recover from emergencies.

Although MIA has on-airport resources which can meet most emergencies, if additional resources are required, off-airport equipment can be obtained from Miami-Dade County. Additional resources can be obtained from adjacent cities, through Mutual-Aid agreements with those cities.

1.4.3. Operations

1.4.3.1. Incident Command Post (ICP)

The Incident Command Post (ICP) will be established on site as rapidly as possible following the incident by the Incident Commander (IC). Support staffing of the ICP shall be comprised of representatives of the Miami-Dade Fire Rescue, Airport Division; Miami-Dade Police Department, Airport District; MDAD Operations; MDAD Maintenance; the aircraft Operator; and such other agencies as may be requested by the IC in response to the emergency. Responsibility of the ICP personnel shall be as follows:

1. Direct and/or coordinate all emergency response activities at the airport in connection with the incident. Coordinate all activities with the Department Airport Emergency Operations Center (Airport EOC)¹ upon such being activated.
2. Take action to maintain airfield safety, initiating appropriate notices, Notice to Airmen (NOTAMS), or other communications.
3. Ensure that the various departments and agencies involved have been notified and are performing their assigned functions².
4. Relay or initiate requests for additional help or service needed.
5. Restore airport operations to the maximum extent possible after the emergency area is isolated and restore normal operations as soon as possible.

1.4.3.2. Airport Emergency Operations Center (Airport EOC)

In accordance with the Airport Certification Manual of Miami International Airport, provisions for a MDAD Airport EOC have been established in the Concourse 'E' 5th Floor Conference Room and will be activated at the direction of the Deputy Di-

¹ Reference section 1.4.3.2., MDAD Airport Emergency Operations Center (Airport EOC)

² Reference Exhibit 1A, Emergency Notification Chart

rector, or Assistant Director of Operations or his/her designated representative, in the event of a major emergency.

1.4.3.3. Family Room

A Family Room has been created for the use of families of victims of aircraft accidents. This room can be activated if necessary by the Airport EOC in coordination with the IC. The Family Room will not be set up adjacent to the Airport EOC or near the Press room.

1.4.3.4. Reunification Center

The Reunification Center will be established off-airport by the Airline/Aircraft Operator to reunite victims of aircraft accidents with their families as soon as possible following an aircraft accident.

1.4.3.5. Rendezvous Points

As outlined in the Miami-Dade Fire Rescue's Airport Operations and Procedures; in order to assist the IC in effective deployment of additional equipment from off-airport stations, rendezvous points for on-airport incidents have been established³. The purposes of these points are to:

1. Ensure that only authorized persons are admitted to the scene of an emergency.
2. Provide an established point from which emergency vehicles or convoys can enter the emergency area and be directed or escorted to the incident scene.

All vehicles responding to an on-airport emergency shall enter only at the designated rendezvous point(s). Dependent upon the location of the incident, the IC shall select the appropriate rendezvous point(s) and shall establish such as "Convoy Assembly Points". The MDPD, Airport District, in coordination with the MDAD Airside Operations Division will control access through these points.

Properly identified emergency or airport vehicles maintaining two-way radio communications with Air Traffic Control Tower (ATCT), shall escort vehicles authorized to enter the airport through these points to the emergency scene. Emergency or airport vehicles equipped with ground control radios and in communication with ATCT may receive their own clearance from ATCT and proceed accordingly if released to do so. Unless safety of life or property would be jeopardized by so doing, all vehicles, including emergency vehicles, shall proceed to the extent possible, on established vehicular roadways, and not on or across runways or taxiways.

1.4.3.6. MIA Air Traffic Control Tower (ATCT)

As stated in the US Department of Transportation / Federal Aviation Administration Aeronautics Information Manual, the Miami ATCT will be the first agency aware of aircraft related emergencies and incidents. The Letter of Agreement, ti-

³ Reference Exhibit 2A, Fire Mutual Aid Rendezvous Points

tled “Emergency Procedures” between the Miami Federal Aviation Administration ATCT and MDAD describes the emergency procedures to be employed by the Miami ATCT⁴. Details of the procedures are listed in Hazard Section 2, “Aircraft Incidents and Accidents”. In the event of any emergency other than those related to aircraft, the Miami ATCT will follow the procedure listed for each type of Hazard Section described herein.

1.4.3.7. Emergency Response Organizations

Any emergency response organization required under this plan shall follow the Incident Command System structure⁵ and become part of the Unified Command Post.

1.4.4. Organization and Assignment of Responsibilities

1.4.4.1. MDAD Aviation Director / Deputy Director / Assistant Director of Operations

1. Initiates the activation of the Airport EOC (full or partial), when appropriate
2. Directs all tasked organizations to ensure appropriate response in accordance with established plans and procedures

1.4.4.2. Aircraft Rescue and Fire Fighting (ARFF)

The ARFF requirements at MIA are performed by the Miami-Dade Fire Rescue, Airport Division. When notified of any emergency, shall:

1. Respond to incident with appropriate personnel and firefighting equipment in accordance with standard operating procedures.
2. Identify an initial IC and establish an ICP, if appropriate
3. Performs IC duties at the scene of the incident as appropriate
4. Keeps the IC and Airport EOC informed of scene status, as appropriate
5. Manages fire/rescue resources, directs fire operations, conducts necessary rescue operations, and determines the need to evacuate the area in the vicinity of the scene or to initially shelter in place.

1.4.4.3. Law Enforcement

The Law Enforcement requirements at MIA are performed by the Miami-Dade Police Department, Airport District. When notified of any emergency, shall:

1. Respond to scene, or other location, with appropriate personnel and law enforcement equipment, in accordance with standard operating procedures and as prescribed by 49 CFR 1542, Airport Security.
2. Identify an initial IC and establish an ICP, if appropriate
3. Performs IC duties at the scene of the incident as appropriate
4. Manage law enforcement resources and directs law enforcement operations.

⁴ Reference Exhibit 14A, Miami ATC Tower and Miami-Dade Aviation Department Letter of Agreement, Emergency Procedures

⁵ Reference Exhibit 1B, Aircraft Accident Incident Command System Layout

1.4.4.4. Public Works

The Miami-Dade Aviation Department Public Works section, upon being notified of an emergency, shall:

1. Send response teams/personnel, equipment, and vehicles to the scene, staging area, or other location, when appropriate or requested.
2. Keep the IC and Airport EOC informed of scene status, as appropriate
3. Manage public works resources and directs public works operations

1.4.4.5. Public Information Officer

The Miami-Dade Aviation Department Public Information Officer shall:

1. When notified, report to the Airport EOC
2. Perform interface with media regarding the emergency

1.4.4.6. Press Coverage Control

The following procedures shall be implemented for any emergencies where press coverage is expected.

1. Aircraft Emergencies Within Airport Boundaries

All press will be directed to a designated assembly point by MDAD PIO. Such location shall be coordinated with the MDAD Assistant Director of Operations. This location will be the assembly area for all press personnel authorized to cover an airport emergency

a) Authorized Press Personnel

Only officially authorized members of the press will be admitted to the briefing area, the Air Operations Area (AOA), or transported to the scene of the emergency.

UNDER NO CIRCUMSTANCES WILL THE PRESS OR ANY OTHER PERSONNEL NOT INVOLVED IN LIFESAVING OR FIRE-FIGHTING OPERATIONS BE PERMITTED INSIDE SECURITY LINES AT THE SCENE OF THE INCIDENT DURING THE LIFESAVING OR FIRE-FIGHTING PHASE.

The Assistant Director of Operations or his/her appointed representative will authorize press access to the scene only with the approval of the Incident Commander.

b) Briefing

The MDAD Public information Officer (PIO) or his/her appointed representative will be stationed in the press briefing or press assembly area and available information will be reported as follows:

1. In the event of an injury or fatality, the Airline PIO will be responsible for all press announcements reference the incident.
2. Develop and provide press releases relative to the airport's responsibilities and activities, as needed.

3. Interface with the media, as well as with air carrier and emergency response on-scene public relations personnel.
4. Participate in Airport EOC activities.

c) Vehicular Parking

Vehicles of press personnel may be parked in any of the regular term public parking lots where space is available. Heavy mobile radio and TV equipment will be directed to a press staging area to be determined by the MDAD PIO.

Private vehicles of press personnel will not be permitted to enter the AOA, nor will such be parked on airport roadways in such a manner as to restrict the movement of traffic in any way.

2. Aircraft Emergencies Beyond Airport Boundaries

The Aviation Department will cooperate when possible, to assist in news coverage, but will not be responsible for transportation and escort service to the scene as described above. A Press Briefing Room, to be designated by the Department may be activated to provide information in such instances.

1.4.4.7. Health and Medical Coordinator

The Miami-Dade County Health Department shall:

1. Send a representative to the scene and/or Airport EOC.
2. Coordinate with ICP and airline/operator in establishing and operating a temporary morgue.
3. Conduct necessary operations with airline/operator to identify injured or remains at site.
4. Coordinate with ICP in marking of locations of fatally injured.

1.4.4.8. Animal Care and Control Agency

The United States Department of Agriculture (USDA) Animal and Plant health Inspection Service (APHIS), when requested, shall:

1. Send a representative to the scene and/or Airport EOC.
2. Manage efforts to meet animal services needs, such as:
 - a) Rescue and capture of animals that have escaped confinement
 - b) Care of injured, sick, and stray; and disposal of dead animals
 - c) Activates emergency response teams, as needed
 - d) Prepares a resource list of organizations that are responsible for providing supplies needed to treat and care for injured and sick animals during large-scale emergencies and disasters.

1.4.4.9. Airside Operations

The Miami-Dade Aviation Department Airside Operations will liaise with and support the Incident Commander / Unified Command. Airside Operations, via Ramp One, will be the MDAD prime point of contact for the IC/UC.

1.4.5. Administration and Logistics

The management of administration and logistics in the event of emergencies is detailed in the Miami-Dade Aviation Department, Continuity of Operations Plan (COOP) revised annually.

1.4.6. Plan Development and Maintenance

Refer to section 1.3.

1.5. COMMUNICATIONS

1.5.1. Purpose

The communications systems in everyday use in operating the airport are the primary means for notifying agencies and persons having responsibilities that an emergency exists, its nature, and the actions that are required. It is incumbent upon the person in charge of each department, agency, or other activity, to make certain that each individual who may be involved in an emergency knows how to properly use communication equipment available to him/her and has pertinent phone numbers and call signs readily available. Copies of the Emergency Notification Chart⁶ are distributed to all air carriers and airport tenants for posting at strategic locations. It is also essential that persons who may use the communications systems be trained to avoid unnecessary use of those facilities so that there is minimum interference with either the task of responding to the emergency or normal operation of the airport.

General functions and responsibilities related to these functions, with respect to communications and controls are listed below. The person in charge of each entity shall perform the execution of these responsibilities at the time of the emergency. The responsibilities listed here are general in nature. Specific requirements will vary according to the situation and therefore additional detailed tasks are listed under the various types of emergencies in the following sections. Each entity shall be responsible for the recall of its own personnel, or request for additional help as may be necessary to accomplish the tasks assigned to it. Close coordination among all functions involved is of vital importance.

1.5.2. Situation and Assumptions

It is recognized that large-scale emergency operations usually require a communication capability beyond the normal capacities of the equipment of a typical airport. In addition, shared frequencies would be required for multi-agency communications. Dependent upon the areas, either on-airport or off-airport, there is a need to ensure communication capability is not diminished by:

1. Overwhelming cell network systems
2. Failure of the 800Mhz Radio System
3. Failure of the ATCT VHF 108 to 136 MHz Civil Aviation Band system for aircraft and NAVAID control.

⁶ Reference Exhibit 1A, Emergency Notification Chart

1.5.3. Operations

MDAD communication and applications systems are managed and maintained by its Information Systems/Telecommunication Division (IS/T). It is the responsibility of IS/T to provide the maximum level of uninterrupted Information Technology (IT) and Telecommunication services possible during major emergencies. Disaster recovery and related activities cover a wide and complex set of activities cover a wide and complex set of activities in an IT and Telecommunications environment.⁷

1.5.4. Organization and Assignment of Responsibilities

1.5.4.1. Miami-Dade Aviation Department

MDAD uses the 800MHz radio system for daily operations as do the rest of the County departments. The radios are equipped with emergency channels already programmed into the units and are activated by the Enterprise Technology Service Department (ETSD) at the time of the emergency. Police, Fire, and other County departments will all be able to communicate with each other utilizing this system.

The MDAD IS/T Technical Shop supplies the ICP with spare 800MHz radios (maximum of 100 units). In the unlikely event that the 800MHz system is damaged, MDAD will still be able to use the radios in “Local” mode. This mode will be transparent to most users, and the radios will only transmit/receive around the airport vicinity (not County-Wide). In the unlikely event that the 800MHz system is totally inoperative, the IS/T Technical Shop will deploy 400MHz radios to the ICP (maximum of 100 units).

1.5.4.2. Miami-Dade Fire Rescue, Aviation Division

The Miami-Dade Fire Rescue, Airport Division is an entity of Miami-Dade County. Support for communications of this Division is provided by the County. If communication is lost, the following resources are available:

1. Additional satellite phones and radios
2. Two Mobile Command Posts, with Satellite Communication equipment
3. Mobile repeater antennas,
4. Special communication mobile equipment with cell phone and satellite capabilities

If catastrophic failure of the County system of communication occurs, agreements with adjacent cities provide the use of their 800MHz radio systems.

⁷ Section 8, Interoperable Data / Communications, MDAD Continuity of Operations Plan (COOP), revised annually.

1.5.4.3. Miami-Dade Police Department, Airport District

The Miami-Dade Police Department, Airport District, is an entity of Miami-Dade County. Support for communications of this Division is provided by the County. Communication resources are listed in paragraph 1.4.4.2 (1-4).

1.5.5. Administration and Logistics

Administration and Logistics for the Communications section of this manual is detailed in the MDAD Continuity of Operations Plan (COOP), revised annually.

1.5.6. Plan Development and Maintenance

Refer to section 1.3.

1.5.7. Authorities and References

1. AC 150/5200-31, Airport Emergency Plan
2. Continuity of Operations (COOP) Plan
3. Miami-Dade County Communications SOPs

1.6. ALERT NOTIFICATION AND WARNING

1.6.1. Purpose

This section provides information which identifies the methods and sequences to be used in notifying all appropriate airport personnel of an emergency situation on, or in the vicinity of the airport. It details the various alert and warning systems and equipment available at the airport, how and under what conditions they are to be used, and who is responsible for them.

1.6.2. Situation and Assumptions

Due to MIA's diversity of international traffic, the following are conditions considered in developing system design and utilization:

1. The possibility that certain passengers would ignore or not understand the alert and warning signal
2. Special needs groups such as people with sight, hearing, mobility impairments, or unaccompanied children, requiring specific assistance
3. Fire, police, or other airport personnel, or outside agencies may be called upon to assist in the alert and warning process
4. Activation of the Mass Notification System by the Miami-Dade County Department of Emergency Management & Homeland Security

1.6.3. Operations

The MDAD Airport Operations Center (AOC) is a 24-hour, multi-function operation that is critical to MDAD's response to emergencies. In the event an emergency occurs, the AOC initiates the activation of the Incident Notification Call List (INCL) which contains the key and essential personnel and organizations to be contacted for various emergencies. In the event the AOC is disabled, the critical operations may be replicated at Maintenance and Engineering, building #3030, for long term operation.

Notification is made through a system consisting of:

1. Public address announcements for passenger terminal evacuations
2. Crash Phone for aircraft emergencies (from ATCT)
3. Fire Alarms for any structural fires
4. Pagers and phones for key personnel notification
5. Radios for daily operations
6. NOTAMS for change in airfield or NAVAID conditions

1.6.4. Organization and Assignment of Responsibilities

Activation of the INCL is automatic for certain emergencies and notifications received through Drop Down speakers from ATCT. Additional activation of the call list is made by the responding Incident Commanders, or Federal Agencies.

1.6.4.1. Miami-Dade Fire Rescue, Aviation Division

Miami-Dade Fire Rescue personnel will be dispatched by the Miami-Dade County Fire Alarm Office, through notifications received via 911, by direct phone call or via the Tower Emergency Telephone lines initiated by the ATCT to the Miami-Dade Fire Rescue Watch Office. One for Medical Emergencies (medical line) and one line for aircraft emergencies (Crash Phone).

1.6.4.2. Miami Air Traffic Control Tower (ATCT)

Normally, the MIA FAA ATCT will be the first to be aware of aircraft incidents and accidents and will institute the alert procedure outlined below. Such procedures are established by Letter of Agreement between Miami ATC Tower and Miami-Dade Aviation Department, titled "Emergency Procedures", a copy of which is included in Section 14, "Control Tower Functions". Such guidelines are also found in the FAA Aeronautics Information Manual, Official Guide to Basic Flight Information and ATC Procedures⁸

1.6.5. Administration and Logistics

Administration and logistics for the Alert Notification and Warning section of this manual is detailed in the MIA Emergency Evacuation Plan and through each Agencies SOP.

1.6.6. Plan Development and Maintenance

Refer to section 1.3.

1.6.7. Authorities and References

1. MIA Emergency Evacuation Plan
2. Continuity of Operations (COOP) Plan
3. AC 150/5200-31, Airport Emergency Plan
4. LOA Miami ATC Tower and Miami-Dade Aviation Department, Emergency Procedures, Exhibit 14A

⁸ See section 2.8.1. Organization and Assignment of Responsibilities for ATCT

1.7. EMERGENCY PUBLIC INFORMATION (EPI)

1.7.1. Purpose

This functional section describes the means, organization, and processes by which MIA provides timely, accurate, and useful information and instructions throughout an emergency.

1.7.2. Situation and Assumptions

This section describes the overall Emergency Public Information function for MIA. It considers response to all hazards listed in this AEP and assumes the following:

1. Each hazard's effect upon the general public either on-airport or off-airport
2. Coverage
3. Vulnerability of dissemination due to communications failure or natural hazards
4. Accessibility to special needs groups
5. Limited time between incident to notification and its effect
6. Message content and ongoing development updates

1.7.3. Operations

The Miami-Dade Public Affairs Division is responsible for media related notifications. Determination for response is determined by the MDAD Media Relations Manager or by direction of the Aviation Director or his/her designates.

1.7.4. Organization and Assignment of Responsibilities

In the event of an injury or fatality, the Airline PIO will be responsible for all press announcements reference the incident. The MDAD Public Affairs Division is responsible for:

1. Coordinating press/media briefings as needed to update the community on the nature of the incident and effects
2. Develop and provide press releases relative to the airport's responsibilities and activities, as needed.
3. Ensuring control of the media by providing and coordinating staging areas
4. Interface with the media, as well as with air carrier and emergency response on-scene public relations personnel.
5. Participate in Airport EOC / Joint Information Center (JIC) activities.

A Family Room has been created for the use of families of victims of aircraft accidents. This room can be activated if necessary by the Airport EOC in coordination with the IC. The Family Room will not be set up adjacent to the Airport EOC or near the Press room⁹.

⁹ Reference section 1.4.3.3., Family Room

1.7.4.1. MDAD Aviation Director / Deputy Director / Assistant Director of Operations

1. Serves as the primary spokesperson before media, or delegates the function to the MDAD PIO
2. Serves as the final approval authority to release emergency instructions and information, or delegates function to MDAD PIO
3. In cases where Incident Command has been established, provides policy guidance on the transfer of authority to release information from the Incident Command post to the Airport EOC

1.7.4.2. MDAD Media Relations Manager

1. Designates location for media briefings in coordination with the IC
2. Approves implementation of any special provisions for media convergence
3. Manages all aspects of EPI on behalf of the MDAD Aviation Director
4. Assumes EPI functions delegated by the Airport Manager
5. Ensures timely preparation of EPI materials and their dissemination
6. Ensures timely and appropriate coordination with off-airport emergency public information personnel
7. Briefs public affairs officers who to the incident site
8. Schedules news conferences, interviews, and other media access
9. Supervises the media center
10. Assigns personnel to monitor all media reports for accuracy
11. Coordinates rumor control activity
12. Maintains a chronological record of emergency events

1.7.4.3. All Tasked Organizations

1. Provide information as requested by the MDAD PIO
2. Clear all emergency-related news releases with the MDAD PIO
3. Provide public affairs officers to support EPI activities, as requested by the MDAD PIO
4. Refer media inquiries to the PIO

1.7.5. Administration and Logistics

Administration of the flow for the EPI function shall be maintained by the MDAD Media Relations Manager. Reports of press coverage summaries and/or clips, public reaction and concerns, and final chronology of events shall be maintained and distributed by the MDAD Public Affairs Division.

Facilities and equipment is determined by the location of the emergency or incident. Miami-Dade County Fire Rescue or Miami-Dade County Police Department mobile JIC will be utilized as the primary media center if available. If none is available, the location for a media center will be determined by the MDAD Relations Manager.

1.7.6. Plan Development and Maintenance

Refer to section 1.3.

1.7.7. Authorities and References

1. MIA Emergency Evacuation Plan
2. Continuity of Operations (COOP) Plan
3. AC 150/5200-31, Airport Emergency Plan
4. MDAD Policies and Procedures
5. MDAD Airport Emergency Plan

1.8. PROTECTIVE ACTIONS

1.8.1. Purpose

This section covers those events which may require a protective action involving the entire airport (hurricane or extensive hazardous materials) to those involving more local events (terminal building evacuation-fire/bomb incident, or a more localized hazardous materials).

1.8.2. Situation and Assumptions

The conditions requiring some type of protective action of MIA's permanent and transient population consist of:

1. Emergency conditions that could occur at the airport that may require implementation of protective actions
2. Areas on or near the airport that use, store, produce, or transport hazardous materials
3. Site-specific evacuation plans and maps
4. Provisions for the identification of population groups requiring special assistance
5. Probable operational situations under emergency conditions such as:
 - a) Hazards that provide sufficient warning time to implement a planned protective action for individuals effected
 - b) Responding organization's knowledge of all resources required to implement protective actions
 - c) Conditions where individuals will ignore the protective action recommendation, regardless of the threat
 - d) Designated hurricane evacuation routes

1.8.3. Operations

The factors considered when planning for protective actions include the characteristics of the hazard or the threat itself; magnitude, intensity, speed of onset, duration; and impact on the airport.

While, Miami International Airport (MIA) is not a shelter area for the general public or cruise passenger, it is to be expected that some travelers will be stranded at the airport and every attempt must be made by MDAD personnel to ensure their safety. Based on the Hurricane Advisory and/or by instructions from the Mayor or his designee, of an approaching Hurricane or emergency event, the appropriate precautionary measures are to be taken by all MDAD personnel, Airport occupants, tenants and airport contractors to:

1. Protect and properly secure their own property prior to and after a hurricane or emergency event
2. Ensure that materials/debris displaced or other created hazard from their area is promptly removed/corrected and does not endanger the life and property of others

Except during hurricanes, the decision to evacuate, either partially or completely, will be made by the responding Incident Commander. The decision to evacuate in preparation for a hurricane is made by the Assistant Aviation Director for Operations or his/her designee.

Decision to evacuate an aircraft will be the responsibility of the aircraft owner / operator.

1.8.4. Organization and Assignment of Responsibilities

1.8.4.1. Miami-Dade Police Department, Airport District

The Miami-Dade Police Department, along with MDAD Security shall:

1. Provide traffic control during evacuation operations
2. Provide security to evacuated / sheltered areas / facilities
3. Control access to evacuated / sheltered areas

1.8.4.2. MDAD Public Information Officer

The MDAD PIO shall:

1. Coordinate press/media briefings as needed to update the community on the status of airport
2. Develop and provide press releases relative to the airport's responsibilities and activities, as needed.

1.8.4.3. All Tasked Organizations

1. Make provisions to protect and secure facilities in the area(s) affected by the protective action
2. Identify and make provisions to relocate the organizational equipment and supplies that will be moved from an evacuated area
3. To the extent possible, will assist with evacuation of the general public.
4. Shall follow the MDAD Hurricane Manual and MIA Emergency Evacuation Plan SOPs as required

1.8.5. Administration and Logistics

Administration and logistics for the Protective Actions section of this manual is updated annually through the AEP review process

1.8.6. Plan Development and Maintenance

Refer to section 1.3.

1.8.7. Authorities and References

1. AC 150/5200-31, Airport Emergency Plan
2. MDAD Hurricane Manual, updated annually
3. MIA Emergency Evacuation Plan

1.9. LAW ENFORCEMENT/SECURITY

1.9.1. Purpose

This section provides information which identifies the methods used in mobilizing and managing law enforcement / security services in response to emergencies.

1.9.2. Situation and Assumptions

In accordance with 49 CFR Part 1542, law enforcement procedures are already defined in the Airport's TSA-approved Airport Security Program (ASP). The ASP includes law enforcement response and procedures which support the airport's security program and air carrier passenger screening activities. Situation and assumptions included in this section have been coordinated with the law enforcement procedures specified in the ASP.

This section includes limitations or situations which may impact law enforcement support. Assumptions made during an emergency include the following:

1. On-airport and off-airport law enforcement emergency response support organizations will be available to assist in accordance with established agreements, plans, and procedures
2. All responding law enforcement units will be familiar with their responsibilities
3. Large scale emergencies may require law enforcement support of mutual aid agencies
4. Bomb or hijacking emergencies require specialized law enforcement and other technical support such as Explosive Ordinance Disposal (EOD) or the FBI

1.9.3. Operations

The Miami-Dade Police Department, Airport District (MDPD) is a division of the Miami-Dade County Police Department and has mutual aid agreements with adjacent Cities for additional resources if required.

Policies, plans and procedures of the MDPD are detailed in the ASP. Additional procedures covering hazard specific responses are detailed in the Hazards section of this AEP.

The Airport District consists of one Major, one Captain, seven Lieutenants, 23 Sergeants, and 138 Officers. These units include:

1. The General Investigations Unit (GIU) which consists of two investigative squads and the Crime Analysis Unit (CAU) comprised of an Intelligence Analyst, two Crime Analysts, and a Police Officer.

2. The Specialized Projects Section which comprises of the Incident Containment Team (ICT) and the Explosive Detection Canine (EDIC) programs. The primary goal of the ICT is to enhance the overall safety and security of MIA, its employee's and the traveling public. The mission of the team is to provide the immediate response to a threat, actual terrorist, or major criminal event. The EDIC teams secure the airport against improvised explosive devices being carried on persons. EDIC teams work in direct coordination with the ICT and are trained to patrol and locate moving explosives within crowded terminals.
3. Motorcycle Unit which is responsible for facilitating the expeditious flow of traffic throughout MIA and the surrounding area. It conducts daily and specialized traffic enforcement operations within the District's geographic boundaries.
4. Explosive Detection Canine Teams which comprised of Transportation Security Agency trained explosive ordinance detection canine teams working 24 hours a day, seven days a week.
5. Civilian Staff

The Specialized Projects Section includes but is not limited to developing and coordinating training sessions to enhance the performance of the airport District's Officers. Along with the MDAD training programs, Officers are trained on Airfield Familiarization before being allowed to drive on the airfield. Airport grid maps are provided in each vehicle (see MIA Existing Airport Operations Map / Exhibit 327C / 1C).

The MDPD, Airport District, is responsible for the area which borders NW 36th Street to the North, the Miami River to the East which encompasses the Miami Intermodal Center and the area known as "the Triangle", South Perimeter Road to the South and NW 72nd Avenue to the West. (see Figure 1, Airport District 7 Boundaries)




Figure 1. Airport District 7 Boundaries

1.9.4. Organization and Assignment of Responsibilities

This section addresses the specific organizational structure and associated responsibilities that are assigned to law enforcement for each type of emergency. These procedures are detailed in the ASP and in the Hazard sections of this AEP.

In response to any emergency, the MDPD Major or his/her designee shall:

1. Designate an MDPD Liaison to report to the Airport EOC if activated
2. Designate an MDPD Liaison to report to the Incident Command Post (ICP)
3. Activate the MDPD Public Information Officer (PIO) if necessary
4. Establish airport policy regarding off-airport response by MDPD, Airport District units
5. Ensure availability of sufficient numbers of qualified and trained law enforcement / security personnel to sustain support around the clock.
6. Ensure compliance with all standards and regulations involving law enforcement, including those involving bomb situations, civil unrest, hazardous materials, and other related matters
7. Ensure availability and operability of all necessary emergency response equipment
8. Coordinate the response of multi-jurisdictional law enforcement response efforts on the airport
9. Designate staff to perform emergency duties

Any additional Organizations tasked to assist with mutual aid shall:

1. Adhere to all professional and legal standards in the performance of duties
2. Provide ongoing status reports to the Law Enforcement Coordinator
3. As needed, coordinate with other emergency services such as medical / EMS, fire, and public works
4. Refer all media requests for information to the Law Enforcement PIO, as appropriate
5. Maintain updated resource inventories of emergency supplies, equipment, and personnel resources, including possible sources of replacements
6. Designate staff to perform emergency duties
7. Prepare detail SOPs and checklists that include:
 - a) Contact information and mechanisms for notifying personnel
 - b) Step-by-step procedures for performing assigned tasks
 - c) Contact information for similar services in other jurisdictions, to include contact information for law enforcement resources (air, land, water)
 - d) Prepare a list of the radio communications call signs and frequencies used by responding organizations.

1.9.5. Administration and Logistics

Administration and logistics for the Law Enforcement / Security function of this manual is managed by the Miami-Dade Police Department, Airport District Division. All contact information for personnel is verified monthly.

The MDPD, Airport District, SOPs contain the following items:

1. Policies and procedure to test, maintain, repair and/or replace law enforcement support equipment
2. Recall of Essential Personnel policies and procedures to provide adequate law enforcement coverage.

1.9.6. Plan Development and Maintenance

Refer to section 1.3.

1.9.7. Authorities and References

1. AC 150/5200-31, Airport Emergency Plan
2. MIA Airport Security Plan
3. MDPD SOPs, and Rules & Regulations
4. Miami-Dade County Aviation Department Rules and Regulations, Chapter 25

1.10. FIREFIGHTING AND RESCUE

1.10.1. Purpose

This section provides information which identifies the methods used in mobilizing and managing fire and rescue services in response to emergencies. It includes:

1. A summary of the available personnel
2. The availability of fire fighting vehicles, agents and equipment
3. The location of personnel, vehicles, and support equipment
4. An overall statement of response and mitigation capabilities
5. The incident command structure
6. Outside resource / agency support

1.10.2. Situation and Assumptions

This section describes the overall ARFF situation at Miami International Airport, to include the certification elements of Title 14, CFR, Parts 139.315-319, which is provided in the Airport Certification Manual. The ARFF component of this airport provides support for emergencies involving aircraft, structures, hazardous material incidents, and emergency medical services. Typical assumptions include:

1. On-airport and off-airport fire and rescue emergency response support organizations will be available to assist in accordance with established agreements, plans, and procedures
2. All responding fire and rescue units will be familiar with their responsibilities
3. Large scale emergencies may require fire and rescue support of mutual aid agencies
4. Fire rescue services located at the airport and the communities it serves, may themselves be impacted by the disaster
5. The possibility of a wide area disaster where the airport fire and rescue services will be operating without the benefit of mutual aid support due to their commitment elsewhere

1.10.3. Operations

The Miami-Dade Fire Rescue, Aviation Division, is part of the Miami-Dade County Fire Rescue Department. It encompasses four major service areas, which include Airport Operations, Training and Safety, Fuel Safety Operations, and Aviation Life Safety (Life Safety Code Enforcement). The Division is responsible to both the Miami-Dade Fire Rescue Department and the Miami Dade Aviation Department and responds to adjacent communities on a Mutual Aid System.

The MDFR Aviation Division consists of 99 Firefighters, 32 Lieutenants, 9 Captains, 3 Aviation Battalion Chiefs, 2 Aviation Administrative Chiefs and 1 Aviation Division Chief, operating out of two Airfield Stations (Station 12 & Station 59). These two stations have all the equipment required to meet Index E requirements under Title 14, CFR, 139.317, Aircraft Rescue and Fire Fighting: Equipment and Agents (reference MIA ACM, Section 317-2 for list of equipment). All vehicles have VHF radios and airport grid maps.

In order to operate on the AOA, all Fire Rescue personnel are trained annually on operating in the airport movement area. Through the collaboration of the MDFR Aviation Division's Training and Safety Bureau and the MDAD Airside Operations Training Section, all Aviation Division uniformed personnel receive training in the following categories:

1. Airport Familiarization
2. Aircraft Familiarization
3. Fire Rescue Personnel Safety
4. Emergency Communications at the Airport
5. Use of fire hoses, nozzles, turrets and other appliances
6. Application of Extinguishing Agents
7. Emergency Aircraft Evacuation
8. Firefighting Operations
9. Adapting and using structural firefighting equipment of ARFF
10. Aircraft Cargo Hazards
11. Familiarization with the Airport Emergency Plan
12. Other training as specified in the Airport Certification Manual (Water Rescue, etc.)
13. Annual Live Fire ("Hot") drills

1.10.3.1. Mobilization

Aircraft Alert notifications are received from a direct line to the MDFR Watch Office from MIA ATCT. The Miami-Dade County Fire Alarm Office is the primary dispatch center for any other emergency.

The "Strategy for Alarm Assignment" Policy dictates what resources will be used on emergency response. If these resources are insufficient, through the ICS, additional resources will be dispatched until the County resources become depleted and then, mutual aid will be used.

1.10.3.2. Phases of Response

The common phases that provide for a systematic approach to planning include four separate but related actions. They are mitigation, preparedness, response, and recovery.

1.10.3.3. Incident Command System

The incident command structure will follow NIMS criteria (reference exhibit 1B). The Battalion Chief will assume the role of IC in the ICP but the first unit on the scene of an emergency will assume responsibility as the IC. For the purpose of communicating with ATCT, the Battalion Chief will be identified as "Fire Commander". Further detail is listed in each respective hazard section of this AEP.

1.10.4. Organization and Assignment of Responsibilities

The Aviation Division Chief shall:

1. Designate a representative from ARFF Management to report to the Airport EOC if activated
2. Become the Incident Commander for the ICP
3. Ensure availability of sufficient numbers of qualified and trained ARFF personnel IN ACCORDANCE WITH:
 - a) AC 150/5200-12, Fire Department Responsibility in Protecting Evidence at the Scene of an Aircraft Accident
 - b) AC 150/5210-7, Aircraft Rescue and Fire Fighting Communications
 - c) AC 150/5210-13, Water Rescue Plans, Facilities and Equipment
 - d) AC 150/5210-14, aircraft Rescue Fire Fighting Equipment, Tools and Clothing
 - e) AC 150/5210-17, Programs for Training of Aircraft Rescue and fire-fighting Personnel
 - f) AC 150/5220-4, Water Supply Systems for Aircraft Fire and Rescue Protection
4. Ensure compliance with all standards and regulations involving fire and rescue response which may include hazardous materials
5. Ensure availability and operability of ARFF equipment as required by 14 CFR part 139
6. Coordinate the response of multi-jurisdictional fire and rescue response efforts on the airport
7. Provide information regarding the fire and rescue response effort through and to the Public Information Officer (PIO) for release to the news media if required
8. Ensure emergency fire and rescue response information is provided to the Airport EOC, as appropriate

All tasked organizations shall:

1. Adhere to all professional and legal standards in the performance of duties
2. Provide ongoing status reports to the Fire and Rescue representative
3. As needed, coordinate with other emergency services
4. Refers all media requests for information to the MDFR PIO, as appropriate
5. Designates staff to perform emergency duties

1.10.5. Administration and Logistics

This section addresses the administrative and general support requirements associated with ARFF. All contact information for personnel to be notified of an emergency situation is listed in Appendix A, Emergency Telephone List, and is to be utilized in accordance with the Emergency Notification Chart¹⁰. The Emergency Telephone List is maintained by MDAD Terminal Operations and is updated quarterly.

1.10.6. Plan Development and Maintenance

Refer to section 1.3.

1.10.7. Authorities and References

1. Policies & Procedures III-E-51, Strategy for Alarm Assignments
2. Policies & Procedures Airport Orientation Manual
3. AC 150/5200-31C, Airport Emergency Plan
4. AC 150/5200-12, Fire Department Responsibility in Protecting Evidence at the Scene of an Aircraft Accident
5. AC 150/5210-7, Aircraft Rescue and Fire Fighting Communications
6. AC 150/5210-13, Water Rescue Plans, Facilities and Equipment
7. AC 150/5210-14, aircraft Rescue Fire Fighting Equipment, Tools and Clothing
8. AC 150/5210-17, Programs for Training of Aircraft Rescue and firefighting Personnel
9. AC 150/5220-4, Water Supply Systems for Aircraft Fire and Rescue Protection
10. Title 14, CFR, Parts 139.315-319

1.11. HEALTH AND MEDICAL

1.11.1. Purpose

This section provides information which identifies the methods used in mobilizing and managing health and medical services in response to emergencies occurring on airport property.

1.11.2. Situation and Assumptions

This section addresses large scale emergency and disaster events that could overwhelm local medical and mortuary services. Focus is on the airport's capability to provide medical care, treatment, and transportation. Support to victims, response personnel, and the general public during the emergency response and recover phases are also taken into consideration. The following assumptions are established:

1. Maximum coordination and efficient use of off-airport medical resources
2. Public and private medical, health, and mortuary services resources located at the airport and the communities it serves, will be available
3. Large-scale emergencies and disaster threat situations

¹⁰ Reference Exhibit 1A, Emergency Notification Chart

4. Public and private health and medical resources, including human resources, located at the airport and communities it serves may themselves be impacted by the disaster
5. Emergency services to protect life and health during the first 12 to 24 hours after the disaster will probably be exclusively dependent on local and area resources
6. Suspected communicable diseases
7. The introduction of volunteer assistance needs to be anticipated and coordinated

1.11.3. Operations

This section provides general information on the process of delivering health and medical operations and how those efforts will be coordinated with those of off-airport medical organizations. The main focus of this section is response to mass or multiple casualty incidents (MCIs). The Miami-Dade Fire Rescue, Aviation Division, is a section of the Miami-Dade County Fire Rescue Department and will be the lead agency for on-airport incidents.

To efficiently triage, treat, and transport victims of (MCIs), the following procedures shall be followed in accordance with all Miami-Dade County Fire Department Policies and Procedures. In order to manage personnel and resources, and to provide for the safety and welfare of personnel, the MDRF operates within the National Incident Management System (NIMS) Incident Command System (ICS) as mandated by Homeland Security Presidential Directive (HSPD) - 5. This guideline identifies the procedures to be employed in establishing and maintaining command and the components of the ICS.

The following levels of response are considered the minimum amount required to manage a specific number of patients:

1. MCI Level 1 Response (5-10 victims)
 - 4 ALS Transport Rescues
 - 2 Suppression units
 - 2 Ambulances
 - 1 Battalion Chief
 - 1 EMS Captain
2. MCI Level 2 Response (11-20 victims)
 - 5 ALS Transport Rescues
 - 2 Suppression units
 - 3 Ambulances
 - 2 Battalion Chief
 - 2 EMS Captains
 - EMS Officer in Charge (OIC) notification

3. MCI Level 3 Response (21-100 victims)
 - 6 ALS Transport Rescues
 - 3 Suppression units
 - 4 Ambulances
 - 3 Battalion Chiefs
 - 3 EMS Captains
 - EMS OIC notification
 - EMS Division Chief notification
4. MCI Level 4 Response (101-1000 victims)
 - Initial MCI Level 3 Response
 - Command will augment additional responses as needed
5. MCI Level 5 Response (1000+ victims)
 - Initial MCI Level 3 Response
 - Command will augment additional responses as needed

The Miami-Dade County Fire Alarm Office (FAO) will dispatch the appropriate units for a declared Level 1 through 5 MCI. Mobilization and dispatch of all MDFR personnel and equipment shall follow Policies and Procedures, III-E-51 Strategy for Alarm Assignments.

Initial notification of on-airport aircraft accidents is made by MIA ATCT and is detailed in section 2.8.1. Organization and Assignment of Responsibilities for ATCT. All MIA ARFF personnel are Paramedic or EMT certified, they are strategically staged at one of two on-field Fire Stations with the following equipment:

- 4 Foam Vehicles
- 1 Engine
- 1 Aerial Platform Vehicle (Hazmat Response Unit)
- 1 Quick Response Vehicle (QRV)
- 1 Rescue Vehicle
- 1 Rigid Hull Inflatable Boat (RHIB)
- 1 MCI Trailer containing emergency supplies for the treatment of 250 seriously injured victims.
- 1 Battalion Vehicle

Additional aviation support equipment is stationed at Opa-Locka Airport (OPF) located 10 miles north and Miami Executive Airport (TMB) located 15 miles Southwest of MIA. Responding drivers from either of these stations are MIA movement area qualified.

Access to the staging area for off-airport County and mutual aid support is available through six rendezvous points throughout the airport. The ARFF IC will determine which point will be used based on the closest access point to the incident. MDAD Operations personnel and/or emergency vehicles shall escort support vehicles authorized to enter the airport through these points. Section 1.4.3.4. of this Airport

Emergency Plan details all actions related to the operation of the Rendezvous Points and Exhibit 2A displays their locations throughout the airfield.

Mutual Aid is a vital component of Miami-Dade County's emergency plan, which provides a process for rendering/receiving mutual aid to/from participating Fire Rescue Departments(s) whenever the need arises. This accord to prevent, combat, or mitigate any type of disaster or emergency is obtained through mutual aid agreements among participating Municipal, County, State, and Federal Members. Guidelines for mutual aid are listed in MDFR Policy & Procedure III-N-5, Mutual Aid.

The Disaster Medical Assistance Team FL5 is a regional team committed to respond to both natural and man-made medical disasters and is under the jurisdiction of the National Disaster Medical System (NDMS). A full deployed DMAT is a group of 35 physicians, nurses, and allied health professionals supported by a cadre of logistical and administrative staff. The DMAT team is deployed by either the federal or state government via request from the Department of Health and Human Services, or the Florida State Response Team (SERT).

The Disaster Mortuary Operational Response Team (DMORT) is a Federal Level Response team designed to provide mortuary assistance in the case of a mass fatality incident. They work under the local jurisdictional authorities such as Coroner/Medical examiners, Law Enforcement, and Emergency Managers.

Activation of the hospital emergency alert is initiated through the FAO or the Director of the Miami-Dade Police Department on the Dade County communications network. The Hospital Capabilities Chart, Table 1, provides the names of all Miami-Dade County and South Broward County along with their capabilities and will be utilized in determining trauma victim destinations. The EMS Task Force will coordinate dispatch from the designated triage staging areas of the incident.

Airport Emergency Plan INTRODUCTION & CORE FUNCTIONS

MIAMI-DADE COUNTY FACILITIES

FACILITY	GENERAL		OB	PSYCH	TRAUMA CENTER				STROKE CENTER	STEMI CENTER	HAZMAT RADIOLOG	HYPER-BARIC	HELI PORT	MCI		
	ADULT	PEDI			ADULT	PEDI	BURN	SPINAL CORD						RED	YELLOW	GREEN
Aventura	YES			YES	YES				CSC	YES	HAZ		YES	12	15	20
Baptist	YES	YES	GEN/HR						CSC	YES	HAZ/RAD		YES	5	15	50
Baptist West	YES		GEN/HR						PSC		HAZ/RAD			5	8	13
Doctors	YES	YES									HAZ/RAD			4	6	10
Hialeah	YES		GEN						PSC					2	4	6
Homestead	YES	YES	GEN/HR	YES							HAZ/RAD		YES	3	5	8
Jackson West Medical Center	YES	YES									HAZ/RAD			4	6	10
JMH North	YES	YES	GEN/HR						PSC	YES	HAZ/RAD			5	10	15
JMH South	YES		GEN	YES	YES				PSC	YES	HAZ		YES	10	15	25
JMH/Ryder	YES	YES	GEN/HR	YES	YES	YES	YES	YES	CSC	YES	HAZ/RAD		YES	30	78	200
Kendall	YES	YES	GEN/HR	YES	YES	YES	YES		CSC	YES	HAZ/RAD		YES	5	15	20
Kendall- Doral FSED	YES	YES		YES							HAZ/RAD			0	1	15
Kendall- Town & Country FSED	YES	YES		YES							HAZ/RAD			0	1	15
Larkin	YES			YES										0	11	0
Larkin-Palm Springs	YES								PSC		HAZ/RAD			10	15	25
Mercy	YES		GEN	YES					PSC	YES	HAZ/RAD	YES	YES	2	5	7
Mount Sinai	YES	YES	GEN/HR	YES					CSC	YES	HAZ/RAD		YES	8	15	20
Mount Sinai- Aventura FSED	YES	YES		YES							HAZ/RAD			4	4	10
Mount Sinai- Hialeah FSED	YES	YES		YES							HAZ/RAD			0	10	10
Nicklaus Children		YES		YES		YES					HAZ/RAD		YES	6	15	15
North Shore	YES	YES	GEN/HR	YES					CSC	YES	HAZ/RAD			3	4	5
South Miami	YES		GEN/HR						PSC	YES	HAZ/RAD			18	27	45
Steward Coral Gables	YES								PSC		HAZ/RAD			5	10	15
Steward Coral Gables- Bird Road FSED	YES										HAZ/RAD			2	3	25
Steward Palmetto General	YES	YES	GEN/HR	YES					CSC	YES	HAZ/RAD		YES	8	20	25
UM	YES	YES							PSC	YES	HAZ/RAD		YES	5	10	30
Veterans	YES			YES					PSC					4	4	4

SOUTH BROWARD FACILITIES

Cleveland Clinic	YES	YES		YES					CSC	YES	HAZ/RAD			6	9	16
Memorial Miramar	YES	YES	GEN/HR								HAZ			2	5	8
Memorial Pembroke	YES	YES							PSC					5	10	15
Memorial Regional	YES	YES	GEN/HR	YES	YES	YES		YES	CSC	YES	HAZ/RAD		YES	10	20	20
Memorial South	YES			YES							HAZ/RAD			0	10	20
Memorial West	YES	YES	GEN/HR						CSC	YES	HAZ/RAD		YES	5	10	15

Revision Date: September 21, 2021

Blank Space = Service not Provided
 BURN = Burn Unit Center
 CSC = Comprehensive Stroke Center
 FSED= Free Standing Emergency Department
 GEN = General OB > 20 wks Gestation
 HAZ = HAZMAT Capable
 HR = High Risk OB > 20 wks Gestation
 MCI= Mass Casualty Incidents Red/Yellow/Green
 PSC = Primary Stroke Center
 RAD = Radioactive Capable
 SPINAL CORD = Brain and Spinal Cord Acute Care Center
 STEMI = ST Elevation Myocardial Infarction

Note: If MERCY is off line for hyperbaric, St. Mary Hospital, West Palm Beach or Mariners Hospital, Tavernier can be used.



Table 1. Hospital Capabilities Chart

1.11.4. Organization and Assignment of Responsibilities

This section describes the responsibilities of those individuals and organizations tasked with providing emergency health and medical services at the airport. Triage, treatment, and transport procedures are detailed in the Miami-Dade Fire Rescue response procedures.

1.11.5. Aircraft Medical Emergencies

The information contained in this subsection defines responsibilities and describes actions to be taken in the event an aircraft has a medical emergency. It is intended to enable the flow of accurate and timely information to Aircraft Rescue and Fire Fighting (ARFF) responders regarding disposition of ill or injured people onboard aircraft and to gain immediate access to the aircraft for the purpose of diagnosis and treatment. All ARFF responders shall follow the MDFR Policy & Procedure, III-F-13, Infectious Control Plan. Upon notification from the MIA ATCT reference medical emergency onboard aircraft, either at or en route to MIA, the following policy shall be followed:

1.11.5.1. Miami-Dade Fire Rescue, Aviation Division

If deemed necessary by ARFF personnel, MIA Tower or the Pilot-in-Command, the MIA Tower will make available frequency 120.35 for direct communication between the pilot-in-command and ARFF personnel.

1. ARFF Incident Commander will advise CDC if necessary.
2. Flight crews at MIA with onboard medical emergencies will keep passengers seated until ARFF or CDC responders have arrived on scene.
3. The aircraft loading bridge shall not be placed upon the aircraft until ARFF or CDC personnel arrive.

1.11.5.2. Miami-Dade Aviation Department

1. In the event of suspected communicable disease, the MIA Communicable Disease Plan will be implemented.
2. MDAD Operations personnel will stand-by at the parking gate to ensure that the aircraft can proceed as expeditiously as possible to parking and to assist the Incident Commander as needed.

1.11.6. MDFR Medical Operations Manual (MOM), Mass Casualty Incidents (MCI)

The following is a synopsis of Procedure 34 of the MOM when dealing with Mass Casualty Incidents.

1.11.6.1. Initial Response Procedures

The first arriving unit's OIC shall:

1. Establish Command
2. Performs a size up as follows:
 - a) Estimates the number of victims.
 - b) Requests the appropriate MCI level response.
 - c) Requests additional units as needed.
3. Identifies a staging area that will permit an orderly flow in and out without congestion.
4. Assumes control of Triage and shall:
 - a) Direct remaining crewmembers to initiate triage
 - b) Directs the walking wounded to a place away from the incident (triage of these persons shall be as soon as manpower permits).

5. As additional units arrive, Command will designate Group Leaders and assign personnel to the following areas:
 - a) Triage
 - b) Treatment
 - c) Transport
6. Assign additional functional groups depending on the complexity of the incident. These may include but are not limited to:
 - a) Staging
 - b) Landing Zone
 - c) Extrication
 - d) Hazmat
 - e) Rehabilitation
 - f) Manpower
 - g) PIO

1.11.6.2. Command

The IC shall use the radio designation “COMMAND” and follow the appropriate Field Operational Guide (FOG). The IC shall:

1. Perform the initial size-up as well as an ongoing evaluation of changing conditions.
2. Request the appropriate level of response and augment as necessary.
3. Maintain a visible presence, stay in a fixed location.
4. Control resources and Coordinate with Group Leaders to provide frequent updates of manpower and equipment needs and tracking of patients

1.11.6.3. Triage Group Leader

The Triage Group Leader shall use the radio designation “TRIAGE” and follow the appropriate FOG. The Triage Group Leader shall:

1. Organize the Triage personnel to begin the initial triaging of victims using color ribbons
2. Advise COMMAND of the total number and category of victims
3. Coordinate with TREATMENT to ensure that priority victims are moved the treatment area.
4. Ensure all areas around the scene have been checked for potential victims, walking wounded, ejected victims etc., and that all victims have been triaged.
5. Report to “COMMAND” upon completion of their duties for further assignments.

1.11.6.4. Treatment Group Leader

The Treatment Group Leader shall use the radio designation “TREATMENT” and follow the appropriate FOG. The Treatment Group Leader shall:

1. Maintain a “Treatment Log” by assigning a “Documentation Aide” to assist with the log.
2. Direct personnel to either begin treatment on the victims where they lie or at a centralized treatment area

3. Ensure that all victims are re-triaged through a secondary exam and the assessment is documented on the Triage Tag.
4. Personnel assigned to the Treatment Area that physically assess and/or treat a patient will document pertinent information on the Triage Tag, affix the tag on the patient in a visible location and remove the ribbon.
5. Ensure that adequate equipment and personnel are available to effectively treat the victims.
6. Communicate with TRANSPORT to coordinate proper transport of the appropriate patients.

1.11.6.5. Transport Group Leader

The Transport Group Leader shall use the radio designation “TRANSPORT” and follow the appropriate FOG. The Transport Group Leader shall:

1. Maintain a “Transport Log” and obtain a “Documentation Aide” with a second radio to assist with the log and communications.
2. Retain the “Transport” section of the Triage Tag.
3. Establish continuous contact with FAO and advise them to begin a “Tally” of hospitals close the affected area
4. Coordinate the transport of all victims from the treatment area(s)
5. Communicate with the LZ Group of the number of patients to be transported by air.
6. When units are prepared to transport, TRANSPORT (or their Aide) will contact MedCom and supply them with the following information:
 - a) The transporting unit number
 - b) The number of patients going to a specific facility, and
 - c) The patient’s priority (RED, YELLOW, or GREEN)
 - d) If any GREEN patients are immobilized on backboards, the receiving facility must be notified.
7. Once the FAO receives the information from TRANSPORT, they will notify the appropriate hospital and then update the “Hospital Capability Sheet”.

1.11.6.6. Staging Group Leader

The Staging Group Leader shall use the radio designation “STAGING” and follow the appropriate FOG. The Staging Group Leader shall:

1. Maintain a “Unit Staging Log”
2. Ensure that all personnel stay with their vehicles unless otherwise directed
3. Determine from TRANSPORT a location for loading BLS and ALS patients
4. Maintain a reserve of at least 1 BLS and 1 ALS transport vehicles. When the reserve is depleted, advise COMMAND.

1.11.6.7. MDFR Fire Alarm Office (FAO)

Once notified of an MCI, shall begin a tally to determine hospital capabilities and capacities.

The following guidelines will be followed unless otherwise directed by COMMAND or TRANSPORT:

1. If a Level 1 MCI is declared, notify the 2 closest hospitals and the Ryder Trauma Center
2. If a Level 2 MCI is declared, notify the 3 closest hospitals and the 2 closest Trauma Centers.
3. If a Level 3 MCI is declared, notify the 4 closest hospitals and the 3 closest Trauma Centers.
4. If a Level 4 or Level 5 MCI is declared, notify ALL hospitals AND all Trauma Centers.

The hospital will be advised of the total potential victims involved based on the level and of the nature of the incident, i.e. aircraft crash, chemical exposure etc.

Once a TRANSPORT Group is established, FAO will pass on the amount and type of patients that can be handled by each hospital as indicated on the "Hospital Capabilities Chart" "MCI" section. This information will be maintained and updated for the duration of the incident.

FAO will advise the receiving facility to keep the Triage Tag with the patient(s) for future documentation.

1.11.7. Administration and Logistics

This section describes administrative and general support requirements for accomplishing emergency health and medical tasks.

1.11.8. Plan Development and Maintenance

Refer to section 1.3.

1.11.9. Authorities and References

1. FAA AC 150/5200-31, Airport Emergency Plan
2. Policies and Procedures III-E-51, Strategy for Alarm Assignments
3. Miami-Dade Fire Rescue Medical Operations Manual (MOM), Procedure 34, Multiple Casualty Incidents
4. Florida Field Operations Guide (FOG)

1.12. RESOURCE MANAGEMENT

1.12.1. Purpose

This resource management section describes the processes by which an airport will identify requirements, expeditiously locate, acquire, allocate and distribute those resources to satisfy needs that are generated by an emergency.

1.12.2. Situation and Assumptions

This section describes the planning environment for the resource management function. These factors directly impact the ability of the airport to satisfy resource demand and manage support activities during response and recovery operations. The potential for emergencies which will require activation of the resource management function considers the following:

1. Potential critical resource shortages (e.g., power, potable water, fire fighting agents, portable equipment)
2. Scenarios that could deplete responding agencies' resources
3. Possible effects on the transportation infrastructure (e.g., restricted airport access, highways, etc.
4. Access to personnel (including skilled labor, task specialists and professionals)
5. Access to communications equipment
6. Vehicles for passengers (injured and non-injured, cargo, and debris removal (e.g., dump trucks, flatbeds, lowboys, buses, mini-vans)
7. Heavy equipment for public works applications (e.g., cranes, road graders, front-end loaders, bobcats, forklifts, mechanical and manual dollies, etc.
8. Portable pumps and hoses
9. Post incident recovery materials and tools such as fuel, sand and sandbags, plastic sheeting, plywood, lumber, shovels picks, chainsaws, etc.
10. Mass care supplies such as first aid supplies, potable water, blankets, sanitation services, and supplies, lighting, etc.
11. The ability for response agencies to sustain themselves during the first 24 hours of an emergency
12. Access to mutual aid.

1.12.3. Operations

In the event of an emergency requiring resource management, priority for emergency victims takes precedence in the allocation of the airport's resources. Secondary resource allocation will be determined at the direction of the IC or as follows:

1. Rescue and lifesaving of persons involved
2. Safety of persons and equipment not directly involved
3. Protection of wreckage from disturbance for later investigation by proper authorities
4. Keeping the unaffected areas of the airport in an operational condition
5. Returning the airport to normal operating status as soon as possible
6. Removal of disabled aircraft and contents
7. Salvage of cargo and equipment

The MDAD Assistant Director, Facilities Maintenance & Engineering, is the designated Resource Manager and is notified through the MDAD Emergency Contact List. In any after hour emergencies, the on-duty MDAD Maintenance One unit will initially liaison with the logistics section of the ICP. The airport will exhaust its own resources before requesting resources from within the County.

The Resource Manager or his/her designee will direct /address four basic concerns of the emergency:

1. Determining needs
2. Obtaining the resources
3. Distributing the resources
4. Maintaining financial and legal accountability

If mutual aid is required, additional support equipment will be obtained from County departments and / or outside vendors, through Memorandum of Understanding (MOU) previously set in place.

1.12.4. Organization and Assignment of Responsibilities

The Resource Manager, upon arrival at the ICP, shall:

1. Direct and supervise the activities of all maintenance resources
2. Coordinate with the IC and Staff regarding needs and priorities
3. Monitor potential resource shortages at the airport and will implement plan to address issue with IC and Staff
4. Identify locations that may be used for storage of resources if needed
5. Manage all needs, supplies, and distribution in accordance with the MDAD COOP Plan.

1.12.5. Administration and Logistics

The Miami-Dade Aviation Department Continuity of Operations Plan (COOP) establishes a framework for MDAD to prepare for, respond to, mitigate the impacts of, and recover from emergencies. The plan incorporates Resource Management, to include:

1. Reports and Records
2. Financial policies
3. Policies on emergency procurement
4. Staffing
5. Augmentation of equipment
6. Staging and storage
7. Communications
8. Transportation

MIA is a major complex with self-sustaining facilities and operations. As such, most events requiring activation of the COOP may be managed within the extensive on-site facilities. Initial assessments will be reviewed to determine the extent of facility damage and operational disruption. Barring major catastrophic events that incapacitate the basic infrastructure rendering the airport untenable, most events may be managed by restructuring existing facilities and making operational adjustments.

1.12.6. Plan Development and Maintenance

Refer to section 1.3.

1.12.7. Authorities and References

1. FAA AC 150/5200-31, Airport Emergency Plan
2. Miami-Dade Aviation Department Continuity of Operations Plan (COOP)

1.13. AIRPORT OPERATIONS AND MAINTENANCE

1.13.1. Purpose

This section provides information which identifies the roles and responsibilities of operations and maintenance personnel during an airport emergency. It includes a summary of:

1. Personnel and equipment
2. Where they are located
3. General notification procedures
4. Overall statement of capabilities

1.13.2. Situation and Assumptions

This section describes the overall Operations and Maintenance situation at the airport. This includes the staffing and general schedules and manning levels and limitations or situations which may impact operations and maintenance support during emergencies. Some of the typical assumptions that are made include:

1. All responding operations and maintenance personnel will be familiar with their responsibilities
2. Airport operations and/or maintenance personnel may be the first to respond to many airport emergencies
3. Airport operations personnel may have to represent airport management during the initial stages of some emergencies
4. Operations and/or maintenance functions may not be covered 24-hours a day, 7 days a week

1.13.3. Operations

Operations personnel respond to all emergency events on the airfield while Maintenance personnel may standby, ready to respond to requests for assistance if required. Operations personnel are trained to make initial determinations to protect areas considered unsafe through closure and issuance of NOTAM(s) if required.

The closure of the airfield to safely accommodate the movement of emergency response vehicles is an automatic function in the case of an Alert III declaration. In cases of other types of emergencies, Ramp One will determine the need for closures of the areas affected.

1.13.4. Organization and Assignment of Responsibilities

This section describes the specific organizational structure and associated responsibilities that are assigned to airport operations and maintenance personnel for each type of emergency.

1.13.4.1. MDAD Aviation Director / Deputy Director / Assistant Director of Operations

1. Designates representative to report to Airport EOC when appropriate
2. Establishes the MDAD Airport EOC when appropriate
3. Establishes the Family Room¹¹
4. Establishes airport policy regarding off-airport response by airport operations and maintenance personnel and equipment

1.13.4.2. MDAD Division Director, Airside Operations

1. Ensure compliance with all appropriate aviation standards and regulations
2. Coordinate emergency response efforts with air traffic control personnel
3. Ensure any and all required NOTAMS have been issued
4. Provide overall airport familiarization and training program for designated on and off-airport maintenance personnel
 - a) Provide training to reduce the potential for Vehicle/Pedestrian Deviations (V/PD) and Runway Incursion
 - b) Provide grid maps for each vehicle, as appropriate
5. Ensure completion of necessary airport inspections upon emergency termination
6. Prepare detailed SOPs and checklists that include:
 - a) Contact information and mechanisms for notifying personnel
 - b) Step-by-step procedures for performing assigned tasks
 - c) Contact information for agency notification (e.g. air traffic control, FAA, NTSB, etc.)
 - d) Listing of the radio communications call signs and frequencies used by responding organizations
 - e) Provide means (e.g. buses), to evacuate people from the accident scene
7. Provide information regarding the status of the airport to the news media through the Public Information Officer (PIO)
8. Maintain a chronological event log

1.13.4.3. MDAD Maintenance Operations

1. Prepares and maintains an airport resource list
2. Ensures the restoration of utilities to critical and essential facilities, when necessary
3. Ensures the safety of facilities (e.g. post-fire, flood, earthquake, tornado, hurricane, explosion)
4. Provides backup electrical power
5. Clears debris, as necessary
6. Ensures availability of potable water supply
7. Prepares detailed SOPs and checklist that include:
 - a) Contact information and mechanisms for notifying personnel
 - b) Step-by-step procedure for performing assigned tasks
8. Provides sanitation services

¹¹ The Family Room will not be set up adjacent to the MDAD Airport EOC or Press Room.

9. Maintains a chronological event log

1.13.4.4. Miami-Dade Police Department, Airport District

1. Provides access control to the air operations area
2. Provides other law enforcement support, as required

1.13.4.5. All Other Tasked Organizations

1. Adhere to all airport rules and regulations in the performance of duties
2. Provide related status reports to the Operations and/or Maintenance Coordinator, as appropriate

1.13.5. Administration and Logistics

This section focuses on the general support requirements and identifies sources that will be relied upon to obtain personnel, equipment and supplies.

MDAD Maintenance shall be established as Resource Manager and provides vital supplies and equipment to support emergency operations. The MDAD Cert team is one source of support personnel specifically established for the purpose of emergency response and recovery operations. This team is on-call 24 hours a day and is dispatched by the Resource Manager. All stock and equipment supplies are maintained on-airport at the MDAD Warehouse and Maintenance yard. Additional equipment can be obtained from Miami-Dade County.

In the event of emergencies, MDAD Maintenance has developed and shall maintain the following resources:

1. Facilities and Equipment.
 - a) Portable lavatories
 - b) Drinking water
 - c) Ropes, barricades, barrier tape, etc.
 - d) Portable lighting
 - e) Cones, stakes, flags and signs
 - f) Portable shelter(s)
 - g) Machinery, heavy equipment, and extraction tools
 - h) Fuel removal equipment
 - i) Portable public address system
 - j) Communications equipment (cellular telephones, two-way radios, etc.)

Transportation resources (bussing operations) shall be provided by MDAD Airside Operations. Once on-airport bus services are depleted, additional busses are obtained from on-airport bussing operator. Additional vans, trucks, will be obtained through the Resource Manager.

1.13.6. Plan Development and Maintenance

Refer to section 1.3.

1.13.7. Authorities and References

1. FAA AC 150/5200-31, Airport Emergency Plan
2. Miami-Dade Aviation Department Continuity of Operations Plan (COOP)

1.14. DELEGATION OF AUTHORITY

The Aviation Director is empowered to take such action as the Director deems necessary when an emergency exists at an airport which, in the director's judgment, presents an immediate threat to public health, security, safety or welfare, or to the operation of an Airport; provided, however, that in the exercise of such power the director shall promptly notify the governmental agency(ies) or County department(s) having been assigned by the Board or County Manager Primary responsibility for the handling and resolution of such emergency, and provided further that the Director's power herein granted shall cease upon the assumption of jurisdiction over such emergency by the governmental agency(ies) or County department(s) and such assumption of responsibility shall not be inconsistent with the requirements of any emergency procedure or program for an Airport adopted and approved by the Board. No action shall knowingly be taken by the Director hereunder or by any County department(s) contrary to any regulation or order of the Federal Aviation Administration or of any other Federal, State or County agency having appropriate jurisdiction. 25-1.4 Emergencies, Chapter 25, Dade County Code, Aviation Department Rules and Regulations, (Ord. No. 75-113, § 2, 12-2-75; Ord. No. 95-41, § 38, 3-7-95).

1.15. EMERGENCY PERSONNEL TRAINING

All firefighting/rescue personnel at Miami International Airport are trained in at least the following areas:

1. Airport Familiarization
2. Aircraft Familiarization
3. Fire Rescue Personnel Safety
4. Emergency Communications at the airport
5. Use of fire hoses, nozzles, turrets and other appliances
6. Application of Extinguishing Agents
7. Emergency Aircraft Evacuation
8. Firefighting Operations
9. Adapting and using structural firefighting equipment of ARFF
10. Aircraft Cargo Hazards
11. Familiarization with the Airport Emergency Plan
12. Other training as specified in the Airport Certification Manual (Water Rescue, etc.)
13. Annual Live Fire ("Hot") drills

1.16. ADMINISTRATION AND COORDINATION OF THE EMERGENCY PLAN

The Aviation Department will:

1. Coordinate its plan with law enforcement agencies, rescue and firefighting agencies, medical personnel and organizations, the principle tenants at the airport, and all other persons who have responsibilities under this plan.
2. To the extent practicable, provide for participation by all facilities, agencies, and personnel specified in paragraph 1.6. (1.).

3. Ensure that all airport personnel having duties and responsibilities under the plan are familiar with their assignments and are properly trained.
4. At least once every twelve (12) consecutive calendar months, review the plan with all of the parties with whom the plan is coordinated to ensure that all parties know their responsibilities and that all of the information in the plan is current.
5. Hold a full-scale airport emergency plan exercise at least once every 36 consecutive calendar months.
6. Ensure that instructions for response to Section 3 and Section 7 of this Airport Emergency Plan are consistent with the airport's Security Program.

EMERGENCY NOTIFICATION CHART

Person first aware of emergency shall contact FAA ATCT, Fire Department or Police Department. The notified Agency shall make certain that the other two (2) are properly advised. The Tower is to contact MDAD Airside Operations, which will contact the AOC.

Note: Notifications to appropriate Law Enforcement and Governmental Agencies listed below will take place by primary points of contact work at MIA. For example: Notification to FHP will be handled by

		Aircraft	Bomb Incident	Structural Fire	Natural Disaster	Hazardous Material	Sabotage
1	Miami FAA Air Traffic Control Tower (ATCT)						
2	Miami-Dade Fire Rescue, Airport Division						
3	Miami-Dade County Police Department, Airport District						
4	Airside Operations Gate Control Towers						
5	Airport Operations Center (AOC)						
6	Landside Operations Control Room						
7	Office of Communications, MDAD						
8	Maintenance Office, MDAD						
9	Airlines						
10	Tenants						
11	U.S. Coast Guard, Department of Homeland Security						
12	Florida Highway Patrol						
13	Miami-Dade County Department of Emergency Management & Homeland Security (activated by MDFR Fire Alarm Office)						
14	National Transportation Safety Board (NTSB)						
15	Miami-Dade County Health Department						
16	U.S. Postal Service						
17	U.S. Customs and Border Protection						
18	U.S. Department of Agriculture						
19	U.S. Citizenship and Immigration Services						
20	U.S. Department of Health & Human Services						
21	U.S. Federal Bureau of Investigation						
22	U.S. Bureau of Alcohol, Tobacco, Firearms and Explosives (ATF)						
23	U.S. Transportation Security Administration (TSA)						

Notification of all incidents:

Notification determined at time of incident:

Notification not required:

EXHIBIT 1A

Original 11/04 | Revised 01/22

Page |1 - 45

**AIRCRAFT ACCIDENT
INCIDENT COMMAND SYSTEM LAYOUT**





EXHIBIT 1B

Airport Emergency Plan INTRODUCTION



SECTION 2

Table of Contents

2. AIRCRAFT INCIDENTS AND ACCIDENTS	2 - 3
2.1. INTRODUCTION	2 - 3
2.2. PURPOSE	2 - 3
2.3. ADMINISTRATION AND LOGISTICS	2 - 3
2.4. DEVELOPMENT AND MAINTENANCE	2 - 3
2.5. AUTHORITIES AND REFERENCES	2 - 3
2.6. SITUATION AND ASSUMPTIONS	2 - 3
2.7. OPERATIONS	2 - 4
2.7.1. Classifications	2 - 4
2.8. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES	2 - 4
2.8.1. MIA Air Traffic Control Tower (ATCT)	2 - 4
2.8.1.1. <u>Activate Emergency Procedures</u>	2 - 5
2.8.1.2. <u>Notification of Airport Fire Department</u>	2 - 5
2.8.1.3. <u>Closing of Runway(s) / Taxiway(s)</u>	2 - 6
2.8.1.4. <u>Notification of Agencies</u>	2 - 6
2.8.2. Miami-Dade Fire Rescue, Aviation Division	2 - 6
2.8.2.1. <u>Responsibilities</u>	2 - 6
2.8.2.2. <u>Routing Control of Support Equipment</u>	2 - 7
2.8.2.3. <u>Additional Equipment Assignments</u>	2 - 7
2.8.2.4. <u>Mutual Aid</u>	2 - 8
2.8.3. MDAD Operations	2 - 8
2.8.3.1. <u>Responsibilities</u>	2 - 8
2.8.3.2. <u>Procedures: Alert II</u>	2 - 8
2.8.3.3. <u>Procedures: Alert III On-Airport</u>	2 - 9
2.8.3.4. <u>Procedures: Alert III Off-Airport Aircraft Incident/Accident with ARFF Response</u>	2 - 11
2.8.4. Miami-Dade Police Department, Airport District	2 - 12
2.8.4.1. <u>Responsibilities</u>	2 - 12
2.8.4.2. <u>Procedures</u>	2 - 12
2.8.5. Miami-Dade County Department of Emergency Management & Homeland Security (County EOC)	2 - 13
2.8.6. Miami-Dade County Health Department (Medical Examiner)	2 - 13
2.8.7. United States Postal Service	2 - 13
2.8.8. Aircraft Owner/Operator or Designated Representative	2 - 13
2.9. HEALTH AND MEDICAL	2 - 14
2.9.1. Purpose	2 - 14

2.9.2. Objective.....2 - 14

2.9.3. Procedure2 - 14

EXHIBIT 2A Fire Mutual Aid Rendezvous Points

2. AIRCRAFT INCIDENTS AND ACCIDENTS

2.1. INTRODUCTION

Aircraft incidents or accidents can vary greatly by circumstances. This section describes the emergency preparedness plan for aircraft incidents or accidents located either on-airport, off-airport on adjacent property, or off-airport where the airport is either a point of origin or destination.

2.2. PURPOSE

The information contained in this section defines responsibilities and describes actions to be taken in the event that an aircraft incident/accident affects the airport in any of the situations. This section represents the Standard Operating Procedures for Miami-Dade Aviation Department employees, airport tenants, users, and other agencies.

2.3. ADMINISTRATION AND LOGISTICS

The management of support resources in the event of emergencies is detailed in the Miami-Dade Aviation Department, Continuity of Operations Plan (COOP). This plan establishes a framework for MDAD to prepare for, respond to, mitigate the impacts of, and recover from emergencies.

2.4. DEVELOPMENT AND MAINTENANCE

Revisions to this Aircraft Incidents and Accidents section shall be maintained by the Division Director, Airside Operations or his/her designee. A true and current copy of the Airport Emergency Plan shall be maintained by the Airside Operations Supervisor, Ramp Control.

2.5. AUTHORITIES AND REFERENCES

Initial response to any aircraft accident, emergency, or potential emergency, will follow the guidelines established by Letter of Agreement between the Miami ATC Tower and the Miami-Dade Aviation Department, "FAA Emergency Procedures", reference Section 14, "MIA ATCT Functions Relating to Emergency Actions", Exhibit 14A. Miami-Dade Fire Rescue equipment augmentation will follow Fire Department Strategies for Alarm Assignments III-E-51.

2.6. SITUATION AND ASSUMPTIONS

Miami International Airport (MIA) operates 24 hours a day and manages an average of more than one thousand flights daily, utilizing four runways.

MIA is categorized as an ARFF Index E airport, operating five or more average daily departures of air carrier aircraft at least 200 feet in length. ARFF is operated by the Miami-Dade Fire Rescue, Aviation Division, which conducts operations from two Fire Stations on the Airfield. All equipment required to meet Index are listed in Volume I, Section 317-2.

For the purpose of emergency response, each aircraft incident / accident shall be considered a potential hazardous materials incident. Section 6, "*Hazardous Materials Incidents*", comprises HAZMAT response procedures for this airport.

2.7. OPERATIONS

MDFR will assume the Incident Commander role as the Lead agency at the Incident Command Post for this hazard-specific section. The ICS shall be used throughout the incident.

2.7.1. Classifications

Aircraft incidents, accidents and corresponding alerts are classified as follows:

1. Alert I (Local Standby)
This is notification only. No response is required. All units involved will be manned and will standby in quarters. Specify items 1 – 10 (paragraph 2.5.1.2.(a)).
2. Alert II (Full Emergency)
All units will respond to pre-designated positions. Specify items 1 – 11 (paragraph 2.5.1.2.(a)) only and provide additional information to the Senior Fire Officer on ground control frequency.
3. Alert III (Aircraft Accident)
All designated emergency response units proceed to the scene in accordance with established plans and procedures. Specify items 1 and 2 (paragraph 2.5.1.2.(a)) only and provide additional information to the Senior Fire Officer on ground control frequency.

2.8. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES

2.8.1. MIA Air Traffic Control Tower (ATCT)

Normally, the MIA FAA ATCT will be the first to be aware of aircraft incidents and accidents and will institute the alert procedure outlined below. Such procedures are established by Letter of Agreement between Miami ATC Tower and Miami-Dade Aviation Department, titled "Emergency Procedures", a copy of which is included in Section 14, "Control Tower Functions". Such guidelines are also found in the FAA Aeronautics Information Manual, Official Guide to Basic Flight Information and ATC Procedures.

Any person becoming aware of an aircraft incident and/or accident should immediately notify the MIA ATCT by radio or telephone.

2.8.1.1. Activate Emergency Procedures

In the event of an aircraft accident, emergency, or potential emergency, MIA ATCT personnel shall alert the Airport Fire Division, ARFF equipment when any of the following personnel request such action.

1. The Miami Tower Cab Supervisor.
2. The pilot of the aircraft concerned.
3. The operator of the aircraft or his/her representative.
4. A representative of the airport management.

2.8.1.2. Notification of Airport Fire Department

MIA ATCT shall advise the Airport Fire Station via the Tower Emergency Telephone (Crash Phone) of all emergencies, potential emergencies, fires, bomb threats, or any operation other than normal.

If events do not permit coordination via the Emergency Telephone (Crash Phone), the Tower personnel shall determine the appropriate alert category and coordinate with the ARFF Commander using the call sign "Fire Commander".

"Drop Monitors" off the Tower emergency telephone (Crash Phone) are installed in the Miami-Dade Police Department (MDPD), Airport District, General Aviation Center (GAC), MDAD Airside Operations Gate Control Towers, MDAD Operations Executive Office, Airside Operations Administrative Office, and the MDAD Airport Operations Center (AOC). These monitors provide for notifications to Airport Operations personnel.

MDAD Airside Operations constantly monitors the Emergency Telephone (Crash Phone) and when an Alert is received or when notified by the Fire Department, they notify appropriate airfield personnel, in accordance with procedures, section 2.5.3.2.

(a) MIA FAA ATC Tower shall provide the following information to the Airport Fire Division or Fire Commander:

1. Alert status: I, II, or III.
2. Aircraft location / runway as appropriate.
3. Flight number and/or registration.
4. Number and type of aircraft.
5. Aircraft problem.
6. Souls on board.
7. Fuel on board in pounds or gallons.
8. Hazardous cargo status (not on board or on board with type of material).
9. Wind direction and velocity.
10. Estimated time of arrival and landing runway.
11. Any additional information relative to the emergency.

MIA ATCT shall provide the Fire Commander with updated information concerning the aircraft position and/or landing sequence via Ground or Discrete Emergency Frequency (see *exhibit 14A, "Emergency Procedures"*).

MIA ATCT shall request the pilot to report when assistance from ARFF is no longer necessary and will relay this information to the Fire Commander.

2.8.1.3. Closing of Runway(s) / Taxiway(s)

During an Alert III, the MIA ATCT shall immediately discontinue use of the affected runway(s) and/or taxiway(s) and promptly notify the MDAD Airside Operations Ramp Control Sr. Agent (Ramp 1) and the Fire Commander. Ramp 1 will make the decision to close the affected area.

Ramp 1 will reopen the areas affected at the earliest possible time following the incident.

2.8.1.4. Notification of Agencies

MIA ATCT shall normally provide initial information for:

- a. Alert I and II to the Airport Fire Division.
- b. Alert III to the following:
 1. Airport Fire Division
 2. Aircraft Operator
 3. MDAD (Ramp 1)

2.8.2. Miami-Dade Fire Rescue, Aviation Division

The Aviation Division of the Miami-Dade Fire Rescue provides immediate firefighting and rescue services for any aircraft alert or incident on or in the vicinity of MIA.

2.8.2.1. Responsibilities

Responsibilities of the Airport Fire Division for aircraft incidents on the airport or in the immediate vicinity of the airport are as follows:

1. The Sr. Fire Officer as IC assumes primary responsibility at the immediate scene of any incident involving aircraft fire or rescue.
2. Directs, controls, and conducts rescue and firefighting activities during period of emergency.
3. Establishes Incident Command Post (ICP) in conjunction with Airport Police and MDAD.
4. Determines need for and requests ambulance service and medical assistance as required through the Fire Department Alarm Office or MDR Med-Com System.
5. Requests additional firefighting and rescue or other equipment as needed, through the Fire Department Alarm Office.
6. Supports the Miami-Dade Police as needed, in activities for which Police have primary responsibility, i.e., bomb incidents.

2.8.2.2. Routing Control of Support Equipment

The IC on the scene of an accident will normally make requests for additional support equipment and personnel through the Miami-Dade County Fire Alarm Office.

The IC will determine the appropriate Rendezvous Point(s) for entrance of incoming support emergency equipment (*see exhibit 2A - Attachment 1 / Exhibit 14A*, depicting the following Rendezvous Points):

1. Terminal entrance
2. Southeast Gate
3. NW 36th St. and NW 57th Ave
Southbound to gate east of Bldg. 841
4. Red Road Gate South
5. 2650 NW Perimeter Road
6. Southwest Gate

Properly identified emergency or airport vehicles maintaining two-way radio communications with the Air Traffic Control Tower (ATCT), shall escort vehicles authorized to enter the airport through these points to the emergency scene. Emergency or airport vehicles equipped with ground control radios and in communication with ATCT may receive their own clearance from ATCT and proceed accordingly if released to do so. Unless safety of life or property would be jeopardized by so doing, all vehicles, including emergency vehicles, shall proceed to the extent possible, on established vehicular roadways, and not on or across runways or taxiways.

2.8.2.3. Additional Equipment Assignments

Additional equipment procedures are to be handled in the following manner:

The IC in charge at the time of the emergency shall, upon arrival at the scene, evaluate the situation and determine what additional equipment and personnel will be needed to control the emergency at hand. Upon making such determination, the IC shall take the following actions:

1. Establish the incident identification category, i.e. minor or major accidents (*see Classifications* descriptions, paragraph 2.4.1.).
2. Establish the rendezvous point(s) for direction of off-airport equipment units (*see Exhibit 2A*).
3. Initiate notification of the appropriate agencies or organizations, identifying himself by name and rank and giving the following information:
 - a. Emergency description and identification (minor or major accident).
 - b. Rendezvous point(s) established.
 - c. Location – if off-airport, giving grid coordinates where possible.
4. Notify MDAD Airside Operations Ramp Control Senior Agent (Ramp 1) for the purpose of escort duty.
5. Upon arrival of off-airport units at ICP, shall furnish necessary information and directions as to action required.

If the emergency should involve an airborne aircraft and the pre-alert time is sufficient, requests for equipment assignments will be made direct from the Airport Fire Station to the Miami-Dade Fire Alarm Office by telephone, giving the necessary particulars on the emergency, including the Estimated Time of Arrival (ETA) of the aircraft.

If such requests are made after airport fire personnel have responded from quarters, such will be communicated to the Alarm Office via Fire Department radio frequency.

2.8.2.4. Mutual Aid

All requests made for mutual aid assistance will be made through the Miami-Dade Fire Alarm Office only by the FAO Chief or FAO Dispatch Supervisor.

Mutual aid rendered by the Airport Fire Division, MIA, will also be handled through Miami-Dade County Fire Alarm Office. Where possible, airport fire equipment will be available to local municipalities as well as areas of the County which may have an emergency requiring large foam producing equipment (reference section 15, "Mutual Aid Agreements"). At no time however, shall the airport response capability be reduced below ARFF Index E category.

2.8.3. MDAD Operations

2.8.3.1. Responsibilities

The Airside Operations Ramp Control Senior Agent (Ramp 1), operating on a 24-hour basis, will act as the Staff Duty Officer and may be reached through the MDAD Airport Operations Center (AOC).

2.8.3.2. Procedures: Alert II

A. Airside Operations

Upon occurrence of an Alert II situation, Ramp 1 shall take the following actions:

1. Ramp 1 will establish CP with Fire Commander.
2. Assign Agent(s) for runway sweep (all runway sweeps must start at the beginning of the runway).
3. Assign Agent to follow aircraft to parking location (this will ensure that aircraft does not leave FOD and covers a possible secondary emergency).
4. If debris / spill is found, close runway for clean-up.
5. Inspecting Agent will notify ATCT only when he/she confirms that all vehicles responding to the Alert II, as well as the Alert II aircraft, are clear of the runway.

2.8.3.3. Procedures: Alert III On-Airport

A. Airside Operations

Upon occurrence of an Alert III situation, Ramp 1 shall take the following actions:

1. Close Airport (Airfield) – to facilitate emergency response and perform airfield inspection.¹²
2. Direct the AOC to notify (RED) list.
3. Establish liaison with IC.
4. At direction of the IC, Contact Maintenance at Station 5 or Maintenance 1 after hours to direct “Cert Team” to muster point.
5. Coordinate with IC to establish Air Rescue landing zone. Zone shall be established by an area 100 feet by 100 feet square.
6. As determined by IC, dispatch personnel to rendezvous point and begin transportation of emergency equipment to the site.
7. Establish outer perimeter boundary until MDPD arrival.
8. Direct Security Division to cancel all delivery escorts until further notice.
9. Open unaffected areas – only after it is ascertained by the IC that the rescue and evacuation activities associated with the event will not be impacted negatively by the resumption of airfield operation and the accident event does not pose a hazard to the resumption of airfield operation.
10. Issue NOTAM to close those areas affected by the event.
11. Upon completion of life safety activities, the following shall be completed:¹³
 - a) Establish Inner and Outer Perimeter
 - i. Protect property
 - ii. Prevent the disturbance of wreckage and debris except to preserve life, rescue the injured, or protect the wreckage from further damage.
 - iii. Protect and preserve ground scars and marks made by the aircraft.
 - iv. Admit Public Safety personnel access to the wreckage to the extent necessary to preserve life, and/or stabilize HAZMAT.
 - v. Maintain a record of personnel who enter the accident site.
 - b) Prior to NTSB arrival on scene, restrict access only to authorized personnel:
 - i. FSDO
 - ii. Police / Fire / EMS
 - iii. Medical Examiner / Coroner
 - iv. Other Emergency Services Agencies

¹² Reference AC 150/5200-31C, “Airport Emergency Plan”, 7-1-5 e.(2)(d)

¹³ Checklist references NTSB Form SPC-04-02, “Responding to an Aircraft Accident – A Guide for Police and Public Safety Personnel.

- c) After NTSB arrival on scene, no access without NTSB authorization.¹⁴

B. Terminal Operations

Terminal Operations shall take the following actions upon listed direction.¹⁵

- 1. Setup and activate the Airport EOC at the direction of the Deputy Director or Assistant Director of Operations.
- 2. Setup and activate the Family Room at the direction of the Airport EOC and in coordination with the IC.

C. Maintenance

MDAD Maintenance shall take the following actions as required by the IC.

- 1. Cert Team
 - a) Place "Cert Team" on stand-by when directed by Station 5 during working hours or Maintenance 1 after hours.
 - b) Direct "Cert Team" to staging area as determined by the IC.
- 2. Perimeter Barricades
 - a) Setup Inner & Outer perimeter as directed by IC.
- 3. Heavy Equipment
 - a) Direct Heavy equipment to staging area as determined by the IC.
- 4. Assist/provide critical services, including utility support (activation/cut-off), as needed.
- 5. Provide sanitation services for extended operations.
- 6. Assist in the provision of required resources.
- 7. To the extent possible, arrange to have available the following equipment/supplies/services:
 - a) Portable lavatories.
 - b) Drinking water.
 - c) Ropes, barricades, barrier tape, etc.
 - d) Portable lighting.
 - e) Cones, stakes, flags and signs.
 - f) Portable shelter(s), as needed.
 - g) Machinery, heavy equipment, and extraction tools.
 - h) Fuel removal equipment.
 - i) Portable public address system.
 - j) Communications equipment (cellular telephones, two-way radios, etc.).¹⁶

¹⁴ 49 CFR §831.2., Responsibility of the Board.

¹⁵ Per MDAD Terminal Operations SOP.

¹⁶ Paragraph "c." lines 4 thru 7 references AC 150/5200-31C, Airport Emergency Plan 7-1-5 e.(3)(c), Organization and Assignment of Responsibilities.

D. Public Information Officer (PIO)

The PIO shall initiate the following procedures:¹⁷

1. In the event of an injury or fatality, the Airline PIO will be responsible for all press announcements reference the incident.
2. Develop and provide press releases relative to the airport's responsibilities and activities, as needed.
3. Interface with the media, as well as with air carrier and emergency response on-scene public relations personnel.
4. Participate in Airport EOC or ICP activities as directed.

2.8.3.4. Procedures: Alert III Off-Airport Aircraft Incident/Accident with ARFF Response

- a. In the event of an off-airport crash in the vicinity of the airport, Ramp 1 will take the following action:
 1. Close Airport (Airfield) - to facilitate emergency response and perform airfield inspection.
 2. Direct the AOC to notify (RED) list.
 3. Establish Liaison with IC.
 4. At direction of the IC, Contact Maintenance at Station 5 or Maintenance 1 after hours to direct "Cert Team" to muster point.
 5. Reopen Airport (Airfield) upon direction of IC.
 6. Issue Appropriate NOTAM(s).
 7. Ensure Index E at all times:
 - a) INDEX E EQUIPMENT
 - i. Three vehicles:
 1. One carrying 500 lbs of sodium-based dry chemical, halon 1211, or clean agent; or 450 lbs of potassium-based dry chemical and water with a commensurate quantity of AFFF to total 100 gallons for simultaneous dry chemical and AFFF application and;
 2. Two vehicles carrying an amount of water and the commensurate quantity of AFFF so the total quantity of water for foam production carried by all three vehicles is at least 6,000 gallons.
 8. In the event that any ARFF equipment required under our index is out of service, Ramp 1 shall implement the following procedures:
 - a) Notification shall be made to the FAA Southern Region Airports Division Manager.

¹⁷ Checklist references AC 150/5200-31C, Airport Emergency Plan 7-1-5 e.(3)(e), Organization and Assignment of Responsibilities.

- b) Direct notification of equipment status shall be made to local air carriers through a self-cancelling NOTAM which shall be issued for the first 48 hours, stating the following:
 - i. **ARFF VEHICLE OTS INDEX UNCHANGED**
- c) If the ARFF equipment remains out of service after 48 hours, the following NOTAM shall be issued:
 - i. **ARFF NOW INDEX D**
- d) Throughout the time of reduced index, the airport shall allow no more than four (4) Index E aircraft operations per day until all equipment required to meet Index E is returned to service.

2.8.4. Miami-Dade Police Department, Airport District

2.8.4.1. Responsibilities

The general responsibilities of the Airport Police District in the event of an aircraft incident or accident alerts are as follows:

2.8.4.2. Procedures

A. Alert I

Standby and monitor MIA ATCT Ground Control and Police frequencies

B. Alert II

In the event of such an Alert, the following actions are to be taken:

1. Airport patrol vehicle(s) will proceed to standby position near runway, or proceed to alarm scene and establish liaison with IC.
2. Activate and monitor Police channel "D" in the event police action is needed.
3. Upon notification by the IC that an airport support assignment has been requested, proceed to the established rendezvous point(s) to assist with traffic and entry control.

C. Alert III

In the event of such an alert, the following actions are to be taken:

1. Proceed to the scene and assist the movement of emergency vehicles and authorized persons to and from the crash or emergency site as required.
2. Staff and control rendezvous points and established access roads for movement of people and equipment to the emergency scene.
3. Secure the scene of the emergency from spectators and other persons not authorized to be present by establishing a security perimeter.

4. Request and coordinate the activities of other law enforcement agencies as needed.
5. Provide temporary security for wreckage or any other property at an incident scene pending assumption of responsibilities by properly identified owner or investigative agencies.
6. Consult with the IC regarding termination of the emergency.
7. Provide necessary investigative support.

2.8.5. Miami-Dade County Department of Emergency Management & Homeland Security (County EOC)

The Miami-Dade County EOC will, upon arrival:

1. Assume responsibility for calling additional medical resources from outside Miami-Dade County, including the Medical Disaster Teams, such as the Disaster Medical Assistance Team (DMAT) and the Disaster Mortuary Response Team (DMORT).

2.8.6. Miami-Dade County Health Department (Medical Examiner)

Coordinate with ICP and airline/operator concerned in establishing and operating a temporary morgue.

1. Conduct necessary operations with airline/operator to identify injured or remains at site.
2. Coordinate with ICP in marking of locations of fatally injured.

2.8.7. United States Postal Service

When notified, will receive mail off-loaded at emergency site.

2.8.8. Aircraft Owner/Operator or Designated Representative

The aircraft owner/operator or designated representative shall:

1. Provide pertinent information to Incident Commander, to include:
 - a. Number of persons on board.
 - b. The presence and location of any dangerous goods.
2. Provide Airport EOC representation.
3. Make necessary notifications, to include the FAA and NTSB.
4. Arrange for appropriate passenger services, to include:
 - a. The transportation of uninjured passengers/crew members.
 - b. Adequate holding facilities for uninjured passengers/crew members.
 - c. Commissary items, telephone facilities, clothing, and additional medical services, as needed.
 - d. Facilities for friends and families of victims/passengers.
 - e. Passenger/crew accountability and tracking.
 - f. Hotel and/or other alternative travel arrangements for passengers.
 - g. Critical Incident Stress Management (CISM) support.
5. Implement approved plan in compliance with the requirements established in the ADFAA (Aviation Disaster Family Assistance Act).¹⁸

¹⁸ Public Law 104-264, Title VII, Oct. 9, 1996, Aviation Disaster Family Assistance Act (ADFAA)

6. Coordinate news releases with Airport Community/Public Relations personnel.
7. Provide for the timely removal of the wrecked or disabled aircraft as soon as authorized by the appropriate authority.

2.9. HEALTH AND MEDICAL

2.9.1. Purpose

This Standard Operating Procedure was created to standardize procedures for medical emergencies onboard aircraft at MIA.

2.9.2. Objective

The information contained in this subsection defines responsibilities and describes actions to be taken in the event that an aircraft has a medical emergency. It is intended to enable the flow of accurate and timely information to Aircraft Rescue and Fire Fighting (ARFF) responders regarding disposition of ill or injured people onboard aircraft and to gain immediate access to the aircraft for the purpose of diagnosis and treatment.

2.9.3. Procedure

1. Federal Aviation Administration (FAA) Miami Tower will notify the Miami-Dade Fire (ARFF) Watch Office via a dedicated Medical Emergency Telephone of medical emergencies onboard aircraft at MIA or en route to MIA.
2. If deemed necessary by ARFF personnel, MIA Tower or the Pilot-in-Command, the MIA Tower will make available frequency 120.35 for direct communication between the pilot-in-command and ARFF personnel.
3. ARFF Incident Commander will advise CDC if necessary.
4. Flight crews at MIA with onboard medical emergencies will keep passengers seated until ARFF or CDC responders have arrived on scene.
5. In the event of suspected communicable disease, the MIA Communicable Disease Plan will be implemented.
6. MDAD Operations personnel will stand-by at the parking gate to ensure that the aircraft can proceed as expeditiously as possible to parking and to assist the Incident Commander as needed.
7. The aircraft loading bridge shall not be placed upon the aircraft until ARFF or CDC personnel arrive.

R.P. #1 Terminal Entrance. On the main entrance to the Terminal Building, from N.W. 42nd Avenue, (Le Jeune Rd.), westbound at the overpass.


R.P. #2 Southeast Gate. On the east side of the airport, approximately at the intersection of Perimeter Road and N.W. 16th Street.

R.P. #3 Enter at the intersection of NW 36th Street and 57th Avenue and proceed southbound to the gate east of building 841.


R.P. #4 Red Road Gate South. On the south side of the airport, at Red Road, (N.W. 57th Avenue), and approximately N.W. 14th Street.

R.P. #5 2650 N.W. Perimeter Road, (one block north of N.W. 25th Street).

R.P. #6 Southwest Gate. On the southwest corner of the airport, just south of building #706, at the point of access from N.W. 16th Street into the ADA.



FAA Use Only



Magnetic Declination
6° 5' West (2012)

Annual Rate of Change
5.8' West

MIAMI-DADE COUNTY AVIATION DEPARTMENT
MIAMI INTERNATIONAL AIRPORT

**FIRE MUTUAL AID
RENDEZVOUS POINTS
EXHIBIT 2A
ATTACHMENT 1 / EXHIBIT 14A**

DRAWN BY	DATE	CHECKED BY	DATE	IN CHARGE	SCALE	FILENAME
H.I.	04-01-2019	P.W.	04-01-2019	L.C.K.D.	-	60377_Rev06

AIRSIDE OPERATIONS DIVISION

SHEET 1 of 1

SECTION 3 Table of Contents

3. BOMB INCIDENTS	3 – 2
3.1. INTRODUCTION	3 – 2
3.2. PURPOSE	3 – 2
3.3. ADMINISTRATION AND LOGISTICS	3 – 2
3.4. DEVELOPMENT AND MAINTENANCE	3 – 2
3.5. AUTHORITIES AND REFERENCES	3 – 2
3.6. SITUATION AND ASSUMPTIONS	3 – 2
3.6.1. Threat Evaluation	3 – 3
3.7. OPERATIONS	3 – 4
3.7.1. Aircraft Threats	3 – 4
3.7.1.1. <u>Notifications</u>	3 – 4
3.7.1.2. <u>Aircraft Placement</u>	3 – 4
3.7.1.3. <u>Search Procedures</u>	3 – 5
3.7.2. Structure/Facility Threats	3 – 5
3.7.2.1. <u>Notifications</u>	3 – 5
3.7.2.2. <u>Search Procedures</u>	3 – 6
3.7.2.3. <u>Evacuation Procedures</u>	3 – 7
3.8. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES	3 – 7
3.8.1. Aircraft Threats	3 – 7
3.8.1.1. <u>Miami-Dade Police Department, Airport District</u>	3 – 7
3.8.1.2. <u>Miami-Dade Fire Rescue, Aviation Division</u>	3 – 8
3.8.1.3. <u>MDAD Airside Operations, Ramp Control Sr. Agent (Ramp 1)</u> ..	3 – 8
3.8.1.4. <u>Airline/Aircraft Operator</u>	3 – 9
3.8.2. Structure/Facility Threats	3 – 9
3.8.2.1. <u>Miami-Dade Police Department, Airport District</u>	3 – 9
3.8.2.2. <u>MDPD Bomb Squad</u>	3 – 10
3.8.2.3. <u>Miami-Dade Fire Rescue, Aviation Division</u>	3 – 10
3.8.2.4. <u>MDAD Operations and Security</u>	3 – 10

EXHIBITS

3A Aircraft Placement, Bomb Threat

3B Detail – Aircraft Placement, Bomb Threat

3C Bomb Threat Checklist

Warning: This record contains Sensitive Security Information that is controlled under 49 CFR parts 15 and 1520. No part of this record may be disclosed to persons without a "need to know", as defined in 49 CFR Parts 15 and 1520, except with the written permission of the Administrator of the Transportation Security Administration or the Secretary of Transportation. For U.S. Government agencies, public disclosure is governed by 5 U.S.C. 552 and 49 CFR parts 15 and 1520. This Airport document may also be exempt from disclosure and/or public access under one or more of the following: FSS 119.07; FSS 281.301; FSS 331.22. Unauthorized release may result in civil or criminal penalty.

3. BOMB INCIDENTS

3.1. INTRODUCTION

This section describes the emergency preparedness plan for bomb incidents involving any arriving airborne aircraft, aircraft on the ground, or a bomb threat involving airport facilities.

3.2. PURPOSE

The information contained in this section defines responsibilities and describes actions to be taken in the event a bomb threat or actual incident occurs at the airport. This section represents the Standard Operating Procedures for Miami-Dade Aviation Department employees, airport tenants, users, and other agencies.

3.3. ADMINISTRATION AND LOGISTICS

The management of support resources in the event of emergencies is detailed in the Miami-Dade Aviation Department, Continuity of Operations Plan (COOP). This plan establishes a framework for MDAD to prepare for, respond to, mitigate the impacts of, and recover from emergencies.

3.4. DEVELOPMENT AND MAINTENANCE

Revisions to this Bomb Incidents section shall be maintained by the Division Director, Airside Operations or his/her designee. A true and current copy of the Airport Emergency Plan shall be maintained by the Airside Operations Supervisor, Ramp Control.

3.5. AUTHORITIES AND REFERENCES

Initial response to any aircraft accident, emergency, or potential emergency, will follow the guidelines established by Letter of Agreement between the Miami ATC Tower and the Miami-Dade Aviation Department, "FAA Emergency Procedures", reference Section 14, "MIA ATCT Functions Relating to Emergency Actions", Exhibit 14A. Miami-Dade Fire Rescue equipment augmentation will follow Fire Department Strategies for Alarm Assignments III-E-51.

3.6. SITUATION AND ASSUMPTIONS

Miami International Airport, its aircraft owner/operator, or any other agency operating at this airport is a potential target for a bomb threat. All threats will be taken seriously until the validity of the threat can be determined.

Warning: This record contains Sensitive Security Information that is controlled under 49 CFR parts 15 and 1520. No part of this record may be disclosed to persons without a "need to know", as defined in 49 CFR Parts 15 and 1520, except with the written permission of the Administrator of the Transportation Security Administration or the Secretary of Transportation. For U.S. Government agencies, public disclosure is governed by 5 U.S.C. 552 and 49 CFR parts 15 and 1520. This Airport document may also be exempt from disclosure and/or public access under one or more of the following: FSS 119.07; FSS 281.301; FSS 331.22. Unauthorized release may result in civil or criminal penalty.

Miami International Airport has two designated parking areas for aircraft isolation during a threat (exhibit 3B, Aircraft Placement Bomb Threat, details the locations on the airfield). The primary location is identified as the Penalty Box (building 610). The secondary location is identified as the Midfield Blast Fence.

3.6.1. Threat Evaluation

Bomb threats generally can be classified in three categories:

1. Specific threats or suspicious conditions involving aircraft or a group of aircraft.
 - a. Definition of a specific threat against an aircraft can be any one of the following combinations:
 - i. Airline and flight number
 - ii. Airline and origin or destination
 - iii. Flight and origin or destination
 - iv. Registration of aircraft
 - v. Pilot in charge
 - vi. Flight number and time
 - vii. Airline and time
 - viii. Origin or destination and time
 - ix. Any other information deemed relevant by the Airport Sr. Police Officer or designee
2. Specific threats or suspicious conditions involving a building structure or structures.
 - a. Definition of a specific threat against a building structure can be any one of the following:
 - i. Tenant name
 - ii. Building address
 - iii. Building number
 - iv. Description of location
 - v. Any other information deemed relevant by the Airport Sr. Police Officer or designee
3. General threat with no specifics given.

All threats, other than a general threat, shall be considered valid until proven otherwise. Notifications, responsibility, search, evacuation and reporting, shall be performed in compliance with these procedures.

Warning: This record contains Sensitive Security Information that is controlled under 49 CFR parts 15 and 1520. No part of this record may be disclosed to persons without a "need to know", as defined in 49 CFR Parts 15 and 1520, except with the written permission of the Administrator of the Transportation Security Administration or the Secretary of Transportation. For U.S. Government agencies, public disclosure is governed by 5 U.S.C. 552 and 49 CFR parts 15 and 1520. This Airport document may also be exempt from disclosure and/or public access under one or more of the following: FSS 119.07; FSS 281.301; FSS 331.22. Unauthorized release may result in civil or criminal penalty.

Consideration will be given to the evaluation of the incident by the airline, tenant, occupant, or owner (MDAD) involved, as to the need for a search. The Sr. Police Officer or his/her designee may overrule a decision and place the aircraft in an isolation area to determine the search limits of the involved aircraft or decisions made by facility tenants or owner (MDAD).

3.7. OPERATIONS

While airborne, the aircraft pilot in command shall be the individual responsible. When the aircraft is on the ground at MIA, the Miami-Dade Police Department, Airport District (MDPD), will assume the Incident Commander role as the lead agency at the Incident Command Post for this hazard-specific section unless otherwise declared in the subsections listed herein. The ICS shall be used throughout the incident.

3.7.1. Aircraft Threats

3.7.1.1. Notifications

1. When a threat is received, the person, airline, tenant, or agency receiving the call shall immediately notify the MIA ATCT and the Airport District Police Station.
2. Before making any notifications, the Airport District Police Station will check with ATCT to assure that they have knowledge of the threat. The airport District Police Station will then notify:
 - a. Airport Fire Division
 - b. MDAD Airport Operations Center (AOC)
 - c. MDPD Bomb Squad (called by the on-scene Sr. Police Officer as needed)
 - d. FBI
 - e. TSA
 - f. ATF
3. The AOC will activate the "Blue List" and then notify the Airline

3.7.1.2. Aircraft Placement

The IC will determine if the affected aircraft is to be moved to, or remain in the aircraft isolation area. Two locations are designated for isolation of the aircraft as shown on Exhibits 3A and 3B. The primary aircraft parking position is the Penalty Box – located as shown on Exhibit 3B. The secondary parking position is located at the Midfield Blast Fence as shown on Exhibit 3B.

Warning: This record contains Sensitive Security Information that is controlled under 49 CFR parts 15 and 1520. No part of this record may be disclosed to persons without a "need to know", as defined in 49 CFR Parts 15 and 1520, except with the written permission of the Administrator of the Transportation Security Administration or the Secretary of Transportation. For U.S. Government agencies, public disclosure is governed by 5 U.S.C. 552 and 49 CFR parts 15 and 1520. This Airport document may also be exempt from disclosure and/or public access under one or more of the following: FSS 119.07; FSS 281.301; FSS 331.22. Unauthorized release may result in civil or criminal penalty.

3.7.1.3. Search Procedures

1. Arriving or Returning Aircraft

Upon arrival at the aircraft isolation location, the passengers and crew shall be expeditiously deplaned using air stairs, self-contained stairs, or (at pilot/airline discretion) emergency chutes if circumstances so dictate. Passengers and crew will be loaded onto buses for transport to a safe area, preferably the Airport Terminal building.

2. Aircraft at Gate Position – Parked Aircraft

The following steps shall be taken when the incident involves an aircraft parked on a gate position:

a. Baggage Aboard Aircraft

Aircraft and baggage aboard the aircraft will be relocated to the designated search location. All baggage will be checked by the Police Canine Unit assigned to the Airport and/or the mobile X-Ray Van as determined by the IC. The MDPD Bomb Squad will check any suspect baggage if directed by the IC.

b. Baggage Not Aboard Aircraft

Any baggage in the possession of the airline at the time of the threat (but not on the aircraft), and baggage being checked in thereafter, may be searched in the baggage makeup area. The IC may direct that baggage be relocated to building 610 (the luggage search building), due to the nature of the threat or conditions existing at the time.

3.7.2. Structure/Facility Threats

For the purpose of this Document, it is assumed that a 300 foot evacuation zone will be established, centered on threat location unless otherwise directed by IC.

3.7.2.1. Notifications

When a threat is received involving a structure of facility, the person receiving the threat shall immediately notify the Airport District Police Station. The Airport District Police Station will then notify:

1. MIA ATCT
2. Airport Fire Division
3. MDAD AOC (the AOC will activate the “Blue List” and then notify tenant/occupant)
4. MDPD Bomb Squad (called by IC as required)
5. FBI
6. TSA
7. ATF

Warning: This record contains Sensitive Security Information that is controlled under 49 CFR parts 15 and 1520. No part of this record may be disclosed to persons without a “need to know”, as defined in 49 CFR Parts 15 and 1520, except with the written permission of the Administrator of the Transportation Security Administration or the Secretary of Transportation. For U.S. Government agencies, public disclosure is governed by 5 U.S.C. 552 and 49 CFR parts 15 and 1520. This Airport document may also be exempt from disclosure and/or public access under one or more of the following: FSS 119.07; FSS 281.301; FSS 331.22. Unauthorized release may result in civil or criminal penalty.

3.7.2.2. Search Procedures

1. General Area

If a threat is received regarding an explosive device which does specify a particular office or point in the terminal or other structure, the IC will determine if a general public area search will be initiated. If a search is conducted, Airport Police, EOD K-9, and MDAD Security teams will be utilized to check for an explosive device.

2. Specific Location

If a threat is received for a specific location within the terminal building (gate position, airline counter, concession area, etc...) or other structure, an immediate search will be conducted as determined by MDPD using the Explosive Detection Canine Unit. MDPD, MDAD Security, and Terminal Operations personnel will visually survey that location, pending the arrival of the Canine Team(s). If an object of a suspicious nature is detected, it must be left isolated and undisturbed until arrival of the Canine Team or MDPD Bomb Squad.

3. Other Structures

The tenant/occupant has the responsibility of searching the affected structure under supervision of the Airport Police and with the standby assistance (outside the area of estimated blast effect) of Fire Department personnel.

4. Suspicious Item

If a suspicious item, which indicates a possible explosive device, is found, the area will be isolated and the MDPD Canine Team will be used to confirm or refute the finding. If confirmed, the IC will notify the MDPD Bomb Squad.

5. Explosive Device

If an actual device is found, the area around the object will be secured and evacuated pending arrival of the MDPD Bomb Squad. Under no circumstances is any actual explosive device or suspicious item to be moved or attempted to be removed by anyone other than a member of the MDPD Bomb Squad.

Warning: This record contains Sensitive Security Information that is controlled under 49 CFR parts 15 and 1520. No part of this record may be disclosed to persons without a "need to know", as defined in 49 CFR Parts 15 and 1520, except with the written permission of the Administrator of the Transportation Security Administration or the Secretary of Transportation. For U.S. Government agencies, public disclosure is governed by 5 U.S.C. 552 and 49 CFR parts 15 and 1520. This Airport document may also be exempt from disclosure and/or public access under one or more of the following: FSS 119.07; FSS 281.301; FSS 331.22. Unauthorized release may result in civil or criminal penalty.

3.7.2.3. Evacuation Procedures

1. Main Terminal Building

If the IC determines that an evacuation of the Terminal is required, the "MIA Emergency Evacuation Plan" procedures shall be utilized.

2. Aircraft at Loading Gates

At the direction of the IC, MDAD Airside Operations and Terminal Operations personnel, in coordination with airlines located at gates in the area, will evaluate conditions and take appropriate action to relocate aircraft, associated fuel trucks, etc..., to secure locations.

3. Other Structures

The ranking representative of an affected office building, hangar, or any other structure, will consult with the IC to determine if and how an evacuation will take place. If the building is evacuated, MDPD along with Operations and Security will assist in the evacuation and will provide crowd control and cordoning off affected structure.

3.8. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES

3.8.1. Aircraft Threats

3.8.1.1. Miami-Dade Police Department, Airport District

The Incident Commander (IC) shall:

1. In cooperation with Airport Fire Division, Airline, and MDAD Airside Operations, determines the location required for inspection of aircraft, baggage, and conduct of search.
2. Assume full responsibility for, and activate search of aircraft, baggage, and cargo, utilizing Police Canine Unit(s) and/or mobile X-Ray Van.
3. In coordination with the Sr. Fire Officer, shall take any additional action necessary to assure that inspection is carried out in a safe and orderly manner.
4. Ensure that the MDPD Bomb Squad if required, is notified, responds, and conducts search as detailed herein.
5. Initiates through the MDPD Communications Shift Commander, the appropriate notifications of Investigative and Management Office.

Warning: This record contains Sensitive Security Information that is controlled under 49 CFR parts 15 and 1520. No part of this record may be disclosed to persons without a "need to know", as defined in 49 CFR Parts 15 and 1520, except with the written permission of the Administrator of the Transportation Security Administration or the Secretary of Transportation. For U.S. Government agencies, public disclosure is governed by 5 U.S.C. 552 and 49 CFR parts 15 and 1520. This Airport document may also be exempt from disclosure and/or public access under one or more of the following: FSS 119.07; FSS 281.301; FSS 331.22. Unauthorized release may result in civil or criminal penalty.

3.8.1.2. Miami-Dade Fire Rescue, Aviation Division

The Airport Fire Division shall:

1. Report to the ICP, making certain that his/her presence and identity is made known to the IC.
2. Follow aircraft to designated search location and then standby on Alert I status at the station until cleared by IC.
3. Deploy Fire Rescue equipment at the scene for coverage until emergency is over if directed by IC.
4. Direct scene stabilization, treatment, and removal of injured persons at the site of an actual detonation. **Assume lead role as IC during firefighting and life-saving phase.**

3.8.1.3. MDAD Airside Operations, Ramp Control Sr. Agent (Ramp 1)

Upon determination that inspection will be made of the aircraft, baggage, cargo, etc..., remote from the terminal, Ramp 1 shall:

1. Report to the ICP, making certain that his/her presence and identity is made known to the IC.
2. Ramp 1 will establish a 300 foot radius protection zone, centered on the threat aircraft.
3. Advise the MIA ATCT:
 - a. The designated search location where aircraft will be taken (primary or secondary).
 - b. Escort aircraft to designated search location as directed by the IC.
 - c. The Aircraft is in the designated isolation area (primary or secondary).
 - i. Primary Position (Penalty Box)
 1. Close taxiway 'JJ' from taxiway 'M' to taxiway 'Y2' and taxiway N from taxiway HH to taxiway Z.
 - ii. Secondary Position (Midfield Blast Fence)
 1. Close taxiway 'R' from taxiway 'Y' to taxiway 'S'.
4. Advise all Ramp and Access units by radio to standby for instructions.
5. Dispatch Ramp or Access Unit to open building 610.
6. Contact the Operations Division of Airline involved and ascertain if escort is needed for movement of ground handling equipment. If escort is required, provide escort.
7. Under direction of IC, mobilize MDAD buses and in coordination with MDAD Terminal Operations Senior Agent and Airline, establish location to which passengers are to be transported. All buses will remain outside of 300 foot protection zone unless otherwise directed by IC.

Warning: This record contains Sensitive Security Information that is controlled under 49 CFR parts 15 and 1520. No part of this record may be disclosed to persons without a "need to know", as defined in 49 CFR Parts 15 and 1520, except with the written permission of the Administrator of the Transportation Security Administration or the Secretary of Transportation. For U.S. Government agencies, public disclosure is governed by 5 U.S.C. 552 and 49 CFR parts 15 and 1520. This Airport document may also be exempt from disclosure and/or public access under one or more of the following: FSS 119.07; FSS 281.301; FSS 331.22. Unauthorized release may result in civil or criminal penalty.

8. Upon the aircraft reaching the designated isolation area, all passengers will be off-loaded onto buses under control of the Airline Representative(s), for transport (under escort) to the designated location in the terminal. Baggage will be offloaded and transported to building 610, where it will be searched.
9. When the IC has confirmed that the aircraft under search has been cleared, initiate movement of the aircraft from the isolation area.
10. After baggage search, coordinate escort with Ramp or Access vehicles. Allow no vehicles to proceed from building 610 without clearance for radio escort.
11. Direct Ramp or Access vehicles to escort all ground handling equipment, buses, etc., back to the terminal area.
12. Secure building 610.

3.8.1.4. Airline/Aircraft Operator

The Airline or Aircraft Operator involved with the incident shall:

1. Report to the ICP, making certain that his/her presence and identity is made known to the IC.
2. Relocate aircraft to designated inspection area and assist in search by opening all inspection plates and other concealment areas. Shut down air conditioning units in aircraft prior to arrival of Canine Unit(s)
3. Arrange for necessary numbers and types of ground handling equipment to offload and transport passengers, baggage, and cargo.
4. Direct the removal of passengers, baggage, cargo freight, and mail from the aircraft and transport to established location(s).
5. Coordinate search of baggage and cargo with IC.
6. Coordinate search of aircraft with IC.
7. Upon completion of search of aircraft and baggage, transport same as required to resume normal operation. If the flight is an international arrival, transport baggage to U.S. Customs and Border Patrol.
8. Relocate aircraft and ground handling equipment from the designated search location.

3.8.2. Structure/Facility Threats

3.8.2.1. Miami-Dade Police Department, Airport District

In cooperation with the Miami-Dade Aviation Department, Terminal Operations, Landside Operations, and appropriate Operations Security Senior Agent, establishes need for evacuation of area to the isolated. Assumes primary responsibility for and coordinates search activities in all instances. If no explosion has occurred and a real device is located, notify the MDPD Bomb Squad.

Warning: This record contains Sensitive Security Information that is controlled under 49 CFR parts 15 and 1520. No part of this record may be disclosed to persons without a "need to know", as defined in 49 CFR Parts 15 and 1520, except with the written permission of the Administrator of the Transportation Security Administration or the Secretary of Transportation. For U.S. Government agencies, public disclosure is governed by 5 U.S.C. 552 and 49 CFR parts 15 and 1520. This Airport document may also be exempt from disclosure and/or public access under one or more of the following: FSS 119.07; FSS 281.301; FSS 331.22. Unauthorized release may result in civil or criminal penalty.

3.8.2.2. MDPD Bomb Squad

The MDPD Bomb Squad is normally called to the scene only in the event of an explosion or if a suspected device is found. Upon arrival at the scene, the MDPD Bomb Squad will assist the Platoon Commander.

3.8.2.3. Miami-Dade Fire Rescue, Aviation Division


Report to the ICP, making certain that his/her presence and identity is made known to the IC. Stand by with emergency units and equipment until the areas is secured. Direct scene stabilization, treatment, and removal of injured persons at the site of an actual bomb detonation, and assume lead role as IC during fire-fighting and life-saving phase.

3.8.2.4. MDAD Operations and Security

Report to the ICP, making certain that his/her presence and identity is made known to the IC. Assist MDPD by providing personnel and equipment in carrying out area evacuation, area isolation, and other necessary tasks. The location of the incident or suspected device will dictate which appropriate Sr. Agents will report to the ICP.

Warning: This record contains Sensitive Security Information that is controlled under 49 CFR parts 15 and 1520. No part of this record may be disclosed to persons without a "need to know", as defined in 49 CFR Parts 15 and 1520, except with the written permission of the Administrator of the Transportation Security Administration or the Secretary of Transportation. For U.S. Government agencies, public disclosure is governed by 5 U.S.C. 552 and 49 CFR parts 15 and 1520. This Airport document may also be exempt from disclosure and/or public access under one or more of the following: FSS 119.07; FSS 281.301; FSS 331.22. Unauthorized release may result in civil or criminal penalty.

SENSITIVE SECURITY INFORMATION (SSI)



Warning: This record contains Sensitive Security Information that is controlled under 49 CFR parts 15 and 1520. No part of this record may be disclosed to persons without a "need to know" as defined in 49 CFR Parts 15 and 1520, except with the written permission of the Administrator of the Transportation Security Administration or the Secretary of Transportation. For U.S. Government agencies, public disclosure is governed by 5 U.S.C. 552 and 49 CFR parts 15 and 1520. This document may also be exempt from disclosure and/or public access under one or more of the following: FSS 119.07; FSS 291.301; FSS 331.22. Unauthorized release may result in civil or criminal penalty.

Magnetic Declination
8° 5' West (2012)

Annual Rate of Change
5.0' West



MIAMI-DADE COUNTY AVIATION DEPARTMENT

MIAMI INTERNATIONAL AIRPORT

AIRCRAFT PLACEMENT
BOMB THREAT
EXHIBIT 3A

DRAWN BY	DATE	CHECKED BY	DATE	IN CHARGE	SCALE	REVISIONS
111	10-27-2011	J.M.	10-27-2011	J.M.	1:1	1

AIRSIDE OPERATIONS DIVISION

SHEET 1 of 1

11/16/09

Airport Emergency Plan
EXHIBIT 3C**BOMB THREAT
CALL PROCEDURES**

Most bomb threats are received by phone. Bomb threats are serious until proven otherwise. Act quickly, but remain calm and obtain information with the checklist on the reverse of this card.

If a bomb threat is received by phone:

1. Remain calm. Keep the caller on the line for as long as possible. DO NOT HANG UP, even if the caller does.
2. Listen carefully. Be polite and show interest.
3. Try to keep the caller talking to learn more information.
4. If possible, write a note to a colleague to call the authorities or, as soon as the caller hangs up, immediately notify them yourself.
5. If your phone has a display, copy the number and/or letters on the window display.
6. Complete the Bomb Threat Checklist (reverse side) immediately. Write down as much detail as you can remember. Try to get exact words.
7. Immediately upon termination of the call, do not hang up, but from a different phone, contact FPS immediately with information and await instructions.

If a bomb threat is received by handwritten note:

- Call _____
- Handle note as minimally as possible.

If a bomb threat is received by e-mail:

- Call _____
- Do not delete the message.

Signs of a suspicious package:

- No return address
- Excessive postage
- Stains
- Strange odor
- Strange sounds
- Unexpected Delivery
- Poorly handwritten
- Misspelled Words
- Incorrect Titles
- Foreign Postage
- Restrictive Notes

DO NOT:

- Use two-way radios or cellular phone; radio signals have the potential to detonate a bomb.
- Evacuate the building until police arrive and evaluate the threat.
- Activate the fire alarm.
- Touch or move a suspicious package.

WHO TO CONTACT (select one)

- Follow your local guidelines
- Federal Protective Service (FPS) Police
1-877-4-FPS-411 (1-877-437-7411)
- 911

BOMB THREAT CHECKLIST

Date: _____ Time: _____

Time Caller Hung Up: _____ Phone Number where Call Received: _____

Ask Caller:

- Where is the bomb located?
(Building, Floor, Room, etc.)
- When will it go off?
- What does it look like?
- What kind of bomb is it?
- What will make it explode?
- Did you place the bomb? Yes No
- Why?
- What is your name?

Exact Words of Threat:**Information About Caller:**

- Where is the caller located? (Background and level of noise)
- Estimated age:
- Is voice familiar? If so, who does it sound like?
- Other points:

Caller's Voice

- ☐ Accent
- ☐ Angry
- ☐ Calm
- ☐ Clearing throat
- ☐ Coughing
- ☐ Cracking voice
- ☐ Crying
- ☐ Deep
- ☐ Deep breathing
- ☐ Disguised
- ☐ Distinct
- ☐ Excited
- ☐ Female
- ☐ Laughter
- ☐ Lisp
- ☐ Loud
- ☐ Male
- ☐ Nasal
- ☐ Normal
- ☐ Ragged
- ☐ Rapid
- ☐ Raspy
- ☐ Slow
- ☐ Slurred
- ☐ Soft
- ☐ Stutter

Background Sounds:

- ☐ Animal Noises
- ☐ House Noises
- ☐ Kitchen Noises
- ☐ Street Noises
- ☐ Booth
- ☐ PA system
- ☐ Conversation
- ☐ Music
- ☐ Motor
- ☐ Clear
- ☐ Static
- ☐ Office machinery
- ☐ Factory machinery
- ☐ Local
- ☐ Long distance

Threat Language:

- ☐ Incoherent
- ☐ Message read
- ☐ Taped
- ☐ Irrational
- ☐ Profane
- ☐ Well-spoken

Other Information:

Homeland Security

Warning: This record contains Sensitive Security Information that is controlled under 49 CFR parts 15 and 1520. No part of this record may be disclosed to persons without a "need to know", as defined in 49 CFR Parts 15 and 1520, except with the written permission of the Administrator of the Transportation Security Administration or the Secretary of Transportation. For U.S. Government agencies, public disclosure is governed by 5 U.S.C. 552 and 49 CFR parts 15 and 1520. This Airport document may also be exempt from disclosure and/or public access under one or more of the following: FSS 119.07; FSS 281.301; FSS 331.22. Unauthorized release may result in civil or criminal penalty.

SECTION 4

Table of Contents

4. STRUCTURAL FIRES	4 – 2
4.1. INTRODUCTION	4 – 2
4.2. PURPOSE	4 – 2
4.3. ADMINISTRATION AND LOGISTICS	4 – 2
4.4. DEVELOPMENT AND MAINTENANCE	4 – 2
4.5. AUTHORITIES AND REFERENCES	4 – 2
4.6. SITUATION AND ASSUMPTIONS	4 – 2
4.6.1. Structural Fire or Alarm	4 – 2
4.6.2. Fuel Storage Facilities	4 – 3
4.7. OPERATIONS	4 – 3
4.7.1. Structural Fire or Alarm	4 – 3
4.7.1.1. <u>Miami-Dade Fire Rescue, Aviation Division</u>	4 – 3
4.7.1.2. <u>Miami-Dade Police Department, Airport District</u>	4 – 3
4.7.1.3. <u>MDAD Airport Operation Center (AOC)</u>	4 – 4
4.7.1.4. <u>Miami FAA Air Traffic Control Tower (ATCT)</u>	4 – 4
4.7.2. Fuel Storage Facility	4 – 4
4.7.2.1. <u>Miami-Dade Fire Rescue, Aviation Division</u>	4 – 4
4.8. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES	4 – 4
4.8.1. Structural Fire or Alarm	4 – 4
4.8.1.1. <u>Miami-Dade Fire Rescue, Aviation Division</u>	4 – 4
4.8.1.2. <u>Miami-Dade Police Department, Airport District</u>	4 – 5
4.8.1.3. <u>MDAD Operations / Security</u>	4 – 5
4.8.2. Fuel Storage Facility	4 – 5
4.8.2.1. <u>Miami-Dade Fire Rescue, Aviation Division</u>	4 – 5
4.8.2.2. <u>Miami-Dade Police Department, Airport District</u>	4 – 6
4.8.2.3. <u>MDAD Operations / Security</u>	4 – 6

EXHIBITS

- 4A LIFE SAFETY SYSTEMS
- 4B FIRE SAFETY SYSTEMS
- 4C FUEL FARM AREA

4. STRUCTURAL FIRES

4.1. INTRODUCTION

This information outlines the on-airport structural fire response procedures and responsibilities at Miami International Airport. Anyone, upon discovering a fire, shall notify the Miami-Dade Fire Rescue – Aviation Division Watch Office by calling 9-1-1 or by activation of the Alarm System from the Miami Dade Fire Alarm Office or the MIA ATCT Emergency Telephone (Crash Phone).

4.2. PURPOSE

The information contained in this section defines responsibilities and describes actions to be taken in the event of a structural fire. This section represents the Standard Operating Procedures for Miami-Dade Aviation Department employees, airport tenants, users, and other agencies.

4.3. ADMINISTRATION AND LOGISTICS

The management of support resources in the event of emergencies is detailed in the Miami-Dade Aviation Department Continuity of Operations Plan (COOP). This plan establishes a framework for MDAD to prepare for, respond to, mitigate the impacts of, and recover from emergencies.

4.4. DEVELOPMENT AND MAINTENANCE

Revisions to this Structural Fires section shall be maintained by the Division Director, Airside Operations or his/her designee. A true and current copy of the Airport Emergency Plan shall be maintained by the Airside Operations Supervisor, Ramp Control.

4.5. AUTHORITIES AND REFERENCES

Miami-Dade Fire Rescue equipment augmentation will follow Fire Department Strategies for Alarm Assignments III-E-51.

4.6. SITUATION AND ASSUMPTIONS

A structural fire or alarm shall be considered as any fire or alarm involving facilities other than aircraft, i.e. buildings such as terminals and hangars. In the event that an evacuation of the main terminal has been determined, the MIA Emergency Evacuation Plan shall be implemented.

4.6.1. Structural Fire or Alarm

All structures at Miami International Airport are regulated under Title XXXVII, Chapter 633, "Fire Prevention and Control", of the Florida Statutes. This Statute, adopts the National Fire Protection Association (NFPA) Codes and Standards¹⁹. Under these codes and standards, inspections of structure fire systems are performed annually. The Miami-Dade Aviation Department has adopted the Life Safety Master Plan which extends and strengthens NFPA Codes and Standards. Under this Plan, the AOC is the airport's Proprietary Monitoring Station and will make notifications to the airport ARFF Department for any alarms. The locations of MIA's water supply system, hy-

¹⁹ Reference Exhibit 4A, Miami International Airport Life Safety Systems

drant locations, and fire wells, are detailed in Exhibit 4B, Fire Safety Systems.

4.6.2. Fuel Storage Facility

The Fuel Storage Facility at MIA currently carries enough fuel to supply up to approximately four to five days of aircraft activity²⁰. This facility has the capability of holding up to 16 million gallons of Jet A. The fuel is supplied through underground pipeline from Port Everglades to MIA. This facility runs parallel to the Tamiami Canal and Perimeter road, south of NW 21st Street. The entire facility has fixed Fire Protection Systems that can be placed into operation prior to arrival of the Fire Department. The National Emergency Plan, Spill Prevention and Control Plan, and the Facility Response Plan, as well as spill prevention control & countermeasures have been developed to manage emergencies at this facility.

The Fuel Storage facility feeds the West Fuel Tender, a tanker loading station located south of runway 12/30 and west of building 716. This is a nine-bay facility utilizing four UV infrared sensors per bay and a wet based Water / AFFF foam solution system for fire protection.

4.7. OPERATIONS

MDFR will assume the Incident Commander role as the Lead agency at the Incident Command Post for this hazard-specific section. The ICS shall be used throughout the incident.

4.7.1. Structural Fire or Alarm

4.7.1.1. Miami-Dade Fire Rescue, Aviation Division

Miami-Dade Fire Rescue Personnel will be dispatched by the Miami-Dade County Fire Alarm Office. The Fire Department, Airport Division Watch Office shall:

1. Receive alarms via:
 - a. MIA ATCT Emergency Telephone (Crash Phone) (the AOC monitors ATCT drop monitors)
 - b. Radio
2. Notify Senior Fire Officer and dispatch equipment as needed.
3. Notify Miami-Dade Police Department, Airport District, and the AOC.

4.7.1.2. Miami-Dade Police Department, Airport District

The Airport District Desk Operations Center, upon receipt of notification of a fire shall:

1. Relay the call to the Miami-Dade County Fire Alarm Office (or 9-1-1) and the AOC.
2. Dispatch the designated Police personnel and equipment.

²⁰ Reference Exhibit 4C, Miami International Airport Fuel Farm Area

4.7.1.3. MDAD Airport Operations Center (AOC)

The AOC, upon receipt of notification of a fire, shall:

1. Notify Miami-Dade County Fire Alarm Office (or 9-1-1)
2. Notify Police
3. Notify Operations and Security
4. Activate "Blue List"
5. Notify the airline or tenant involved

4.7.1.4. Miami FAA Air Traffic Control Tower (ATCT)

The ATCT upon receipt of notification of a fire shall:

1. Notify the Airport Fire Division Watch Office on Tower Emergency Telephone (Crash Phone) which is monitored by the AOC and Airside Operations.
2. Assist emergency vehicles in facilitating their movement to the scene.

4.7.2. Fuel Storage Facility

4.7.2.1. Miami-Dade Fire Rescue, Aviation Division

Miami-Dade Fire Rescue Personnel will be dispatched by the Miami-Dade County Fire Alarm Office. The Fire Department, Airport Division Watch Office shall:

1. Receive alarms via:
 - a. Tower Emergency Telephone (Crash Phone) the AOC monitors ATCT drop monitors)
 - b. Radio
2. Notify Senior Fire Officer and dispatch equipment as needed.
3. Notify Miami-Dade Police Department, Airport District, and MDAD Airside Operations.

4.8. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES

4.8.1. Structural Fire or Alarm

4.8.1.1. Miami-Dade Fire Rescue, Aviation Division

1. The Airport Fire Units shall make initial fire attack and initiate any required rescue activities essential to protecting life and property until augmented with off-airport Fire Department Units, as per Fire Department Strategy for Alarm Assignments III-E-51.
2. The Incident Commander will determine when there is no further need for ARFF units and return all equipment not needed back to quarters to be replenished and placed back in service.
3. The MDAD Division Director of Airside Operations will be informed of the status of airport equipment, especially if capacity falls below Airport Index E. The Division Director of Airside Operations will decide if action is necessary regarding the classification status of the Airport.

4.8.1.2. Miami-Dade Police Department ,Airport District

The Airport District Police Department shall:

1. Report to the ICP, making certain that his/her presence and identity is made known to the IC.
2. Block off all unauthorized vehicular and pedestrian traffic to allow for an adequate area for firefighting operations.
3. Maintain access routes to "emergency area" for emergency equipment responding from off-airport locations.
4. Set up and implement plans for crowd control and perimeter lines at the fire scene.
5. Set up and implement plans for rerouting traffic.
6. Secure scene for investigation.

4.8.1.3. MDAD Operations / Security

1. MDAD Operations will establish liaison at the ICP in conjunction with the IC. Assist by providing personnel and equipment in carrying out area evacuation, isolation, and other necessary tasks as directed by IC and the MIA Emergency Evacuation Plan.
2. Airside Operations will staff rendezvous point(s) as directed by IC and assist with escort for additional support equipment. All vehicles responding to an on-airport emergency shall enter only at the designated rendezvous point(s). Dependent upon the location of the incident, the IC shall select the appropriate rendezvous point(s). The Airport Police, in coordination with the MDAD Airside Operations Division will control access through these points.
3. MDAD will escort support equipment and control traffic to the affected area. Ramp 1, will control aircraft traffic to affected areas if terminal aircraft parking locations are affected.

4.8.2. Fuel Storage Facility

4.8.2.1. Miami-Dade Fire Rescue, Aviation Division

1. The Airport Fire Units shall make initial fire attack and initiate any required rescue activities essential to protecting life and property until augmented with off-airport Fire Department Units, as per Fire Department Strategy for Alarm Assignments III-E-51.
2. The Incident Commander will determine when there is no further need for ARFF units and return all equipment not needed back to quarters to be replenished and placed back in service. Equipment kept at the scene should be placed back in service as soon as possible.
3. The MDAD Division Director of Airside Operations will be informed of the status of airport equipment, especially if capacity falls below Air-


port Index E. The Division Director of Airside Operations will decide if action is necessary regarding the classification status of the Airport.


4.8.2.2. Miami-Dade Police Department ,Airport District

1. The Airport District Police Department shall report to the ICP, making certain that his/her presence and identity is made known to the IC.
2. Establish perimeter around the facility and begin evacuation as instructed by the IC.
3. Block off all unauthorized vehicular and pedestrian traffic to allow for an adequate area for firefighting operations.
4. Maintain access routes to "emergency area" for emergency equipment responding from off-airport locations.
5. Set up and implement plans for crowd control and perimeter lines at fire scene.
6. Set up and implement plans for rerouting traffic.
7. Secure scene for investigation.

4.8.2.3. MDAD Operations / Security

1. MDAD Operations will report to the ICP, making certain that his/her presence and identity is made known to the IC. Provide personnel and equipment to carry out area evacuation, isolation, and other necessary tasks as directed by IC. Ramp 1 will coordinate with FAA ATCT if airspace isolation becomes necessary.
2. In conjunction with the Fire Department, MDAD Environmental will initiate control and clean up of any areas affected by fuel.






Copyright © 2012

Warning: This record contains Sensitive Security Information that is controlled under 49 CFR parts 15 and 1520. No part of this record may be disclosed to persons without a "need to know", as defined in 49 CFR Parts 15 and 1520, except with the written permission of the Administrator of the Transportation Security Administration or the Secretary of Transportation. For U.S. government agencies, public disclosure is governed by 5 U.S.C. and 552 CFR parts 15 and 1520. This document may also be exempt from disclosure and/or public access under one or more of the following: FSS 119.07; FSS 281.301; FSS 331.22. Unauthorized release may result in civil or criminal penalty.

LEGEND

- EXISTING WATER MAIN
- FH — EXISTING FIRE HYDRANT
- FIRE WELLS



Magnetic Declination
6° 5' West (2012)
Annual Rate of Change
5.5' West

MIAMI-DADE COUNTY AVIATION DEPARTMENT
MIAMI INTERNATIONAL AIRPORT

MIAMI INTERNATIONAL AIRPORT FIRE SAFETY SYSTEM EXHIBIT 4B

DRAWN BY	DATE	DESIGNED BY	DATE	IN CHARGE	SCALE	FILENAME
NGM/HJL	03-25-2019	JM	03-25-2019	LCM/D		EXHIBIT 4B REV.04

AIRSIDE OPERATIONS DIVISION

SHEET 1 of 1



Warning: This record contains Sensitive Security Information that is controlled under 49 CFR parts 15 and 1620. No part of this record may be disclosed to persons without a "need to know", as defined in 49 CFR parts 15 and 1620, except with the written permission of the Administrator of the Transportation Security Administration or the Secretary of Transportation. For U.S. Government agencies, public disclosure is governed by 5 U.S.C. 552 and 49 CFR parts 15 and 1620. This document may also be exempt from disclosure under public access under one or more of the following: FSS 119.07; FSS 261.301; FSS 351.22. Unauthorized release may result in civil or criminal penalty.

SECTION 5

Table of Contents

NATURAL DISASTERS	5-3
5.1. HURRICANES	5-3
5.1.1. TERMS AND DEFINITIONS	5-3
5.1.2. PURPOSE	5-3
5.1.3. ADMINISTRATION AND LOGISTICS	5-3
5.1.4. DEVELOPMENT AND MAINTENANCE	5-4
5.1.5. AUTHORITIES AND REFERENCES	5-4
5.1.6. SITUATION AND ASSUMPTIONS	5-4
5.1.6.1. Advisory	5-4
5.1.6.2. Intermediate Advisory	5-4
5.1.6.3. Local Statements	5-4
5.1.6.4. Severe Weather Warning	5-4
5.1.6.5. Hurricane Watch	5-4
5.1.6.6. Hurricane Warning	5-5
5.1.7. OPERATIONS	5-5
5.1.8. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES	5-6
5.1.8.1. Miami-Dade Fire Rescue – Aviation Division	5-6
5.1.8.1.1. <u>Aid Stations</u>	5-6
5.1.8.1.2. <u>Fire Teams</u>	5-6
5.1.8.2. Miami-Dade Police Department, Airport District	5-6
5.1.8.2.1. <u>Mobilization</u>	5-6
5.1.8.3. Operations Personnel	5-7
5.1.8.3.1. <u>During Emergency</u>	5-7
5.1.8.3.2. <u>Post Emergency</u>	5-7
5.1.8.4. Tenant Responsibilities	5-7
5.1.8.4.1. <u>Hurricane Watch</u>	5-7
5.1.8.4.2. <u>Severe Weather Warning and/or Hurricane Warning</u>	5-7
5.1.8.5. Properties Division	5-8
5.1.8.6. Deputy Director, Operations; Assistant Director, Facilities Management; Assistant Director, Operations	5-8
5.1.8.6.1. <u>Pre-Emergency</u>	5-8
5.1.8.6.2. <u>During Emergency</u>	5-9
5.1.8.6.3. <u>Post Emergency</u>	5-9
5.1.8.7. Emergency Purchase of Materials or Services	5-9

5.2. FLOODING	5-9
5.2.1. INTRODUCTION	5-9
5.2.1.1. Risk Area	5-9
5.2.1.2. Risk Assessment.....	5-10
5.2.2. PURPOSE	5-10
5.2.3. SITUATION AND ASSUMPTIONS	5-10
5.2.3.1. Susceptibility.....	5-10
5.2.3.2. Impact	5-11
5.2.3.3. Review of Airport Access	5-11
5.2.3.4. Review of Airport Structures	5-11
5.2.3.5. Review of Airport Utilities	5-11
5.2.3.6. Review of Worse Case Scenarios	5-11
5.2.4. OPERATIONS	5-11
5.2.5. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES	5-12
5.2.6. ADMINISTRATION AND LOGISTICS	5-12
5.2.7. PLAN DEVELOPMENT	5-12
5.2.8. AUTHORITIES AND REFERENCES	5-12
5.2.9. SOPS AND CHECKLISTS	5-13

NATURAL DISASTERS

5.1. HURRICANES

The natural disasters to which airports may be subjected include storms, floods, hurricanes, earthquakes, and seismic sea waves. The vulnerability of an airport to any of these will be affected by geography, since certain areas or belts often define the more dangerous occurrences. Miami International Airport can expect natural disasters from severe weather, which is covered in the following paragraphs.

5.1.1. TERMS & DEFINITIONS

The Saffir-Simpson Hurricane Wind Scale is a 1 to 5 categorization based on the hurricane's intensity at the indicated advisory time.

Category One Hurricane: Winds 74-95 mph (64-82 knots) and storm surge generally 4-5 ft above normal.

Category Two Hurricane: Winds 96-110 mph (83-95 knots) and storm surge generally 6-8 feet above normal.

Category Three Hurricane: Winds 111-129 mph (96-112 knots) and storm surge generally 9-12 ft above normal.

Category Four Hurricane: Winds 130-156 mph (113-136 knots) and storm surge generally 13-18 ft above normal.

Category Five Hurricane: Winds greater than 156 mph (136 knots) and storm surge generally greater than 18 ft above normal.

Tropical Cyclone: A warm core, low pressure system without any "front" attached, which develops over the tropical or sub tropical waters, and has an organized circulation about a well defined center.

Tropical Disturbance: A discrete tropical weather system of apparently organized convection -- generally 100 to 300 nm in diameter -- originating in the tropics or subtropics, having a non-frontal migratory character, and maintaining its identity for 24 hours or more.

Tropical Depression: A tropical cyclone in which the maximum sustained surface wind speed (using the U.S. 1-minute average) is 33 knots (38 mph) or less.

Tropical Storm: A tropical cyclone in which the maximum sustained surface wind speed (using the U.S. 1-minute average) ranges from 34 knots (39 mph) to 63 knots (73 mph).

Hurricane: A tropical cyclone in which the maximum sustained surface wind (using the U.S. 1-minute average) is 64 knots (74 mph) or more. The term hurricane is used for Northern Hemisphere tropical cyclones east of the International Dateline to the Greenwich Meridian.

5.1.2. PURPOSE

The information contained in this section defines responsibilities and describes actions to be taken in the event of natural disasters. This section represents the Standard Operating Procedures for Miami-Dade Aviation Department employees, airport tenants, users, and other agencies.

5.1.3. ADMINISTRATION AND LOGISTICS

The management of support resources in the event of emergencies is detailed in the Miami-Dade Aviation Department, Continuity of Operations Plan (COOP). This plan establishes a framework for MDAD to prepare for, respond to, mitigate the impacts of, and recover from emergencies.

5.1.4. DEVELOPMENT AND MAINTENANCE

Revisions to this Natural Disasters section shall be maintained by the Division Director, Airside Operations or his/her designee. A true and current copy of the Airport Emergency Plan shall be maintained by the Airside Operations Supervisor, Ramp Control.

5.1.5. AUTHORITIES AND REFERENCES

Miami-Dade Fire Rescue equipment augmentation will follow Fire Department Strategies for Alarm Assignments III-E-51.

5.1.6. SITUATION AND ASSUMPTIONS

The hurricane season in the Atlantic, Caribbean, and Gulf of Mexico runs from June 1 to November 30. The U.S. National Weather Service observes the development of weather patterns, predicts and tracks the movement of storms, estimates the buildup of wind velocity, and notifies the public of potential dangers resulting there from, in the following manner:

5.1.6.1. Advisory

The National Weather Service, a component of the National Oceanographic and Atmospheric Administration (NOAA) issues all advisory messages, watches and warnings via the National Hurricane Center. An advisory gives details concerning any tropical storm or hurricane in effect, their locations, intensity and movement as well as precautions that should be taken. (*see also "Hurricane Warning", paragraph 5.4.6.*).

5.1.6.2. Intermediate Advisory

An intermediate advisory is a public release from a U.S. National Weather Service Hurricane Warning Center during periods between regular advisories, giving latest details on the tropical storm or hurricane.

5.1.6.3. Local Statements

A public release prepared by local National Weather Service offices in or near a threatened area giving specific details for its county/parish warning area on (1) weather conditions, (2) evacuation decisions made by local officials, and (3) other precautions necessary to protect life and property.

5.1.6.4. Severe Weather Warning

A formal Weather Service message advising the possibility of severe weather in specified areas including severe thunderstorms, high winds, heavy rainfall, hail, and the possibility of tornadoes.

5.1.6.5. Hurricane Watch

An announcement that sustained winds of 64 knots (74 mph) or higher are *possible* within the specified area. The hurricane watch is issued 48 hours in advance of the anticipated onset of tropical storm force winds.

5.1.6.6. Hurricane Warning

An announcement that sustained winds of 64 knots (74 mph) or higher are *expected* somewhere within the specified area. The warning is issued 36 hours in advance of the anticipated onset of tropical storm force winds. The warning can remain in effect when dangerously high water or a combination of dangerously high water and waves continue, even though winds may be less than hurricane force.

5.1.7. OPERATIONS

Upon receipt of hurricane information that suggests the possibility that it may threaten the South Florida area, steps shall be taken to insure readiness on the part of all airport occupants.

Precautionary action shall be progressive as the threat strengthens based on the National Weather Service reports. Preparation must not be left to the last minute. Airport occupants have the responsibility, not only to protect their own property, but also to insure that material blown from their area will not endanger the life and property of others.

A Hurricane Command Post (HCP) will be established in the Concourse "E" 5th floor Conference Room. During a hurricane, storm or emergency alerts, a communications system will be available in the HCP. The communications system will be comprised of an ATCT frequency monitor, ten (10) telephone lines, and 800MHz radios.

The IS/T Technical Shop supplies the HCP with spare 800MHz radios (maximum of 100 units). MDAD uses the 800MHz Radio System for daily operations as do the rest of the County departments. These radios have emergency channels already programmed into the units, and those channels are activated by ETSD (Enterprise Technology Service Department) at the time of the emergency. Police, Fire, and other County Departments will all be able to communicate with each other via the 800MHz system.

If part of the 800MHz system is damaged, MDAD will still be able to use the radios in "Local" mode. The local mode will be transparent to most users, and the radios will only transmit/receive around the airport vicinity (not County-Wide).

In the unlikely event that the 800MHz system is totally inoperative, the IS/T Technical Shop will deploy 400MHz radios to the HCP (maximum of 100 units). The HCP will distribute these radios as they deem necessary. The Technical Shop maintains 400MHz repeaters for such emergencies.

Personnel of the following Divisions will man the HCP, under the direction of the Deputy Aviation Director of Operations or his/her representative.

1. Police
2. Fire
3. Maintenance
4. Airside Operations
5. Landside Operations
6. Terminal Operations
7. Security
8. PIO

Overall, command coordination will emanate from this Aviation HCP. For specific details, each MDAD Division will refer to the Miami-Dade County Aviation Department Hurricane Procedures Manual (updated yearly).

5.1.8. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES

5.1.8.1. Miami-Dade Fire Rescue – Aviation Division

When emergency mobilization is necessary, it shall be in accordance with MDR P&P III-P-4 “*Hurricane Procedures*”.

5.1.8.1.1. Aid Stations

Due to the possibility of cancelled flights, a large amount of potentially stranded passengers is anticipated. To provide the best emergency medical coverage possible under these conditions, two (2) Aid Stations shall be set up in the Terminal. Two (2) Fire Department EMS trained personnel shall man each Aid Station.

Work to set up Aid Station should begin approximately four (4) hours in advance of forecast gale winds of 60 mph (52 knots).

5.1.8.1.2. Fire Teams

To provide fire suppression capability, two (2) Fire Teams, staffed with five (5) Fire Department Personnel each, will be assigned to Concourses ‘D’ and ‘F’ respectively or as determined by the Airport Rescue Fire Chief.

5.1.8.2. Miami-Dade Police Department, Airport District

5.1.8.2.1. Mobilization

When emergency mobilization is necessary, it shall be in accordance with MDPD SOP 4-7, “Mobilization and Emergency Operations” and the MDPD Airport District Hurricane Preparedness Plan.

5.1.8.3. Operations Personnel

Operations personnel, Airside Operations, Landside Operations, Terminal Operations, and Security will provide general supervision of the activities at the airport to assure compliance with good operating practices in preparation for the oncoming emergency.

5.1.8.3.1. During Emergency

All available Aviation Department personnel will be subject to call for assistance due to a storm.

5.1.8.3.2. Post Emergency

As soon as the County Manager's office issues the "All Clear" message, all personnel should either report for work for reinstatement of regular schedule or special assignment as conditions warrant.

Effort must be made to return the airport to normal operation as quickly as possible.

5.1.8.4. Tenant Responsibilities

All tenants are responsible for the protection and securing of property on their leaseholds and in addition, their property, including aircraft, vehicles, and aircraft service equipment, which is located at various places in public areas such as parking areas, terminal ramps, etc...

5.1.8.4.1. Hurricane Watch

Effective with the issuance of a Hurricane Watch by the National Hurricane Center, tenants should survey their leasehold and assure that:

1. Area is clean – all trash or loose material is removed from the premises.
2. Lightweight and moveable equipment is placed under shelter or otherwise secured.
3. Permanent appurtenances such as doors, signs windows, fences, gates, etc..., checked and secured to withstand high wind velocities.

5.1.8.4.2. Severe Weather Warning and/or Hurricane Warning

Effective with the issuance of Severe Weather Warning and/or Hurricane Warning:

1. Secure all equipment.
2. Relocate flyable aircraft to other geographical areas, place under suitable shelter, or secure as appropriate.
3. Protect breakables such as light globes, windows, etc...
4. Cooperate with Aviation Department personnel in the completion of necessary actions for the greatest possible protection of all.
5. Private, executive, or other aircraft parked on non-leased Aviation Department property will be the responsibility of the owner or operator.

6. If it becomes necessary for MDAD emergency crews to tie-down or secure property on leased portions of the airport due to the negligence or refusal of a lessee to take proper precautionary measures or to provide service for private property items on Aviation Department property, tenants or other responsible parties will be billed for the costs incurred by the Department. The Aviation Department will not assume responsibility for damage caused to aircraft or other effects.

5.1.8.5. Properties Division

A seasonal written directive will be distributed at the beginning date of the Hurricane Season (June 1) to all tenants and operators, reminding them of the necessity of cleaning up and securing their property in anticipation of the storm season.

Within a reasonable time, MDAD Property Management will make a check in collaboration with the Airport Fire Division and Airside Operations as a follow-up on the directive and persons notified as to nonconformance.

5.1.8.6. Deputy Director, Operations; Assistant Director, Facilities Management; Assistant Director, Operations

Upon receipt of the Hurricane Watch concerning South Florida and the Aviation Department Airports:

1. Notify the Aviation Director, Deputy Aviation Director, all Assistant Directors, and Division Directors of the alert and the need for immediate implementation of precautionary action.
2. Invoke the provisions for emergency personnel availability, their assignments, and preparation of their personal property to permit call to airport assignment if necessary.
3. Alert all airport tenants and users to the impending threat and the need for preparation steps.
4. Assume readiness of the HCP (5th Floor Conference Room – “E” Terminal) with functioning communications equipment and supplies to permit 24-hour operation for some indefinite period.

5.1.8.6.1. Pre-Emergency

Upon receipt of Hurricane Warning:

1. Communicate status report to all concerned and call for final preparation action in all quarters.
2. Initiate evacuation of all flyable aircraft and post Airport Operations Sr. Agents / Agents on detail to insure compliance and report results.
3. Direct standby force of Airport Police, Fire, Operations, and Maintenance personnel to meet the pending crisis.

5.1.8.6.2. During Emergency

1. Direct operations of the Aviation HCP.
2. Issue instructions to Airport Police, Fire Operations, and Maintenance Supervisors on duty, as developments dictate.
3. Advise Aviation Public Information Officer (PIO) of storm developments for dissemination to the media as appropriate.

5.1.8.6.3. Post Emergency

1. Initiate activities of a Damage Assessment Team and restore normal airport use based on Team findings and report corrective action by responsible entities.
2. Call for regular employees manning schedules.
3. Notify all airport tenants and users of the restoration progress and the operational status of the airfield and landside service activities.
4. Direct preparation of Damage Assessment Report for submission to the County Manager's Office.
5. Recertify AOA if necessary.
6. Implement MDAD Continuity of Operations Plan (COOP), latest edition if necessary.

5.1.8.7. Emergency Purchase of Materials or Services

In the event of a Hurricane or other disaster, the Director, Deputy Aviation Director, or Assistant Directors, may on their sole initiative order such material or services as they in their professional opinion feel necessary.

Close coordination will be required between the individuals set forth above, so there will be no duplication of services or materials. All authorizations must, after the fact, be documented in writing and staffed through the appropriate channels. Actions thereafter will be effected to gain ratification of the Board if necessary.

Critical type repair contractors (i.e. roofing) shall be hired before a hurricane strikes so that crews are ready to commence repairs immediately after passage of the storm.

5.2. FLOODING

5.2.1. INTRODUCTION

5.2.1.1. Risk Area

Miami-Dade County is located in a unique geographical area. It is particularly susceptible to flooding from major rain events and storm surge. Miami International Airport is categorized as FEMA Zone X site and corresponds to areas protected from the 100-year flood by a Stormwater Management Plan.

5.2.1.2. Risk Assessment

MIA's susceptibility to flooding was assessed by developing a Stormwater Master Plan. The MIA Stormwater Master Plan was originally developed utilizing the En-

Environmental Protection Agency's Stormwater Management Model (SWMM) and has been updated to incorporate new projects built under MIA Capital Improvement Program. This program provides definitions, computer models, design criteria, and standard details for water quantity and water quality, which are mandatory specifications for projects under design. Development and implementation of this plan is authorized through master permits and programs obtained from the South Florida Water Management District (SFWMD), Florida Department of Environmental Protection (FDEP), and the Miami-Dade County Permitting, Environment and Regulatory Affairs (PERA).

The Stormwater Management System (SWMS) at MIA includes four Watersheds, five Outfalls, over 60 miles of pipe, and more than 2,000 structures. The Storm Water Pollution Prevention Plan for Industrial Activities is part of the SWMS and describes the best management practices for each airport facility. Every tenant is required to conform to these standards.

Watershed	Area (Acres)	Basins	Conduits	Nodes	Outfall No.	Discharge (CFS)
Outfall No. 1	62	100	60	120	1	66
NW Cargo	450	34	40	80	5	184
MIAD	885	30	40	80	4	585
Terminal Area	1334	60	100	200	2 & 3	1950
Total	2731	224	240	480	5	2785

Table 1. System Components

The airport drainage is controlled through a system of peripheral inlets, grit chambers, oil/water separators, outfall booms, skimmers, airfield swales, and a 20 Acre storm water management pond. This system enhances water quality and attenuate airport discharge through Outfall No. 5 that leads to the Miami River, Ludlam Canal, and the C4 Canal.

5.2.2. PURPOSE

The information contained in this section defines responsibilities and describes actions to be taken in the event that flooding occurs at the airport. This section represents the Standard Operating Procedures (SOPs) for Miami-Dade Aviation Department employees, airport tenants, users, and other agencies.

5.2.3. SITUATION AND ASSUMPTIONS

5.2.3.1. Susceptibility

The Stormwater Master Plan evaluated several different storm events for the various components of the system. The 10 year – 72 hour criteria for secondary storm water components; the 25 year – 72 hour criteria for our primary system components; and the 100 year – 72 hour criteria for our flood stage elevations. In general, our pavement elevation for runways average one (1) to one and a half (1½) feet above flood plain level and six (6) to ten (10) inches on our taxiways.

5.2.3.2. Impact

MIA's storm water management system was designed to not impact the surrounding communities. The flooding of local communities outside of airport property will be addressed by the Miami-Dade County Department of Emergency Management & Homeland Security in coordination with the South Florida Water Management District (SFWMD), Local, State, and Federal emergency response agencies.

MIA is a self-sustained entity with on-field emergency services, which includes Miami-Dade Fire Rescue, Airport Division; Miami-Dade County Police Department, Airport District; and Miami-Dade Maintenance Division. If conditions are such that off-airport support equipment is required for response and recovery, additional support can be accessed from County or surrounding cities through Mutual Aid Agreements.

5.2.3.3. Review of Airport Access

Central Boulevard is MIA's major roadway in and out of the airport. Current assessment of Central Boulevard determined that this artery is not susceptible to flooding.

5.2.3.4. Review of Airport Structures

Miami-Dade Aviation Department guidelines require that any new airport structure is built one foot above the 100 year flood plain elevation. Several low lying facilities, built prior to FEMA and MIA Stormwater Master Plan requirements were developed, have been identified within the Northeast quadrant of the airfield. This area is being developed and the new elevation and drainage requirements are being implemented.

5.2.3.5. Review of Airport Utilities

MIA does not anticipate any issues with water and sewer systems due to the elevation of our pump stations. All auxiliary generators are above the 100 year flood plain elevation. Due to the level of our water table, most utilities throughout the airfield are under water and are built to operate under these conditions.

5.2.3.6. Review of Worse Case Scenarios

Review of this condition, MIA expects to have isolated impact of low lying areas and would result in a diminished level of service to those areas. MIA's runways and taxiways system would not be impacted.

5.2.4. OPERATIONS

MIA's highest risk of flooding is from severe meteorological conditions such as tropical cyclones (hurricanes) and tropical storms. The MDAD Hurricane & Emergency Preparedness and Response Procedures Manual (updated annually), provides SOPs and checklists for this emergency.

5.2.5. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES

MIA is a FEMA zone X site and corresponds to areas protected from the 100-year flood by a Stormwater Management Plan. Flooding impacts on this airport would be minimal and will not affect any runways, taxiways, or airport structures. If conditions develop to warrant emergency response, the established MDAD Hurricane & Emergency Preparedness and Response Procedures Manual procedures shall be followed by all sections of the Miami-Dade Aviation Department; Miami-Dade Fire Rescue, Airport Division; the Miami-Dade Police Department, Airport District; and all tenants and operators.

Inspection of all MDAD owned property on the Airfield, to include NAVAIDS, ARFF Stations, Airfield Facilities, Hangars, and Office buildings, will be inspected by MDAD Facilities Maintenance in coordination with MDAD Engineering Division, and MDAD Real Estate Management and Development Division. MIA FAA shall inspect all FAA owned, operated, and maintained facilities for damage and operability.

5.2.6. ADMINISTRATION AND LOGISTICS

The management of support resources in the event of emergencies is detailed in the Miami-Dade Aviation Department, Continuity of Operations Plan (COOP). This plan establishes a framework for MDAD to prepare for, respond to, mitigate the impacts of, and recover from emergencies.

5.2.7. PLAN DEVELOPMENT

This Airport Emergency Plan was created in coordination with the Miami-Dade Police Department, Miami-Dade Fire Rescue, Miami-Dade Aviation Department, and all other entities that have responsibilities under this plan. Review of this plan is made once every 12 consecutive calendar months through table-top drills and once every 36 consecutive calendar months, through a full-scale airport emergency exercise. Revisions to this Plan shall be maintained by the Division Director, Airside Operations or his/her designee. A true and current copy of this Airport Emergency Plan shall be maintained by the Airside Operations Supervisor, Ramp Control.

5.2.8. AUTHORITIES AND REFERENCES

The following references represent guidelines used to address flood related issues on this airport.

- FAA AC 150/5320-5, Surface Drainage Design
- FAA AC 150/5320-15, Management of Airport Industrial Waste
- South Florida Water Management District (SFWMD), regulatory requirements and permitting
- Permitting, Environment and Regulatory Affairs (PERA), regulatory requirements.
- The State Floodplain Management Program of the Florida Building Code
- Miami-Dade Building & Zoning, regulatory requirements
- MDAD Design Guideline Manual
- MIA Stormwater Master Plan

5.2.9. SOPS AND CHECKLISTS

If conditions develop to warrant emergency response, the established MDAD Hurricane & Emergency Preparedness and Response Procedures Manual procedures shall be followed by all sections of the Miami-Dade Aviation Department; Miami-Dade Fire Rescue, Airport Division; the Miami-Dade Police Department, Airport District; and all tenants and operators.

SECTION 6

Table of Contents

6. HAZARDOUS MATERIALS INCIDENTS	6 – 2
6.1. INTRODUCTION	6 – 2
6.2. PURPOSE	6 – 2
6.3. ADMINISTRATION AND LOGISTICS	6 – 2
6.4. DEVELOPMENT AND MAINTENANCE	6 – 2
6.5. AUTHORITIES AND REFERENCES	6 – 2
6.6. SITUATION AND ASSUMPTIONS	6 – 3
6.7. OPERATIONS	6 – 3
6.7.1. Notification	6 – 3
6.7.2. Dispatch – Watch Office	6 – 3
6.7.2.1. <u>Dispatch – FAO</u>	6 – 3
6.8. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES	6 – 3
6.8.1. Miami-Dade Fire Rescue Department – Aviation Division	6 – 3
6.8.2. Miami-Dade Police Department – Airport District	6 – 4
6.8.3. MIA ATCT	6 – 4
6.8.4. MDAD Airport Operations Center (AOC)	6 – 4
6.8.5. MDAD Public Information Officer (PIO)	6 – 4
6.8.6. Miami-Dade County Health Department	6 – 4
6.8.7. Aircraft Owner/Operator or Responsible Party	6 – 4
6.8.8. Miami-Dade County Department of Emergency Management & Homeland Security (County EOC)	6 – 5
6.8.9. U.S. Military	6 – 5

6. HAZARDOUS MATERIALS INCIDENTS

6.1. INTRODUCTION

Accidental spillage of hazardous materials in commercial shipment and onboard aircraft are covered in this section. If spillage occurs, the primary concern is the prevention of spreading these materials by vehicles or pedestrians moving through the area. Immediate action should be taken to:

1. Seal the contaminated areas by closing windows, doors, and shutting down ventilation systems and
2. restrict further access

The MDRF Aviation Division provides 24-hour personnel (Platform 59) with detection equipment available to respond.

6.2. PURPOSE

The information contained in this section defines responsibilities and describes actions to be taken in the event a hazmat incident in the vicinity of the airport. This section represents the Standard Operating Procedures for Miami-Dade Aviation Department employees, airport tenants, users, and other agencies.

6.3. ADMINISTRATION AND LOGISTICS

The management of support resources in the event of emergencies is detailed in the Miami-Dade Aviation Department, Continuity of Operations Plan (COOP). This plan establishes a framework for MDAD to prepare for, respond to, mitigate the impacts of, and recover from emergencies.

6.4. DEVELOPMENT AND MAINTENANCE

Revisions to this Hazardous Materials Incidents section shall be maintained by the Division Director, Airside Operations or his/her designee. A true and current copy of the Airport Emergency Plan shall be maintained by the Airside Operations Supervisor, Ramp Control.

6.5. AUTHORITIES AND REFERENCES

Initial response to any aircraft accident, emergency, or potential emergency, will follow the guidelines established by Letter of Agreement between the Miami ATC Tower and the Miami-Dade Aviation Department, "FAA Emergency Procedures", reference Section 14, "MIA ATCT Functions Relating to Emergency Actions", Exhibit 14A. Miami-Dade Fire Rescue equipment augmentation will follow Fire Department Strategies for Alarm Assignments III-E-51.

6.6. SITUATION AND ASSUMPTIONS

Numerous operations, such as maintenance, shipping, and storage, involve hazardous materials at MIA. When dealing with hazardous materials, response personnel shall limit their actions to the isolation/stabilization of the materials and not be directly involved in the cleanup procedures. In the event that an evacuation of the main terminal has been determined, the MIA Emergency Evacuation Plan shall be implemented.

6.7. OPERATIONS

MDFR will assume the Incident Commander role as the lead agency at the Incident Command Post for this type of incident. The ICS shall be used throughout the incident.

6.7.1. Notification

The first person becoming aware of a hazmat incident should immediately notify the Miami-Dade Fire Rescue Department via 911. If the incident is air-side, notify the ATCT. ATCT will notify the MDFR, Aviation Division Watch Office, of this emergency via the emergency phone. Airport Police and (the AOC) are simultaneously notified via the Emergency Phone monitors.

6.7.2. Dispatch – Watch Office

The MDFR Watch Office will then confirm notification to the MDFR Fire Alarm Office where dispatch of appropriate units will continue per MDFR Strategy for Alarm Assignment. Platform 59 would be the initial responding MIA unit.

6.7.2.1. Dispatch – FAO

Miami-Dade Fire Rescue Policy and Procedure, “*Strategy for Alarm Assignment, III-E-51, III, Pre-established assignment packages VI, Hazardous Materials Incidents*”, shall supplement this initial dispatch with resources appropriate for the quantity and type of material.

6.8. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES

At present, MIA will implement the Hazardous Materials Operating Procedure, III-C-10, currently used throughout Miami-Dade Fire Rescue. Further MDFR hazard specific standard operating procedures shall also be followed.

6.8.1. Miami-Dade Fire Rescue Department – Aviation Division

The MDFR Department – Airport Division shall:

1. Respond to the emergency as dispatched.
2. The IC will assess the situation and request the Hazardous Materials Taskforce if needed.
3. Evacuate all personnel/civilians to area of safe refuge.
4. Confirm Fire Alarm Office has made appropriate notifications if needed.
5. Notify Ramp 1 to close specific areas.

6.8.2. Miami-Dade Police Department – Airport District

The MDPD – Airport District shall:

1. Control vehicular and pedestrian traffic.
2. Set perimeter and establish cordon around emergency area to prevent hazardous material from being spread by vehicle or pedestrian traffic.
3. Assist as necessary in evacuating area.
4. Support MDFR personnel as requested.

6.8.3. MIA ATCT

The MIA ATCT will not permit other aircraft to land, takeoff, or taxi through possible closed area(s).

6.8.4. MDAD Airport Operations Center (AOC)

The AOC shall notify the following:

1. Miami-Dade Fire Rescue Department – Airport Division
2. Miami-Dade Police Department – Airport District
3. MDAD Airside Operations (Ramp One)
4. MDAD Landside Operations and Terminal Operations Control Offices
5. MDAD Security

6.8.5. MDAD Public Information Officer (PIO)

The MDAD PIO shall follow the guidelines for public information news releases.

1. The courier accompanying a commercial shipment shall be responsible for providing the information for public statements.
2. If a governmental agency is involved, that agency or its representative will be responsible for assisting the Incident Commander with making the public statements.
3. If the courier or agency representative is incapacitated, responsibility for gathering the information for news releases will be assumed by the Incident Commander.
4. No Statement shall be released without the final review and consent of the Incident Commander.

6.8.6. Miami-Dade County Health Department

The Miami-Dade County Health Department shall:

1. Contact Miami-Dade Police Department – Airport District at Rendezvous point(s) for escort to emergency area.
2. Conduct radiological assistance.

6.8.7. Aircraft Owner/Operator or Responsible Party

The Aircraft Owner/Operator or responsible party shall provide support as needed in response to type and nature of incident.

6.8.8. Miami-Dade County Department of Emergency Management & Homeland Security (County EOC)

The Miami-Dade County Department of Emergency Management & Homeland Security shall:

1. Contact Miami-Dade Police Department – Airport District at Rendezvous point(s) for escort to emergency area.
2. Coordinate with Miami-Dade County Health Department and assist with response.
3. Provide communications for coordination of operations with local, state, and federal resources.

6.8.9. U.S. Military

The U.S. Military shall assume role as lead agency within the Unified Command if a military aircraft is involved.

Airport Emergency Plan
**SABOTAGE, HIJACK, AND OTHER
UNLAWFUL INTERFERENCE WITH OPERATION**

SECTION 7
Table of Contents

7. SABOTAGE, HIJACK, AND OTHER UNLAWFUL INTERFERENCE WITH OPERATIONS.	7 – 2
7.1. INTRODUCTION	7 – 2
7.2. PURPOSE	7 – 2
7.3. ADMINISTRATION AND LOGISTICS	7 – 2
7.4. DEVELOPMENT AND MAINTENANCE	7 – 2
7.5. AUTHORITIES AND REFERENCES	7 – 2
7.6. SITUATION AND ASSUMPTIONS	7 – 3
7.7. OPERATIONS	7 – 3
7.7.1. Miami-Dade County Aviation Department	7 – 3
7.7.2. Penalty Box	7 – 3
7.8. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES	7 – 4
7.8.1. Miami-Dade Police Department – Airport District	7 – 4
7.8.2. Miami-Dade Fire Rescue – Aviation Division	7 – 4
7.8.3. Miami ATCT	7 – 4
7.8.4. MDAD Operations	7 – 4
7.8.5. Airline/Aircraft Operator or Designated Representative	7 – 4

Warning: This record contains Sensitive Security Information that is controlled under 49 CFR parts 15 and 1520. No part of this record may be disclosed to persons without a "need to know", as defined in 49 CFR Parts 15 and 1520, except with the written permission of the Administrator of the Transportation Security Administration or the Secretary of Transportation. For U.S. Government agencies, public disclosure is governed by 5 U.S.C. 552 and 49 CFR parts 15 and 1520. This document may also be exempt from disclosure and/or public access under one or more of the following: FSS 119.07; FSS 281.301; FSS 331.22. Unauthorized release may result in civil or criminal penalty.

Airport Emergency Plan
**SABOTAGE, HIJACK, AND OTHER
UNLAWFUL INTERFERENCE WITH OPERATION**

7. SABOTAGE, HIJACK, AND OTHER UNLAWFUL INTERFERENCE WITH OPERATIONS.

7.1. INTRODUCTION

This section provides guidance, in the event that this airport experiences sabotage, hijack, or other unlawful interference with operations of an aircraft. Understanding that the Federal Bureau of Investigation is the Lead agency for this hazard specific section, it is the intent of this section to provide steps to be taken by the Miami-Dade Police Department – Airport District, prior to the FBI arrival at the Unified Command.

7.2. PURPOSE

The information contained in this section defines responsibilities and describes actions to be taken in the event of sabotage, hijack, and other unlawful interference with operations of an aircraft as it may potentially impact this airport. This section represents the Standard Operating Procedures for Miami-Dade Aviation Department employees, airport tenants, users, and other agencies.

7.3. ADMINISTRATION AND LOGISTICS

The management of support resources in the event of emergencies is detailed in the Miami-Dade Aviation Department, Continuity of Operations Plan (COOP). This plan establishes a framework for MDAD to prepare for, respond to, mitigate the impacts of, and recover from emergencies.

7.4. DEVELOPMENT AND MAINTENANCE

Revisions to this Sabotage, Hijack, and Other Unlawful Interference with Operations section shall be maintained by the Division Director, Airside Operations or his/her designee. A true and current copy of the Airport Emergency Plan shall be maintained by the Airside Operations Supervisor, Ramp Control.

7.5. AUTHORITIES AND REFERENCES

Initial response to any aircraft accident, emergency, or potential emergency, will follow the guidelines established by Letter of Agreement between the Miami ATC Tower and the Miami-Dade Aviation Department, "FAA Emergency Procedures", reference Section 14, "MIA ATCT Functions Relating to Emergency Actions", Exhibit 14A. Miami-Dade Fire Rescue equipment augmentation will follow Fire Department Strategies for Alarm Assignments III-E-51.

Warning: This record contains Sensitive Security Information that is controlled under 49 CFR parts 15 and 1520. No part of this record may be disclosed to persons without a "need to know", as defined in 49 CFR Parts 15 and 1520, except with the written permission of the Administrator of the Transportation Security Administration or the Secretary of Transportation. For U.S. Government agencies, public disclosure is governed by 5 U.S.C. 552 and 49 CFR parts 15 and 1520. This document may also be exempt from disclosure and/or public access under one or more of the following: FSS 119.07; FSS 281.301; FSS 331.22. Unauthorized release may result in civil or criminal penalty.

Airport Emergency Plan
**SABOTAGE, HIJACK, AND OTHER
UNLAWFUL INTERFERENCE WITH OPERATION**

7.6. SITUATION AND ASSUMPTIONS

In the event of aircraft sabotage, hijacking, or other unlawful interference, the following agencies have primary responsibility for the direction of activities:

1. If the aircraft is airborne, the Federal Aviation Administration will direct activity in concert with involved air carrier officials.
2. If the aircraft is on the ground, the Federal Bureau of Investigation (FBI) will direct activities. All organizations will cooperate with these agencies as requested. Anyone having knowledge of a hijacking, hijack threat, sabotage, or other unlawful interference should immediately contact the Airport Police.
3. If a pilot on an aircraft requests assistance through the FAA Flight Service Station, FAA Miami Center, MIA ATCT, or company operations, the recipient of the request shall immediately contact the Airport Police by telephone and providing the following information:
 - a. Name of company
 - b. Flight number and type of aircraft
 - c. Number of souls on board (SOB)
 - d. Estimated time of arrival (ETA)
 - e. Gate number or other location on the AOA where aircraft will be parked upon landing, and repeat the pilot's request, detailing the nature of the problem, the number of persons involved in the threat, and if a weapon or other device is in evidence.
4. When Airport Police are notified of the incident, they will immediately inform MDAD Airport Operations Center (AOC) and the FBI.
5. The AOC will make appropriate notifications.

7.7. OPERATIONS

The Miami-Dade Police Department, Airport District, will assume the Incident Commander role as the lead agency at the Incident Command Post until liaison is established with the FBI.

7.7.1. Miami-Dade County Aviation Department

The Miami-Dade Aviation Department Gate Control Office will work with Miami-Dade Police personnel to expedite aircraft to a parking position or gate. Ramp 1 will liaison with the Miami-Dade Police Department at the gate and provide support as required. If aircraft is international, IC will notify US Customs and Border Protection to meet the aircraft at the gate.

7.7.2. Penalty Box

Every attempt will be made to direct aircraft to the Penalty Box (*see exhibit 3A, "Bomb Incidents", section 3*). If the aircraft cannot be directed to the Penalty Box, Ramp 1 will coordinate with the Miami-Dade Police Department and the MIA ATCT to set a perimeter and isolate the aircraft.

Warning: This record contains Sensitive Security Information that is controlled under 49 CFR parts 15 and 1520. No part of this record may be disclosed to persons without a "need to know", as defined in 49 CFR Parts 15 and 1520, except with the written permission of the Administrator of the Transportation Security Administration or the Secretary of Transportation. For U.S. Government agencies, public disclosure is governed by 5 U.S.C. 552 and 49 CFR parts 15 and 1520. This document may also be exempt from disclosure and/or public access under one or more of the following: FSS 119.07; FSS 281.301; FSS 331.22. Unauthorized release may result in civil or criminal penalty.

Airport Emergency Plan
**SABOTAGE, HIJACK, AND OTHER
UNLAWFUL INTERFERENCE WITH OPERATION**

7.8. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES

7.8.1. Miami-Dade Police Department, Airport District

The Miami-Dade Police Department shall:

1. Dispatch units to meet the aircraft at the gate of arrival.
2. Isolate target(s) from the rest of the passengers.
3. Notify Federal Agencies if required.

7.8.2. Miami-Dade Fire Rescue – Aviation Division

The Miami-Dade Fire Rescue shall:

1. Initiate standby status
2. Determine need for, and initiate as directed by IC, life saving, aircraft rescue and firefighting, or hazardous materials response.

7.8.3. MIA ATCT

The MIA ATCT will, upon notification from Ramp 1, isolate airspace from media aircraft. It shall be recommended that Class B airspace be closed to media aircraft until the operation is completed.

7.8.4. MDAD Operations

The Miami-Dade Aviation Department Airside Operations Senior Agent, Ramp 1, shall:

1. Close taxiways 'M' and 'N' from 'Y' to 'Z'.
2. Close taxiway 'JJ' from 'N' to 'P'.
3. Close taxiway 'HH' from 'N' to 'Y2'.
4. Setup liaison with MDPD IC and Senior Fire Officer on scene.

7.8.5. Airline/Aircraft Operator or Designated Representative

The airline/aircraft operator or designated representative shall:

1. Report to the ICP, making certain that his/her presence and identity is made known to the IC.
2. Advise IC immediately of any radiological or hazmat material aboard the aircraft involved.
3. Provide the IC with any relevant information as required.
4. Designate PIO to provide appropriate information to the news media.
5. Designate and official Recovery Coordinator who will meet with the MDAD Division Director of Airside Operations to coordinate recovery effort upon the outcome of the incident.

SECTION 8
Table of Contents

8. FAILURE OF POWER FOR MOVEMENT AREA LIGHTING	8 – 2
8.1. INTRODUCTION	8 – 2
8.2. PURPOSE	8 – 2
8.3. ADMINISTRATION AND LOGISTICS	8 – 2
8.4. DEVELOPMENT AND MAINTENANCE	8 – 2
8.5. SITUATION AND ASSUMPTIONS	8 – 2
8.5.1. Inspections	8 – 2
8.5.2. Preventive Maintenance	8 – 2
8.5.3. Backup Power	8 – 3
8.5.3.1. <u>ALV 1</u>	8 – 3
8.5.3.2. <u>ALV 2</u>	8 – 3
8.6. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES	8 – 3
8.6.1. ATCT	8 – 3
8.6.2. MDAD Airfield Lighting Maintenance	8 – 3
8.6.3. MDAD Airside Operations, Ramp Control	8 – 3

8. FAILURE OF POWER FOR MOVEMENT AREA LIGHTING

8.1. INTRODUCTION

Miami International Airport has four runways and nineteen taxiways equipped with centerline and edge lighting. In addition, all runway/taxiway intersections are equipped with runway guard lights.

8.2. PURPOSE

The information contained in this section defines responsibilities and describes actions to be taken in the event of failure of power for movement area lighting. This section represents the Standard Operating Procedures for Miami-Dade Aviation Department employees, airport tenants, users, and other agencies.

8.3. ADMINISTRATION AND LOGISTICS

The management of support resources in the event of emergencies is detailed in the Miami-Dade Aviation Department, Continuity of Operations Plan (COOP). This plan establishes a framework for MDAD to prepare for, respond to, mitigate the impacts of, and recover from emergencies.

8.4. DEVELOPMENT AND MAINTENANCE

Revisions to this Failure of Power for Movement Area Lighting section shall be maintained by the Division Director, Airside Operations or his/her designee. A true and current copy of the Airport Emergency Plan shall be maintained by the Airside Operations Supervisor, Ramp Control.

8.5. SITUATION AND ASSUMPTIONS

The sole source of power for Miami International Airport is provided by Florida Power and Light. The airfield lighting is managed by a Siemens Airfield Lighting Control System (ALCS), which upon power failure has a failsafe for movement area lighting. All lights are preset at medium intensity and default to on.

8.5.1. Inspections

Twice a day, MDAD Airside Operations, Ramp Control personnel inspect movement area lighting. The first inspection is performed at dusk and covers all lighting with the exception of runways. After midnight, an inspection is made of all runway and approach lighting.

8.5.2. Preventive Maintenance

Preventive maintenance of all runway lighting is performed bi-weekly. Preventive maintenance of all taxiways are made daily in coordination with Ramp Control inspections.

8.5.3. Backup Power

All backup power is produced by three independent generators located in two Airfield Lighting Vaults (ALV). Each generator is supported by individual 2,000 gallon diesel tanks. Preventive maintenance and testing of all generators are performed monthly.

8.5.3.1. ALV 1

Located midfield, this vault covers all airfield lighting from taxiway Q north, including runways 8R/26L and 8L/26R. Backup power is provided by two generators: a 900kw Cummins Oran Genset, and a 500kw Detroit Diesel Spectrum generator.

8.5.3.2. ALV 2

Located behind the midfield blast fence, this vault provides power to all airfield lighting from runway 12/30 south, including runway 9/27. Backup power is provided by a Caterpillar 500kw generator.

8.6. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES

8.6.1. ATCT

Upon power failure to the movement area lighting, MIA ATCT shall:

1. Coordinate with Ramp 1 for aircraft movement throughout the affected areas.
2. Keep Aviation users informed of the situation.

8.6.2. MDAD Airfield Lighting Maintenance

Airfield Lighting Maintenance personnel, upon being notified of outage shall:

1. Inspect Airfield Lighting Control System (ALCS) and regulator to determine location of problem.
2. Coordinate with Ramp 1 for closure and access to affected areas.
3. Advise Ramp 1 when area has been repaired.

8.6.3. MDAD Airside Operations, Ramp Control

MDAD Airside Operations, Ramp Control personnel shall:

1. Inspect all airfield lighting except runways at dusk
2. Inspect all runway lighting after midnight.
3. If a lighting outage is observed during the inspection, or reported at any other time, advise ATCT to recycle the lights and verify condition of Siemens Airfield Lighting control system.
4. If a failure of movement area lighting is confirmed, contact MDAD Airfield Lighting and issue a NOTAM for the affected area.
5. Provide escorts for any aircraft and/or vehicles requiring access through the affected area(s) if requested.
6. Once repaired, advise ATCT and cancel NOTAM.

SECTION 9

Table of Contents

9. WATER RESCUE SITUATIONS	9 – 2
9.1. INTRODUCTION	9 – 2
9.2. PURPOSE	9 – 2
9.3. ADMINISTRATION AND LOGISTICS	9 – 2
9.4. DEVELOPMENT AND MAINTENANCE	9 – 2
9.5. AUTHORITIES AND REFERENCES	9 – 2
9.6. SITUATION AND ASSUMPTIONS	9 – 2
9.7. OPERATIONS	9 – 3
9.7.1. Notification	9 – 3
9.7.2. Dispatch – Watch Office	9 – 3
9.7.2.1. <u>Dispatch – FAO</u>	9 – 3
9.7.3. Procedures	9 – 3
9.7.3.1. <u>Hose Raft Evolution</u>	9 – 3
9.7.3.2. <u>RHIB</u>	9 – 4
9.7.3.3. <u>Water Rescue Operations</u>	9 – 4
9.7.3.4. <u>SCUBA Divers</u>	9 – 4
9.7.3.5. <u>Triage, Treatment, and Transportation of Patients</u>	9 – 4
9.7.3.6. <u>Other Airport Entities</u>	9 – 4

EXHIBIT

9A - Bodies of Water Adjacent to Airport

9. WATER RESCUE SITUATIONS

9.1. INTRODUCTION

This section prescribes procedures to respond to water rescue situations that would occur in the Blue Lagoon area at the eastern end of runway 12/30. The MDRF, Aviation Division, has 24 hour on site water rescue personnel equipped with SCU-BA and a Rigid Hull Inflatable Boat (RHIB) available to respond.

9.2. PURPOSE

The information contained in this section defines responsibilities and describes actions to be taken in the event an aircraft accident occurs in a body of water, in the vicinity of the airport as described above.

9.3. ADMINISTRATION AND LOGISTICS

The management of support resources in the event of emergencies is detailed in the Miami-Dade Aviation Department, Continuity of Operations Plan (COOP). This plan establishes a framework for MDAD to prepare for, respond to, mitigate the impacts of, and recover from emergencies.

9.4. DEVELOPMENT AND MAINTENANCE

Revisions to this Water Rescue Situations section shall be maintained by the Division Director, Airside Operations or his/her designee. A true and current copy of the Airport Emergency Plan shall be maintained by the Airside Operations Supervisor, Ramp Control.

9.5. AUTHORITIES AND REFERENCES

Initial response to any aircraft accident, emergency, or potential emergency, will follow the guidelines established by Letter of Agreement between the Miami ATC Tower and the Miami-Dade Aviation Department, "FAA Emergency Procedures", reference Section 14, "MIA ATCT Functions Relating to Emergency Actions", Exhibit 14A. Miami-Dade Fire Rescue equipment augmentation will follow Fire Department Strategies for Alarm Assignments III-E-51.

9.6. SITUATION AND ASSUMPTIONS

Blue Lagoon Lake runs east and west, parallel to runway 9/27, and approximately 1,500 feet north, on the eastern end of runway 12/30. At the NW 14th street and Perimeter Road Bridge, the lake transitions into the Tamiami Canal and continues north, then east, just south of Central Blvd (*see exhibit 9A, "Bodies of Water Adjacent to Airport"*).

Description of bodies of water involved:

1. **Type:** Lake
2. **Approximate size:** Greater than ¼ mile square
3. **Average depth:** 0 – 40 feet
4. **Seasonal weather/climatic variations:** Tropic
 - a. **Ice:** Not applicable
 - b. **Water temperatures:** 60° - 85°
 - c. **Wave height:** Minimal, depending on high wind factor
 - d. **Hours of daylight:** Eastern Daylight Time
 - e. **Prevailing winds:** SE

9.7. OPERATIONS

MDFR will assume the Incident Commander role as the Lead agency at the Incident Command Post for this type of incident. The ICS shall be used throughout the incident.

9.7.1. Notification

As noted in Section 2.8.1.2., Aircraft Incidents and Accidents, the MIA ATCT will notify the MDFR Aviation Division Watch Office, via the Emergency Telephone (Crash Phone), of any actual emergency. The Watch Office will then notify the MDFR Fire Alarm Office, where further notification will continue per MDFR Strategy for Alarm Assignment.

9.7.2. Dispatch – Watch Office

Should an aircraft accident occur in or near a body of water proximate to MIA, the Senior Airport Fire Officer shall immediately dispatch all emergency equipment under his command to the scene via the Watch Office. This is to include the RHIB at the Midfield Fire Station.

9.7.2.1. Dispatch – FAO

Miami-Dade Fire Rescue Policy and Procedure: Strategy for Alarm Assignment, III-E-51, III, “*Pre-established Assignment Packages*”: shall supplement this initial dispatch with an Alert III Large Aircraft Assignment and an MCI Level 3 through the MDFR Fire Alarm Office, where MDFR Policy and Procedure III-E-51, Strategy for Alarms, will be followed.

9.7.3. Procedures

At present, MIA will implement the Hose Raft Evolution, Rigid Hull Inflatable Boat (RHIB) Procedure, Water Rescue Operations, and SCUBA Diver Procedures, currently used throughout Miami-Dade Fire Rescue.

9.7.3.1. Hose Raft Evolution

This Operation will deploy a 50' X 5" flotation device to accommodate those aircraft victims that can assist themselves. Additional 50' sections may be added as needed.

9.7.3.2. RHIB

The use of RHIB(s) will assist in the transport of those victims seriously injured, panicked, or unable to care for themselves. Further use of RHIB would facilitate deployment of divers to rescue victims below the water surface and/or in submerged sections of aircraft. A primary (#1) and secondary (#2) location for RHIB deployment are indicated on exhibit 9A, "*Bodies of Water Adjacent to Airport*".

9.7.3.3. Water Rescue Operations

Initial responding Water Rescue assigned units will establish specific docking/landing areas (primary and alternate) onshore, where survivors can be brought for triage, treatment, and transportation to health care facilities.

9.7.3.4. SCUBA Divers


MDFR procedures II-K-3 will be followed to facilitate rescue of victims from water.

9.7.3.5. Triage, Treatment, and Transportation of Patients

MDFR Medical Operations Manual, Multiple Casualty Incident Procedure 34, shall be followed for appropriate actions determined by number of patients for Levels 1 through 5.

9.7.3.6. Other Airport Entities

All other Airport Entities (i.e. MDPD Airport District, MDAD Operations, and Airline) shall follow the operating procedures for Alert III situation as detailed in Section 2.0, "*Aircraft Incidents and Accidents*".



SECTION 10

Table of Contents

10. MEDICAL SERVICES	10 – 2
10.1. INTRODUCTION	10 – 2
10.2. PURPOSE	10 – 2
10.3. ADMINISTRATION AND LOGISTICS	10 – 2
10.4. DEVELOPMENT AND MAINTENANCE	10 – 2
10.5. SITUATION AND ASSUMPTIONS	10 – 2
10.6. OPERATIONS	10 – 3
10.6.1. Miami-Dade Fire Rescue, Aviation Division	10 – 3
10.6.2. Miami-Dade Police Department, Airport District	10 – 3
10.6.3. Airline Facilities	10 – 3
10.6.4. Shelter Facilities	10 – 3
10.7. OFF-AIRPORT MEDICAL FACILITIES	10 – 3
10.8. OFF-AIRPORT RESCUE ASSISTANCE, MILITARY ASSISTANCE, AND AM- BULANCE SERVICES	10 – 4
10.8.1. Miami-Dade Fire Rescue	10 – 4
10.8.2. U.S. Coast Guard	10 – 4
10.8.3. Ambulance Service	10 – 4
10.8.4. Supplemental Transportation Service	10 – 4

10. MEDICAL SERVICES

10.1. INTRODUCTION

The Miami-Dade County Department of Emergency Management & Homeland Security Office has the responsibility of coordinating all health and medical activities in Miami-Dade County, both governmental and private, to minimize illness, disability, and death, in the aftermath of any type of disaster.

10.2. PURPOSE

The information contained in this section establishes procedures of emergency response for prompt and effective care of those affected by a disaster. Application in this respect, as set forth in the Airport Certification Manual of Miami International Airport, is directed principally to those instances involving aircraft.

10.3. ADMINISTRATION AND LOGISTICS

The management of support resources in the event of emergencies is detailed in the Miami-Dade Aviation Department, Continuity of Operations Plan (COOP). This plan establishes a framework for MDAD to prepare for, respond to, mitigate the impacts of, and recover from emergencies.

10.4. DEVELOPMENT AND MAINTENANCE

Revisions to this Medical Services section shall be maintained by the Division Director, Airside Operations or his/her designee. A true and current copy of the Airport Emergency Plan shall be maintained by the Airside Operations Supervisor, Ramp Control.

10.5. SITUATION AND ASSUMPTIONS

The primary responsibility for medical services at Miami International Airport is vested in the Miami-Dade Fire Rescue, Airport Division. Emergency Service is also available from the personnel of the Miami-Dade Police Department, Airport District. Response by either of these sources will be forthcoming upon request. Each also has the authority to initiate assistance from the Miami-Dade County Department of Emergency Management & Homeland Security Office.

10.6. OPERATIONS

10.6.1. Miami-Dade Fire Rescue, Aviation Division

The Emergency Medical Service (EMS) of the Airport Fire Department is located in both Fire Stations on the airfield and are available to all airport locations within a few minutes.

The Miami-Dade Fire Rescue, Airport Division, currently has 3 Advance Life Support Units (ALS) licensed by the State of Florida; a modular ambulance, and 2 fire trucks. These units are equipped with a cardiac monitor / transmitter / defibrillator, which relay medical data to supporting hospitals for evaluating patients at remote incidents, to provide doctor-paramedic dialogue. This EMS Task Force would normally set up the triage should we have a mass casualty incident.

All Fire Department personnel stationed at MIA are either Paramedics or licensed EMTs.

Additional equipment includes the Mass Casualty Incident (MCI) Trailer, a unique, large capacity support vehicle, containing emergency supplies for the treatment of 250 seriously injured victims.

Automated External Defibrillators (AEDs) are located throughout the terminal and are standard equipment in each Miami-Dade Police vehicle.

10.6.2. Miami-Dade Police Department, Airport District

The Miami Dade Police Department, Airport District Station in building 3033, all security checkpoints at each of the concourses in the Main Terminal Building, and all police vehicles, are equipped with portable first-aid kits. Officers are fully trained in first-aid procedures.

10.6.3. Airline Facilities (Reserved)

10.6.4. Shelter Facilities

Buildings, hangars, and other facilities (on airport), capable of sheltering non-injured, triage of injured, and processing of deceased, is listed in Appendix A of the Airport Emergency Plan.

10.7. OFF-AIRPORT MEDICAL FACILITIES

Activation of a hospital emergency alert is initiated through the Fire Department Alarm Office or the Director of the Miami-Dade Police Department on the Dade County communications network. On the initial alert, inform the Director of the Miami-Dade County Department of Emergency Management & Homeland Security Office as to the location and type of disaster, extent of damage, and effected casualties in the area.

10.8. OFF-AIRPORT RESCUE ASSISTANCE, MILITARY ASSISTANCE, AND AMBULANCE SERVICES

10.8.1. Miami-Dade Fire Rescue

In addition to the Airport Fire-Rescue Units at MIA, the Miami-Dade Fire Rescue has additional Fire Rescue units that can be called upon to respond to the scene of a major medical disaster. Further, the City of Miami, Coral Gables, and Hialeah, have similar units which can be called upon if the need arises. Fire Department rescue vehicles, both on and off the airport, and other MDAD vehicles can be used to supplement the ambulance service in transporting injured to designated hospitals as needed.

10.8.2. U.S. Coast Guard

The U.S. Coast Guard, 7th District Office, Search and Rescue Branch, has at least three helicopters available. Each capable of carrying three to four seriously injured persons to local hospitals.

10.8.3. Ambulance Service

One civilian Ambulance company provides all necessary ground transportation for injured persons under contract to Miami-Dade County and provides such service daily on a countywide basis.

10.8.4. Supplemental Transportation Service

On-airport buses and rental car shuttle buses are available 24-hours a day to add to the transport service of injured to hospitals.

NOTE: All of the medical facilities listed in this section have agreed to provide emergency medical services as stated, in accordance with their respective medical disaster plans, as summated to the Miami-Dade County Department of Emergency Management & Homeland Security Office.

SECTION 11

Table of Contents

11. CROWD CONTROL	11 – 2
11.1. INTRODUCTION	11 – 2
11.2. PURPOSE	11 – 2
11.3. ADMINISTRATION AND LOGISTICS	11 – 2
11.4. DEVELOPMENT AND MAINTENANCE	11 – 2
11.5. SITUATIONS AND ASSUMPTIONS	11 – 2
11.6. OPERATIONS	11 – 2
11.6.1. Responsibility	11 – 3
11.6.2. Agencies To Be Notified Upon Receipt of Information	11 – 3
11.6.3. MDAD Rules and Regulations	11 – 3
11.6.3.1. <u>Restricted Areas</u>	11 – 3
11.6.3.2. <u>Prohibition of Activities Harmful to Airport Operations</u>	11 – 3
11.7. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES	11 – 4
11.7.1. Miami-Dade Police Department, Airport District	11 – 4
11.7.2. Miami-Dade Fire Rescue, Aviation Division	11 – 5
11.7.3. Miami-Dade Aviation Department	11 – 5
11.7.4. MIA ATCT	11 – 5
11.8. INTELLIGENCE	11 – 5
11.9. OUTSIDE AGENCIES	11 – 5
11.10. MEDICAL CARE	11 – 5

11. CROWD CONTROL

11.1. INTRODUCTION

This section contains the procedures to be followed in order to effectively contain and control crowds at MDAD facilities. Its purpose is to establish a procedure that will ensure safe and efficient measures to prevent unlawful interference with airport operations. Control related to emergency situations is covered in specific sections.

11.2. PURPOSE

The information contained in this section defines responsibilities and describes actions to be taken in the event a crowd control incident or problem occurs at MDAD facilities. This section represents the Standard Operating Procedures for Miami-Dade Aviation Department employees, airport tenants, users, and other agencies.

11.3. ADMINISTRATION AND LOGISTICS

The management of support resources in the event of emergencies is detailed in the Miami-Dade Aviation Department, Continuity of Operations Plan (COOP). This plan establishes a framework for MDAD to prepare for, respond to, mitigate the impacts of, and recover from emergencies.

11.4. DEVELOPMENT AND MAINTENANCE

Revisions to this Crowd Control section shall be maintained by the Division Director, Airside Operations or his/her designee. A true and current copy of the Airport Emergency Plan shall be maintained by the Airside Operations Supervisor, Ramp Control.

11.5. SITUATION AND ASSUMPTIONS

Crowds generally fall into three categories and are defined as follows:

1. Nonviolent crowd: e.g., large group of air passengers or other persons congregating in terminal area, parade, and V.I.P. celebrity of newsworthy importance.
2. Potentially violent crowd: e.g., a large group of delayed, overbooked, cancelled flight air passengers congregating in terminal area, controversial person or group, demonstrators, labor disputes, or V.I.P.
3. Violent crowd: e.g., militant or controversial person or groups, civil disorders, sabotage, or terrorist groups.

11.6. OPERATIONS

The Miami-Dade Police Department, Airport District (MDPD), will assume the Incident Commander role as the lead agency at the Incident Command Post for this hazard-specific section. The ICS shall be used throughout the incident.

11.6.1. Responsibility

Each element or entity conducting business or operations at the airport has the initial responsibility to control crowds relating to their activities. If control of the crowd is projected to be beyond the resources of concerned element or entity, the senior on duty supervisor of such element or entity has the responsibility to notify a representative of the appropriate MDAD Operations office. The appropriate Division Director of Airside Operations, Landside Operations, or Terminal Operations, has the responsibility to ensure that a Senior Agent will assess the crowd; e.g., nonviolent, potentially violent, violent crowd. The Senior Agent will then contact the Airport Police Station to advise of the situation and request assistance if necessary.

If the Senior Agent requests police assistance, the Police Supervisor will be responsible for coordinating all aspects of crowd control. The Police Supervisor will advise the Senior Agent when the crowd control operation has been concluded.

11.6.2. Agencies To Be Notified Upon Receipt of Information

1. The MDAD Airport Operations Center (AOC) will activate the "Blue List" and make appropriate notifications.

11.6.3. MDAD Rules and Regulations

The following Miami-Dade Aviation Department Rules & Regulations are extracted from Chapter 25, Code of Miami-Dade County, Florida

11.6.3.1. Restricted Areas

§ 25-2.4. Entry to the AOA, SIDA or restricted areas. No Person shall enter the Air Operations Area (AOA), a SIDA area or a restricted area of any County Airport except:

- a) Persons who enter in accordance with security clearance pursuant to the security program established or authorized by the Department, for the particular airport involved or;
- b) Persons assigned duties on the AOA, a SIDA area or other restricted area of any County Airport bearing proper identification as approved and required herein, or;
- c) Persons who are employees or authorized representatives of the Department or other federal, State or local government department or agency, having proper business thereon and bearing proper identification as approved and required herein.

11.6.3.2. Prohibition of Activities Harmful to Airport Operations

§25-1.6 *Other laws.* All applicable provisions of the laws of the State of Florida and ordinances of Miami-Dade County, Florida, now in ex-

istence or hereafter enacted, are hereby adopted by reference as part of these rules and regulations. (Ord. No. 75-113, § 2, 12-2-75)

§25-2.8 Picketing.

- (a) Lawful picketing, marching or demonstrations on the Airport may be conducted only upon Airport public roads, rights-of-way, streets or sidewalks, in accordance with reasonable procedures established by the Department.
- (b) It shall be unlawful to picket, march or demonstrate within the Terminal Building structure at Miami International Airport. (Ord. No. 75-113, § 2, 12-2-75)

§25-2.9 Prohibited conduct. It shall be unlawful for any person to remain in or on any area, place or facility at an Airport, unless such person has a bona fide purpose for being in such area, place or facility, directly related to the normal and regular usage of such area, place or facility, in such a manner as to hinder or impede the orderly passage in or through or the normal or customary use of such area, place or facility by persons or vehicles entitled to such passage or use. (Ord. No. 75-113, § 2, 12-2-75; Ord. No. 95-41, § 48, 3-7-95)

§25-2.15 Weapons.

- (a) No person, other than federal, State or local law enforcement officers on duty or unless otherwise duly authorized by law and the Department, shall carry or transport any weapon on the Airport in a manner contrary to governing law.
- (b) No person shall discharge any gun on the Airport, except in the performance of official duties requiring the discharge thereof or in the lawful defense of life or property.
- (c) No person shall furnish, give, sell or trade any weapon or simulated weapon on the Airport unless authorized under appropriate lease with or permit issued by the County. (Ord. No. 75-113, § 2, 12-2-75; Ord. No. 95-41, § 52, 3-7-95)

§25-2.17. Endangering aircraft or vehicle operations. No person shall throw, shoot or propel any object in such manner as to interfere with or endanger the safe operation of any aircraft landing at, taking off from or operating on the Airport or any vehicle operating on the Airport. (Ord. No. 75-113, § 2, 12-2-75)

11.7. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES

11.7.1. Miami-Dade Police Department, Airport District

1. Dispatch necessary MDPD personnel to area of concern to control the

crowd and ensure that operations at Miami International Airport may proceed as normal.

2. Advise, request, and coordinate with other agencies as needed.
3. Establish a liaison with all Operations Senior Agents when appropriate, at a suitable location.

11.7.2. Miami-Dade Fire Rescue, Aviation Division

1. Extinguish fires and provide rescue service as required.
2. Secure supplemental medical aid as required.

11.7.3. Miami-Dade Aviation Department

1. Activate the MDAD Airport Emergency Operations Center (Airport EOC) if necessary.
2. Assist the Airport Police as necessary. Assign Liaison Officer to assist the Senior On-Duty Police Supervisor.
3. Alert Airport tenants as required.
4. Alert aircraft owners, operators, or their representatives as required.
5. Implement the MDAD Mass Migration Plan if necessary.

11.7.4. MIA ATCT

1. Control taxiing aircraft to avoid area of disturbances as delineated by Airside Operations Sr. Agent, Ramp 1.

11.8. INTELLIGENCE

Accurate and timely intelligence information is essential. Any person or element with such information will advise the Senior On-Duty Police Supervisor of such data. The Senior On-Duty Police Supervisor will consider such information relative to operational decisions.

11.9. OUTSIDE AGENCIES

The Platoon Commander on duty, or the MDAD Airport EOC (if established), will determine if further Police assistance from other Police Department elements or other agencies is necessary. Such assistance will be requested and provided as needed. The Platoon Commander will direct all Police operations.

11.10. MEDICAL CARE

Local facilities in the community will be utilized to service the needs of the public.

SECTION 12

Table of Contents

12. POST ACCIDENT INVESTIGATION AND REMOVAL OF DISABLED AIRCRAFT	12 – 2
12.1. INTRODUCTION	12 – 2
12.2. PURPOSE	12 – 2
12.3. ADMINISTRATION AND LOGISTICS	12 – 2
12.4. DEVELOPMENT AND MAINTENANCE	12 – 2
12.5. SITUATION AND ASSUMPTIONS	12 – 2
12.6. OPERATIONS	12 – 3
12.6.1. Recovery Equipment on Airport	12 – 3
12.7. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES	12 – 3
12.7.1. Aircraft Owner	12 – 3
12.7.1.1. <u>Designation of Recovery Coordinator</u>	12 – 3
12.7.1.2. <u>Recovery Coordinator Duties</u>	12 – 3
12.7.2. Miami-Dade Aviation Department	12 – 3
12.7.2.1. <u>Division Director of Airside Operations</u>	12 – 4
12.8. AIRCRAFT DE-FUELING ACTIONS	12 – 5

12. POST ACCIDENT INVESTIGATION AND REMOVAL OF DISABLED AIRCRAFT**12.1. INTRODUCTION**

Chapter 25, Section §25-10.7 Code of Miami-Dade County, Florida (Miami-Dade Aviation Department Rules and Regulations) stipulates the following:

- (a) Aircraft owners, operators and tenants shall be responsible for the prompt disposal of disabled aircraft and parts thereof, unless required or directed to delay such action by the Director or an authorized federal agency.
- (b) When a disabled aircraft is blocking or delaying the use of any portion of the AOA, the owner or operator of the aircraft shall make immediate arrangements to have such aircraft moved as soon as an authorized representative of the Department and appropriate governmental agencies have authorized such movement. In the event that removal of the aircraft is not initiated as soon as possible, or is not progressing at a rate acceptable to the Department, the Director shall have the right to initiate action to remove the aircraft at the expense and risk of the owner.

12.2. PURPOSE

The information contained in this section defines responsibilities and describes actions to be taken in the event of post accident investigation and removal of disabled aircraft incident or problem occurs at MDAD facilities. This section represents the Standard Operating Procedures for Miami-Dade Aviation Department employees, airport tenants, users, and other agencies.

12.3. ADMINISTRATION AND LOGISTICS

The management of support resources in the event of emergencies is detailed in the Miami-Dade Aviation Department, Continuity of Operations Plan (COOP). This plan establishes a framework for MDAD to prepare for, respond to, mitigate the impacts of, and recover from emergencies.

12.4. DEVELOPMENT AND MAINTENANCE

Revisions to this Post Accident Investigation and Removal of Disabled Aircraft section shall be maintained by the Division Director, Airside Operations or his/her designee. A true and current copy of the Airport Emergency Plan shall be maintained by the Airside Operations Supervisor, Ramp Control.

12.5. SITUATION AND ASSUMPTIONS

Each aircraft operator using Miami International Airport should have a basic recovery plan ready to meet such an emergency. Consultation with aircraft airframe or engine manufacturers should be conducted as appropriate. Likewise, consultation with other airline representatives experienced in such incidents is

available at MIA. The MDAD Division Director of Airside Operations will make these arrangements if requested.

The choice of technical ways and means to remove the aircraft and all costs associated with the recovery is the responsibility of the airline or owner involved.

12.6. OPERATIONS

For most aircraft accidents, the National Transportation Safety Board (NTSB), upon arrival, will take custody of the aircraft and its contents until full investigation is completed or a release is given. The NTSB will assume the primary response role and be the lead agency at the Unified Command Post for this hazard-specific section. The ICS shall be used throughout the incident.

12.6.1. Recovery Equipment on Airport

Recovery equipment and suppliers of equipment will be determined at the time of the incident in accordance with the nature and severity of the incident.

12.7. ORGANIZATION AND ASSIGNMENT OF RESPONSIBILITIES

12.7.1. Aircraft Owner

12.7.1.1. Designation of Recovery Coordinator

One company official should be designated Recovery Coordinator with the authority to make all decisions, technical and financial, necessary to recover the aircraft. It is the responsibility of the aircraft owner/operator to promptly remove the aircraft and to assume all costs associated with the recovery (including contractor charges, airline rental, and service company equipment charges, airport property damage, etc...).

12.7.1.2. Recovery Coordinator Duties

1. Have all required company facilities, including personnel and equipment, made available to him.
2. Meet with MDAD Assistant Director of Operations or his/her representative and NTSB Investigator to develop a comprehensive plan for the removal of the aircraft.
3. Arrange for a company representative available to answer any questions from the press and to issue press releases as may be appropriate.

12.7.2. Miami-Dade Aviation Department

Miami-Dade Aviation Department's role during recovery phase is that of a coordinator with a vested interest in returning the airfield to its normal operating condition as soon as possible.

Airport Emergency Plan
**POST ACCIDENT INVESTIGATION
AND REMOVAL OF DISABLED AIRCRAFT**

12.7.2.1. Division Director of Airside Operations

1. Will issue NOTAMs as may be appropriate.
2. Will coordinate all field operations with MIA ATCT for continuance of flight operations where possible.
3. Will determine any obstructions to established clearance criteria of FAA Regulations, Part 77, and will direct the marking and lighting of the disabled aircraft, and will close sections of the aeronautical areas as is consistent with continued safe flight operations.
4. Will arrange for security of the accident site in coordination with NTSB.
5. Will provide for vehicles and personnel to escort company equipment to the site.
6. Will establish a Recovery Incident Commander (IC) at the site if appropriate.
7. Will inspect all areas prior to resumption of normal operations.
8. Will return to operation effected portions of the airport as expeditiously as possible after assuring that access to the incident area has been secured and associated taxiways and runways are in good operational condition and free of debris and damage.
9. Will convene a meeting with airline recovery coordinator, NTSB Investigator, and where necessary, appropriate fueling Supervisor, rigging contractor and other parties, as may be necessary to implement the recovery operations.
10. Will provide for a fire watch when necessary.
11. Will make decisions on behalf of the Aviation Director as may be necessary to expedite the removal of the disabled aircraft.
12. Will be aware of further penetrations into the clear zone created by cranes during the lifting of the aircraft and coordinate with FAA and on issue of NOTAMs.
13. Will keep aware of the present and forecasted weather conditions.
14. Will maintain a chronological summary of the recovery operation, especially noting cause of delays that would be useful in upgrading procedures.
15. Will see that photographs and/or videotape of the recovery operations are taken.
16. Will represent MDAD at the Recovery ICP.
17. Will keep MDAD staff advised of the progress of the recovery operation.
18. Will coordinate with MDAD Facilities, maintenance, and FAA Airways Facilities Sector, regarding the existence and protection of underground facilities in the area of the incident, as well as restoration of airport facilities damaged by the incident or recovery measures.

Airport Emergency Plan
**POST ACCIDENT INVESTIGATION
AND REMOVAL OF DISABLED AIRCRAFT**

19. Establish Cost Recovery Coordinator for the Miami-Dade
County Aviation Department.

12.8. AIRCRAFT DE-FUELING ACTIONS

Where permission has been granted to de-fuel an aircraft that has been involved in an accident, such operation will be carried out in accordance with Section § 25-6.23, Chapter 25, Miami-Dade Aviation Department Rules and Regulations.

SECTION 13

Table of Contents

13. EMERGENCY ALARM SYSTEMS	13 – 2
13.1. INTRODUCTION	13 – 2
13.2. PURPOSE	13 – 2
13.3. ADMINISTRATION AND LOGISTICS	13 – 2
13.4. DEVELOPMENT AND MAINTENANCE	13 – 2
13.5. AUTHORITIES AND REFERENCES	13 – 2
13.6. SITUATION AND ASSUMPTIONS	13 – 2
13.7. OPERATIONS	13 – 3
13.7.1. Miami-Dade Aviation Department	13 – 3
13.7.1.1. <u>Assistant Aviation Director of Operations</u>	13 – 3
13.7.1.2. <u>Airside Operations Offices</u>	13 – 3
13.7.1.3. <u>Landside Operations</u>	13 – 3
13.7.1.4. <u>MDAD Airport Emergency Operations Center (Airport EOC)</u>	13 – 3
13.8. MIAMI-DADE FIRE RESCUE, AVIATION DIVISION	13 – 3
13.9. MIAMI-DADE POLICE DEPARTMENT, AIRPORT DISTRICT	13 – 4
13.10. MIA ATCT	13 – 4
13.11. FBI	13 – 5
13.12. MIAMI-DADE COUNTY DEPARTMENT OF EMERGENCY MANAGEMENT & HOMELAND SECURITY OFFICE	13 – 5

13. EMERGENCY ALARM SYSTEMS

13.1. INTRODUCTION

This section of the Plan deals with the alarm and communication systems used to notify the various functional units in the event of emergencies that are covered herein.

13.2. PURPOSE

The information contained in this section defines the communications system for Miami International Airport and supporting local, state, and federal agencies, for response to any emergency on the airport property.

13.3. ADMINISTRATION AND LOGISTICS

The management of support resources in the event of emergencies is detailed in the Miami-Dade Aviation Department, Continuity of Operations Plan (COOP). This plan establishes a framework for MDAD to prepare for, respond to, mitigate the impacts of, and recover from emergencies.

13.4. DEVELOPMENT AND MAINTENANCE

Revisions to this Emergency Alarm Systems section shall be maintained by the Division Director, Airside Operations or his/her designee. A true and current copy of the Airport Emergency Plan shall be maintained by the Airside Operations Supervisor, Ramp Control.

13.5. AUTHORITIES AND REFERENCES

Initial response to any aircraft accident, emergency, or potential emergency, will follow the guidelines established by Letter of Agreement between the Miami ATC Tower and the Miami-Dade Aviation Department, "FAA Emergency Procedures", reference Section 14, "MIA ATCT Functions Relating to Emergency Actions", Exhibit 14A. Miami-Dade Fire Rescue equipment augmentation will follow Fire Department Strategies for Alarm Assignments III-E-51.

13.6. SITUATION AND ASSUMPTIONS

The basic elements of the communications and alarm system consist of:

1. A direct alarm signal system between the MIA ATCT and the Airport Fire Station, with additional drop monitors located at strategic locations within the airport.
2. Emergency phones located at the MDAD Airport Emergency Operations Center (Airport EOC).
3. Radio transceivers on County government and ATCT Ground Control frequencies.

4. Conventional telephone (MDAD Private Branch Exchange [PBX]).

In the following paragraphs, a description will be given of each of the functional areas requiring communication capabilities and the systems available during emergency conditions.

13.7. OPERATIONS

13.7.1. Miami-Dade Aviation Department

13.7.1.1. Assistant Aviation Director of Operations

The office of the Assistant Director of Operations (Operations Executive Offices) has conventional telephones, a drop monitor of the emergency direct telephone line from the MIA ATCT to the Airport Fire Station, a portable phone (cellular), and mobile radios on ATCT Ground Control and County government frequencies.

13.7.1.2. Airside Operations Offices

The Airside Operations, Gate Control Office, and the General Aviation Center (GAC) are equipped with two-way airport ground radios, two-way local government radios, conventional telephones, and monitors of the direct "hot-line" emergency telephone between the ATCT and the Fire Station. All Ramp vehicles are equipped with two-way radios on the ground control and local government frequencies.

13.7.1.3. Landside Operations

The Landside Operations Control Office is located in Parking Garage #3, ground level, south end. It is equipped with conventional telephones, a remote radio base station on the local government frequencies, and portable radios for key operational personnel on local government frequencies.

13.7.1.4. Miami-Dade Aviation Department Airport Emergency Operations Center (Airport EOC)

The Miami-Dade Aviation Department Airport Emergency Operations Center (Airport EOC), when activated, will be located in the Concourse 'E', 5th floor Conference Room, inside the Concourse 'E' Terminal Building. They are equipped with conventional telephones and portable radios on local government frequencies, for key operational personnel.

13.8. MIAMI-DADE FIRE RESCUE, AVIATION DIVISION

The Airport Fire Station is equipped with a Watch Office, which is staffed around the clock. The Watch Office contains a red "Emergency" phone (Crash Phone), a direct line with the MIA ATCT, which is used in the event of aircraft emergen-

cies. Additionally, a dedicated “Medical Emergency” phone has been installed which is a direct line with the MIA ATCT to report directly to the MDR Watch Office any aircraft Medical Emergencies onboard aircraft at MIA or en route to MIA. There is also a base station, two-way radio system on the County Fire Department network, and a direct phone line to the Miami-Dade County’s Fire Alarm Office.

There is an alarm system identified by a red button located in the Watch Office, which when activated, turns on the lights at the Fire Station, opens the Fire Station doors, and sounds the alarm klaxon. The Watch Supervisor and/or the MIA ATCT can activate this alarm. The Watch Office is also equipped with an intercom system, which is used to relay instructions to the firefighters both inside and outside the Fire Station. Conventional telephones and backup lines (Aircom) are also provided.

Additionally, all vehicles are equipped with two-way radio capability on ground control, Fire, and County government frequencies. Hand-held radios are also used by the Fire Department for mobility of personnel and maintaining communications with the command units. All components of the communications and alarm system as well as the Miami-Dade County Fire Alarm are tested daily.

13.9. MIAMI-DADE POLICE DEPARTMENT, AIRPORT DISTRICT

The Airport Police Station is located in building 3033. Conventional telephones and backup lines (Aircom) are provided. The station is also equipped with two-way radios and a drop monitor of the direct Emergency line from the MIA ATCT to the Airport Fire Department. The two-way radio is part of the Miami-Dade Police Department’s system and has five channels; one of which can be set up as a command frequency from the airport in the event of an emergency. The Airport Police District is also equipped with hand-held radios, on MDPD frequencies, for utilization in and around the Terminal building and airport areas.

13.10. MIA ATCT

The MIA ATCT is equipped with conventional telephones. It also has two Emergency phone lines connected to the Airport Fire Station Watch Office. One for Aircraft Emergencies, the other for Medical Emergencies. The Aircraft Emergency phone (Crash Phone) line has Drop Monitors for this system located in the Airport Fire Chief’s Office, Airport Police Station, and MDAD Assistant Director of Operations (Executive Offices), MDAD Airside Operations Gate Control Office, MDAD Airport Operations Center (AOC), GAC, and MDAD Public Services Office. The MIA ATCT is equipped with an emergency alarm button which when activated, opens the Fire Station doors, turns on the lights, and sounds a klaxon. This alarm is used in conjunction with the direct Emergency telephone (Crash Phone), which is used to give instructions regarding the extent of the incident. This alarm can be activated from two positions in the MIA ATCT.

13.11. FBI

The FBI has a communication system cabinet in the Airport Division Fire Station, which is locked and is used only for their purposes. It has a direct line with Washington, DC, and can be used to set up an Incident Command Post for the FBI in the MIA ATCT.

13.12. MIAMI-DADE COUNTY DEPARTMENT OF EMERGENCY MANAGEMENT & HOMELAND SECURITY OFFICE

The Miami-Dade County Department of Emergency Management & Homeland Security Office, located at 9300 NW 41st Street, Miami, has a communication room which is equipped with conventional telephone, MDPD police radios, Miami-Dade Fire radio, County government radio, Police emergency radio, and hospital ambulance networks. These systems can be used in combination or separately to receive and transmit messages related to any incidents involving the Miami-Dade County Department of Emergency Management & Homeland Security Office.

SECTION 14
Table of Contents

14. MIA ATCT FUNCTIONS RELATING TO EMERGENCY ACTIONS14 - 2
14.1. INTRODUCTION14 - 2

EXHIBIT
14A Letter of Agreement
ATTACHMENT 1 / EXHIBIT 14A

14. MIA ATCT FUNCTIONS RELATING TO EMERGENCY ACTIONS

14.1. INTRODUCTION

Exhibit 14A is a reproduction of the Letter of Agreement between MIA ATCT and Miami-Dade County Aviation Department describing the functions of the ATCT in the event of an emergency.

MIAMI ATC TOWER AND MIAMI-DADE AVIATION DEPARTMENT
LETTER OF AGREEMENT

EFFECTIVE: February 1, 2009

SUBJECT: EMERGENCY PROCEDURES

1. PURPOSE. This agreement between Miami ATC Tower and the Miami-Dade Aviation Department establishes procedures to be used, to the extent practical, in the event of an aircraft accident, emergency, or potential emergency, and is supplemental to FAA Orders JO 7110.65 and JO 7210.3.
2. CANCELLATION. This agreement cancels and supersedes the Miami Tower and Metro-Dade Aviation Department Letter of Agreement dated September 1, 2005, Subject: "Emergency Procedures".
3. SCOPE. In the event of an aircraft accident, emergency, or potential emergency, Miami Tower personnel shall alert the Aircraft Rescue and Fire Fighting (ARFF) equipment when any of the following personnel requests such action:
 - a. The Miami Tower Operations Supervisor/Controller in Charge (CIC).
 - b. The pilot of the aircraft concerned.
 - c. The operator of the aircraft or his representative.
 - d. A representative of the airport management.
4. RESPONSIBILITIES.
 - a. Miami Tower shall:
 - (1) Notify ARFF Station, normally via the Crash Phone, of all emergencies, potential emergencies, accidents, fires, bomb threats, and/or any operation other than normal. If events do not permit coordination via the Crash Phone, the Tower personnel shall determine the appropriate alert category and coordinate with the ARFF Commander via radio using the call sign "Fire Commander".
 - (2) Provide the following information to the ARFF Station or Fire Commander:
 - (a) Alert Status: I, II, or III.
 - (b) Aircraft location/runway as appropriate.
 - (c) Flight number and/or registration.

- (d) Aircraft problem.
 - (e) Souls on board.
 - (f) Fuel on board in pounds or gallons.
 - (g) Hazardous cargo status (not on board or on board with type of material).
 - (h) Wind direction and velocity.
 - (i) Estimated time of arrival and landing runway.
 - (j) Other information.
- (3) During an ALERT III, immediately discontinue use of the affected runway(s) and taxiway(s) and promptly notify RAMP 1 and the Fire Commander.
- (4) Miami Tower shall monitor frequency 120.35 twenty-fours a day.
- b. Aircraft Rescue and Fire Fighting:
- (1) Fire Department vehicles shall be equipped to communicate with Miami Tower on Ground Control frequency and Emergency Control frequency 120.35 MHZ. Movement of emergency vehicles to and from the emergency site/standby positions shall be controlled on 121.8/127.5. Ground Control shall advise the Fire Commander when the affected taxiways and runways are clear of non-emergency related traffic, and authorize communications emergency frequency. The Fire Commander may respond to direct communications from the cockpit crew on the emergency frequency at any time and initiate communication when, in his judgment, the immediacy or severity of the circumstances warrant.
- NOTE: VEHICLE MOVEMENT OTHER THAN ON THE AFFECTED SURFACES MUST BE AUTHORIZED ON GROUND CONTROL FREQUENCY.
- (2) The Fire Commander on duty shall be responsible for determining when an ALERT I is to be upgraded to an ALERT II and notify the Tower prior to the movement of emergency equipment to standby positions.
- c. Operations Supervisor in Charge/Controller in Charge (OSIC/CIC): It is the responsibility of the OSIC/CIC to alert the emergency equipment operator via the Crash Phone Circuit, commercial telephones, or radio frequency, in accordance with the following alert categories:
- (1) ALERT I. Any event involving an aircraft when the operation of said aircraft is other than normal. Specify items a - j [para. 4.a.(2)].

(2) ALERT II. A potential emergency exists requiring immediate dispatch of emergency equipment to standby positions on the airport. Specify items a - e [para. 4.a.(2)] only and provide additional information to the Fire Commander on 120.35.

(3) ALERT III. An accident has occurred or an accident is imminent requiring immediate dispatch of emergency equipment to the scene. Specify items a and b [para. 4.a.(2)] only and provide additional information to the Fire Commander on 120.35.

d. ARFF shall test the Crash Phone circuit daily at 0700 local time.

5. PROCEDURES.

- a. Miami TRACON shall instruct the emergency landing aircraft to contact Miami Tower 120.35.
- b. It is imperative that only authorized transmissions occur on 120.35. Communications should be limited to: Fire Commander, MDAD on-scene vehicles, the pilot of the emergency aircraft, and the Tower. All other vehicles and personnel on this frequency should be in monitor status only.
- c. Any late responding MDAD or Fire Department vehicles shall request clearance to the emergency site on the appropriate Ground frequency and then be directed to switch to 120.35.
- d. Ground control shall advise Fire Commander and MDAD of the landing runway and when the emergency arrival is the next one to land on that runway.
- e. When the emergency aircraft crosses the landing threshold, a Ramp vehicle will follow it down the runway after receiving clearance on 120.35. Fire vehicles may also follow the aircraft down the runway after receiving clearance on 120.35.
- f. The Airport manager, or designee, shall open the runway as soon as it is determined that it is safe to do so. Notification to this effect shall be made via radio upon exiting the runway. Ground control will continue to monitor the Emergency frequency 120.35. Fire commander will remain in contact with the aircraft until the emergency is secured or terminated.
- g. Upon termination of the emergency, Fire Commander will request authorization on 120.35 to contact the appropriate ground control on frequency (121.8/127.5) for subsequent movement of vehicles on the movement area.

6. REQUEST FOR SUPPORT EQUIPMENT. The Fire Commander on the scene of an accident will normally make requests for additional support equipment and personnel through the Miami-Dade County Fire Alarm Office. The Fire Commander will determine the appropriate Rendezvous Point(s) for the entrance of incoming support emergency equipment. See attachment #1 depicting the following Rendezvous Points:

1. Terminal Entrance.
2. Southeast Gate.
3. Northeast Base Gate.
4. Red Road Gate South.
5. 2650 N.W. perimeter Road (1 block north of N.W. 25th Street).
6. Southwest Gate.


7. NOTIFICATION OF AGENCIES. Miami Tower shall normally provide initial information for:

a. ALERT I and ALERT II to the ARFF Station.

b. ALERT III to the:

- (1) ARFF Station
- (2) Aircraft Operator
- (3) MDAD (Ramp #1)

Thereafter, all inquiries concerning the incident shall be directed to the MDAD Airside Senior Agent (Ramp 1) at 305-876-7001 or the aircraft operator.



William W. Kribble
Air Traffic Manager
Miami Tower




Lonny Craven,
Division Director,
Airside Operations
Miami-Dade Aviation Department


R.P. #1 Terminal Entrances. On the main entrance to the Terminal Building, from N.W. 42nd Avenue, (Le Jeune Rd.), westbound at the overpass.
 R.P. #2 Southeast Gate. On the east side of the airport, approximately at the intersection of Perimeter Road and N.W. 16th Street.

R.P. #3 Enter at the intersection of NW 36th Street and 57th Avenue and proceed southbound to the gate east of building 841.
 R.P. #4 Red Road Gate South. On the south side of the airport, at Red Road, (N.W. 57th Avenue), and approximately N.W. 14th Street.

R.P. #5 2650 N.W. Perimeter Road, (one block north of N.W. 25th Street).
 R.P. #6 Southwest Gate. On the southwest corner of the airport, just south of building #706, at the point of access from N.W. 16th Street into the AOA.



FAA Use Only



Magnetic Declination
 6° 5' West (2012)
 Annual Rate of Change
 5.8' West

MIAMI-DADE COUNTY AVIATION DEPARTMENT
 MIAMI INTERNATIONAL AIRPORT

**FIRE MUTUAL AID
 RENDEZVOUS POINTS
 EXHIBIT 2A
 ATTACHMENT 1 / EXHIBIT 14A**

DRAWN BY	DATE	CHECKED BY	DATE	IN CHARGE	SCALE	FILENAME
H.I.	04-01-2015	F.W.	04-01-2015	L.C.K.D.	-	60377_Rev05
AIRSIDE OPERATIONS DIVISION						SHEET 1 of 1

SECTION 15
Table of Contents

15. MUTUAL AID AGREEMENTS	15 - 2
15.1. MIAMI-DADE FIRE RESCUE, AIRPORT DIVISION	15 - 2
15.2. MIAMI-DADE POLICE DEPARTMENT, AIRPORT DISTRICT	15 - 2
15.3. MEDICAL	15 - 2

15. MUTUAL AID AGREEMENTS

15.1. MIAMI-DADE FIRE RESCUE, AIRPORT DIVISION

Airport Fire Rescue at Miami International Airport is a division of the Miami-Dade Fire Rescue. As such, it is directly supported by the entire County system of Fire Stations and equipment. There are no formal Mutual Aid agreements with other municipalities within Miami-Dade County, however coordination and training have been implemented on an ongoing basis between Miami-Dade County and the principal incorporated cities in the areas surrounding the airport, i.e.; City of Miami, Hialeah and Coral Gables.

15.2. MIAMI-DADE POLICE DEPARTMENT, AIRPORT DISTRICT

The Airport Police at Miami International Airport is a District of the Miami-Dade Police Department and is directly supported, if necessary, by all other county police units. Mutual aid agreements are in effect between Miami-Dade County and Police units of the State of Florida, and principal incorporated cities within the confines of the County.

15.3. MEDICAL

Hospital and medical facilities throughout the County equipped to handle emergencies have submitted medical disaster plans to the Miami-Dade County Department of Emergency Management & Homeland Security Office (*see Section 10*). Hospital capability is monitored by MDFR on a 24-hour basis through the Med-Com system.

EMERGENCY TELEPHONE LIST

CONFIDENTIAL

Updated 3-29-22			
1	EMERGENCY NOTIFICATION DIVISIONS		
	OFFICE		
	Miami FAA Air Traffic Control Tower and Radar (24 Hours)	Tower - 305-869-5476 // Radar - 305-869-5432	
	Fire Department - MDR Airport Division	911	
	Police Department - MDPD Airport District	305- 876-7373 - For emergencies, dial 911	
2	AVIATION DEPARTMENT DIVISIONS		
	AIRSIDE	OFFICE	CELL
	Gate Control	D - 305-876-7978 / E - 305-876-7333 J - 305-869-4018 / 876-0218	
	Bus Coordinator/ Station 2	305-876-7486	
	Ramp 1 (MIA)	305 876-7001	305 815-7390
	Access Control	305-876-7440	24 hr - 305-588-7094
	Access 1	305-588-7094	305 588-7094
	Noise Abatement	305 876-7526	
	General Aviation Center (GAC)/Ramp Control Station 3	305 876-7550	
	General Aviation Airports	OFFICE	FAX
	Opa-locka Executive Airport (OPF)	305 869-1660	305 869 1666
	Ramp 50 - Main Number - Agent		305 439-2696
	Maintenance	Supervisor: 305-869-1644	Lead Worker: 305-869-1668
	Operations	Supervisor: 305-869-1662	
	Miami Executive Airport (TMB)(Kendall-Tamiami)	305 869-1700	305-869-1780
	Ramp 60		305 439-2701
	Maintenance	Supervisor: 305-869-1712	Lead Worker: 305-869-1704
	Dade-Collier Training & Transition Airport (TNT)	239-695-3300	305-793-3158 or 305-869-1660
	Ramp 80		305-794-8984 - Mgr.
	Maintenance	Supervisor: 305-869-1662	Lead Worker: 305-869-1668
	Homestead General Aviation Airport (X51)	305-247-4883 305-247-4884	305-246-4252
	Ramp 70		305-793-2747
	COMMUNICATIONS	OFFICE	CELL
	Duty PIO	305-876-7017	Main - 305-342-1849 Greg - 786-251-0588 Jack - 786-449-2575 Indira - 305-898-7995 Mark - 786-229-9070
	TERMINAL		
	General Information	305 876-7000	
	Airport Operations Center (AOC) - Sta-6	305 876-0385	
	LANDSIDE		
	Operation Control Room - Sta-4	305 876-7447	
	Operation Control Room - GT1	305-876-7442	
	SECURITY		
	Terminal Security 1 - 24 hour Cell		305-793-6680
	Security Operations - Airside Gates - Senior Agent	Office - Office hours - 305-876-7476	24/7 - 305-793-9513
	Access Gates		
	SE Gate #1	305-876-7435	Central Base # 1
	SE Gate #2 - Currently Closed	305-876-7410	Central Base # 2
	SW Gates #1 & 2 - Currently Closed	305-876-7412	
	NW Gate # 1	305-876-7979	Tunnel Base Gate - #1
	NW Gate # 2	305-876-7591	Tunnel Base Gate - #2
	NE Base Gate	305-876-7409	

EMERGENCY TELEPHONE LIST

CONFIDENTIAL

AVIATION DEPARTMENT DIVISIONS CONTINUED		OFFICE	FAX	CELLULAR
Finance & Strategy		305 876-7731		
Administrative Services		305 876-7557		
Capital Facilities Development		305 876-7054		
Computer Room		305 876-0160		
Derm - Hot Line (24 hrs)		305-372-6955		
Facilities Maintenance		305-876-0254	Emergencies - report to 305-869-7311	
Auxiliary Power Electric Shop/Airfield Lighting		305-876-7347		305-979-7140
Auxiliary Electric Shop - Main Bldg 3040		305-876-7335		
Auxiliary Power Field Lighting, Vault # 2, Southside		305-876-7347		305-979-7140
Maintenance 1		305-876-0298		305-606-0099
Legal		305 876-7040		
Marketing		305 876-7862	305-876-7398	
Risk Management		305 876-7777	305-876-7162	
Technical Support		305- 876-7453		
Technical Shop - Radios, Clocks		305-876-7505	305-876-8329	Report problems to 305-869-5900
Video Shop Services - Cameras, Videos		305-876-0989	Report problems to 305-869-7311 or 305 869-5900	
Work Order Center		305-876-7311		
3 AVIATION DEPARTMENT EMERGENCY PERSONNEL				
Name	Division	Office	Cellular	
Cutie, Ralph	Executive	305-876-7066	786-516-3880	
<i>Aviation Director</i>				
Rull Valenciaga, Arlyn	Executive	305-869-4190	305-877-8129	
<i>Chief of Staff, Sr. Policy Advisor</i>				
Hernandez, Patricia M.	Executive	305-876-7726	786-299-7748	
<i>Senior Executive Asst. to the Aviation Director</i>				
Binns II, Basil	Executive - Administration & Business Development & Retention	305-876-0499	305-250-8160	
<i>Deputy Aviation Director</i>				
Pyatt, Ken	Executive - Business Development & Retention & Operations	305-876-7129	305 608 1587	
<i>Deputy Aviation Director</i>				
Deblois, Jenny	Deputy Director's Office	305-876-0544	305-302-6206	
San Miguel, Sergio	Finance Division	305-876-0763	786-334-8321	
<i>Chief Financial Officer</i>				
Murray, David	Legal	305-876-7040	786-239-1910	
<i>Asst. Miami-Dade County Attorney</i>				
Garcia, Eric	MDPD - Airport District	305-876-7416	305-510-9494	
<i>Police Major</i>				
Nunez, R. Jaime	MDPD - Airport District	305-876-7558	786-205-0745	
<i>Police Captain</i>				
Rojas, Enrique J.	MDFD - Airport District	786-336-6592	305-498-0576	
<i>Fire Chief</i>				
Cruz, Al	MDFD - Airport District	305-876-1498	786-229-1411	
<i>Chief, MDFR</i>				
Ricardo, Omar	MDFD - Airport District	786-336-6593	786-258-6963	
<i>Chief, MDFR</i>				

EMERGENCY TELEPHONE LIST

CONFIDENTIAL

Agostino, Dan <i>Asst. Aviation Director</i>	Operations	305-876-7138	305-979-9662
Finol, Ana <i>Asst. Aviation Director</i>	Facilities Management	305-876-8310	786-641-7110
Hatfield Jr., Mark <i>Asst. Aviation Director</i>	Public Safety and Security	305-876-0127	786-602-3093
Jimenez, Barbara <i>Asst. Aviation Director</i>	Administration	305-876-0458	786-229-7315
Smith, Isaac <i>Asst. Aviation Director</i>	Facilities Management and Engineering	305-876-0830	305-903-5712
Warren, Robert N. <i>Asst. Aviation Director</i>	Business Retention & Development	305-869-8530	305-775-9292
Quintero, Tony <i>Associate Aviation Director</i>	Governmental Affairs	305-876-7533	786-295-3514
Abate, Sarah <i>Division Director</i>	Airport Concessions Business Development	305-876-7732	305-458-8477
Aguirre, Oscar <i>Division Director</i>	Finance/Accounting	305-876-7220	305-322-8512
<i>Interim Division Director</i>	Financial Planning & Performance Analysis		
Alufohai, U. Desmond <i>Division Director</i>	Protocol & International Affairs	305-876-7087	305-458-4389
Barroso, Hiram <i>Division Director</i>	Aviation Strategic Manager	305-876-7056	786-218-2691
Campos, Evelyn <i>Division Director</i>	Professional Compliance	305-876-7390	305-439-9439
Carlo, Barbara <i>Division Director</i>	Landside Operations & ADA Coordinator	305-876-7024	786-479-9959
Chin, Greg <i>Division Director</i>	Communications	305-869-3809	786-251-0588
Craven, Lonny <i>Division Director</i>	Airside & GAA Operations	305-876-7038	305-877-5238
Gonzales, Jorge <i>Division Director</i>	Finance/Program Controls	305-876-7224	305-202-2880
Jenkins, Maurice <i>Division Director</i>	Information Systems & Telecommunications	305-876-0934	305-409-4104
Mangos, Chris <i>Division Director</i>	Marketing	305-876-7862	305-877-4882
Mendez, John E. <i>Division Director</i>	Executive/Policy and External Affairs	305-876-0280	305-972-8300
Novela, Sylvia <i>Division Director</i>	Procurement & Materials Management	305-876-7048	786-769-1580
Paan, Juan <i>Acting Division Director</i>	Facilities Maintenance, Planning Engineering & Construction	305-876-7035	786-4984393
Pantoja-Kirtland, Nancy <i>Division Director</i>	Civil Environmental Engineering	305-869-4561	786-495-2239
Philloura, Rupen S. <i>Division Director</i>	Terminal Operations	305-869-5614	305-202-3739
Ragin, Andre T. <i>Division Director</i>	Minority Affairs	305-876-7221	786-255-5771

EMERGENCY TELEPHONE LIST

CONFIDENTIAL

Ramos, Jose	Aviation Planning, Land-Use & Grants	305-876-8080	305-342-9514
<i>Division Director</i>			
Raymond, Michele	Real Estate Management & Development	305-876-0363	305-495-1072
<i>Division Director</i>			
Riesgo, Alicia	Customer Initiatives	305-876-0271	786-351-2986
<i>Division Director</i>			
Sariego, Jorge	Terminal Building Maintenance	305-876-7325	305-458-6035
<i>Division Director</i>			
Simm, Michael	GAA Facilities Maintenance & Public Works	305-876-8479	305-773-4234
<i>Division Director</i>			
Smith, Janice	Finance/Accounting	305-876-0733	305-781-4453
<i>Division Director (Controller)</i>			
Thomas-Stacey, Toni	Human Resources	305-876-0856	305-458-3579
<i>Division Director</i>			
Lopez-Villazan, Yoel	Human Resources	305-876-7557	786-795-3187
<i>Sr. Human Resources Manager</i>			
Armand, Cristina	Social Media	305-876-7434	786-479-5648
<i>Manager</i>			
Bryant, Mike	Information Systems	305-876-0878	786-769-1992
<i>Manager</i>			
Feeney, Susan	Security & Public Safety	305-876-7016	786-493-6579
<i>Manager</i>			
Jackson, Sandra L.	Human Resources	305-876-0995	305-342-1079
<i>Manager</i>			
Jackson-Wright, Kimarkia	Human Resources	305-876-7594	786-334-8231
<i>Manager</i>			
Pineda, Emir	Marketing	305-876-7865	786-502-6072
<i>Manager</i>			
Sherer, Gendry	Airport Fine Arts & Cultural Affairs	305-876-0859	786-606-9318
<i>Manager</i>			
4 FIRE DEPARTMENT - AIRPORT DISTRICT			
NAME	DEPARTMENT	OFFICE	CELLULAR
Chief Enrique J. Rojas	MDFR	786-336-6592	305-498-0576
Chief Al Cruz	MDFR	305-876-1498	786-229-1411
Chief Omar Ricardo	MDFR	786-336-6593	786-258-6963
5 POLICE DEPARTMENT - AIRPORT DISTRICT			
NAME	DEPARTMENT	OFFICE	CELLULAR
Major Eric Garcia	MDPD	305-876-7416	305-510-9494
Captain R. Jaime Nunez	MDPD	305-876-7558	786-205-0745
6 OTHER MIAMI-DADE COUNTY DEPARTMENTS			
NAME	DEPARTMENT	OFFICE	CELLULAR
Hot Line (24 hours)	Derm	305-372-6955	N/A
Dr. Yesenia Diaz Villalta, Administrator	FL Dept. of Health - Miami-Dade	305-324-2400	N/A
Samir M. Elmir, Administrator	HRS-Environmental Health (FL Dept. Health)	305-623-3500	N/A
Charles L. Cyrille	Emergency Management Interim Director	305-468-5400	N/A
Duty Officer	Emergency Management	305-468-5800 / 24 Hrs.	N/A
Emergency Management Coordinator	Emergency Management	305-468-5400 or 305-468-5419	N/A
ISD in the EOC	ISD	305-468-5886	N/A

EMERGENCY TELEPHONE LIST

CONFIDENTIAL

7	U.S. GOVERNMENT DEPARTMENTS & AGENCIES				
	DEPARTMENT / AGENCY			OFFICE	24 HOURS
	ATF - Alcohol, Tobacco, Firearms and Explosives Agency			305-597-4800	
	CBP - US Customs and Border Protection Agency - Command Center			305-874-5403	305-874-5403
	CBP Asst. Port Director - Duty Supervisor & Passenger Control - 6AM - 4 PM			786-369-3816	305-874-5403
	CDC - Center for Disease Control - MIA Quarantine Station - 24 hr.			305-526-2910	
	DEA - Drug Enforcement Administration - Miami Field - M - F 9AM - 5:30 PM			954- 660-4500	
	FAA - Fed. Avia. Admin. - Flight Standards (FDSO) Dist. 19 - MIA Field Office			954-641-6000 M - F 8:00 - 11:30 & 12:30 - 4:30	404-305-5180 after hours
	FAA - Federal Aviation Miami Security Field Office			954-641-6700	404-305-5180
	FAA - General Operations Center			404-305-5180	
	FBI - Federal Bureau of Investigations			754-703-2000	
	FCC - Federal Communication Commission			1-888-225-5322	
	ICE - Homeland Security Investigation			Daytime Hrs. 305-597-2849	After Hrs. 305-597-6000
	Miami Air Traffic Control Tower (ATC)			305-869-5400 - 7AM - 4PM	Tracom - 305-869-5432
	Miami Air Route Traffic Control Center- (ARTCC)			305-716-1500	24/7 - 305-716-1588
	NTSB - National Transp. Safety Board- NTSB - Office of Aviation Safety			571-223-3930	
	NTSB 24 Hour Response Operations Center			844-373-9922	
	NTSB - Public Inquiries			202-314-6000	
	NTSB - Status Reference Specific Accident Investigation			571-223-3930	
	Secret Service (24 Hrs.)			305-863-5000	
	TSA - MIA - Coordination Center			24/7 - 305-421-2421	
	USDA-APHIS Veterinary Svcs. Animal Import Center (Imports, Exports, Inspections & Quarantines) - MIA (Mon-Fri)			305-876-2200	
8	WEATHER SERVICE				
	AGENCY NAMES			OFFICE	
	National Hurricane Center			9AM - 5 PM - 305-229-4470	
	National Weather Service (NWS) Forecaster - 24 hrs.			305-229-4528	
	Coast Guard - Miami Station - Command Ctr. Emergency Notifications			305-535-4472	
	Coast Guard - Miami Air Station			305-953-2130 or 2100	
9	FLORIDA STATE DEPARTMENTS				
	AGENCY NAMES			OFFICE	
	Florida Highway Patrol			305-470-2500	
	South Florida Water Management District - Miami Field Station			6 AM - 4:30 - 305-592-5680 or 305-513-3420	
	FL Dept. of Children and Families - Alcohol, Drug Abuse & Mental Health - Admin Office			786-257-5148	
	Banyan Mobile Response Team: Crises Contract for Children/Fam - Alcohol, Drug Abuse & Mental Health			24/7 - 305-774-3616 or 305-774-3617	
	FL Bureau of Radiation Control - Miami			850-491-0949	
10	MEDICAL OFFICES				
	DEPARTMENT			OFFICE	FAX
	Baptist Medical Plaza - Beacon			786-596-3860	786-596-3862
	Airport Medical Clinic			305-592-5205	305-597-8362
	Occupational Health and Wellness			305-599-9933	305-594-2772
	Physician Health Center - Airport (36th Street)			305-871-3627	N/A

EMERGENCY TELEPHONE LIST

CONFIDENTIAL

11 HOSPITALS			
MIAMI-DADE COUNTY HOSPITALS		TELEPHONE	
Aventura Hospital and Medical Center			305-682-7000
Baptist Hospital of Miami			786-596-1960
Baptist Health West Kendall Baptist Hospital/Baptist Health South FL			786-467-2000
Coral Gables Hospital			305-445-8461
Doctor's Hospital/Baptist Health South FL/Baptist Health Systems			786-308-3000
Hialeah Hospital			305-693-6100
Holtz Children's Hospital/Jackson Health			305-585-5437
Baptist Health Homestead Hospital/Baptist Health South FL			786-243-8000
Jackson Heart Institute/Jackson Health System			305-585-4564
Ryder Trauma Center/Jackson Memorial Hospital			305-585-1111
Jackson North Medical Center			305-651-1100
Jackson South Medical Center			305-251-2500
Kendall Regional Medical Center			305-223-3000
Larkin Community Hospital - South Miami			305-284-7500
Larkin Community Hospital - Palm Springs Campus			305-558-2500
Mercy Hospital			305-854-4400
Miami Burn Center-Jackson Health System / Recesitation-ER			305-5851192 / ER 305-585-1148
Mount Sinai Medical Center			305-674-2121
Mount Sinai- Aventura - Free Standing ED only (ER)			305-692-1000 / 1010
Nicklaus Children's Hospital (Miami Children's Hospital)			305-666-6511 & 662-7702
North Shore Medical Center			305-835-6000
Palmetto General Hospital			305-823-5000
Ryder Trauma Center/Jackson Memorial			305-585-1152
South Miami Hospital			786-662-4000
UM/Cedars (University of Miami Hospital)			305-325-5511 & 305-689-4515
Veterans (Bruce W. Carter VA Medical Center)			305-324-4455 & 305-575-7000
SOUTH BROWARD COUNTY HOSPITALS		TELEPHONE	
Cleveland Clinic			954-689-5000/ 954-602-6000
Memorial Hospital Miramar			954-538-5000
Memorial Hospital Pembroke			954-962-9650
Memorial Regional Hospital			954-987-2000
Memorial Regional South Hospital			954-518-5000
Memorial Hospital West			954-436-5000
12 NON-INJURES, MINOR ASSEMBLY AREAS			
AIRPORT HANGARS		CONTACT	OFFICE
Northeast Base		Manager	
Central Base - American Airlines - Hangar Operations 24/7		Shift Manager Aircraft Maintenance	786-591-3955
TERMINAL BUILDING HOLD ROOMS		CONTACT	OFFICE
Concourse Hold Rooms		Terminal Supervisor	305-876-7081
Concourse D Auditorium		MIA Hotel	305-871-4100, ext 2238
13 TRANSPORTATION SERVICES			
COMPANY NAME		TELEPHONE	
Randle-Eastern Ambulance Service, Inc./AMR Medics			305-718-6400
MDPD Helicopter-(Opa-Locka)			305-463-6420 or 305-953-6000
MDPD Helicopter (Tamiami)			305-463-6400
MDFR/Air Rescue			305-513-7924 (St 24) or 305-513-7683 or 305-513-7680 or 911

EMERGENCY TELEPHONE LIST

CONFIDENTIAL

14	COMMON ASSISTANCE AGENCIES				
	AGENCY NAME	TELEPHONE			
	American Red Cross, S. FL Region - Debra Koch - Executive Director	305-644-1200, Ext. 282510			
15	UTILITIES SERVICES				
	COMPANY NAME	TELEPHONE			
	Florida City Gas Company - Jonathan Vreeland, Dir. Of Oper.	Cell - 786-582-9437			
	Miami-Dade Water & Sewer - Roy Coley, Director	305-665-7477 & 24 hr. emergency: 305-274-9272			
	Florida Power & Light	305-442-8770			
	MDAD Contact- Adriana Alvarez	305-442-5542 & Cell - 305-775-6047			
16	COMMUNICATIONS				
	COMPANY NAME	TELEPHONE			
	Blackbox	Service calls to 305-869-5900			
	Maria Perez - MDAD Telecommunications	305-876-7092			
	AT & T Repair Center	1-800-247-2020			
17	ESCALATOR & ELEVATOR SERVICE				
	DEPARTMENT	OFFICE			
	MDAD Airport Operations Center (AOC)	305-876-0385			
18	VEHICLE FUELING SERVICES				
	COMPANY NAME	OFFICE			
	Main Fuel - Orders (MDC - ISD Fleet)	305-375-5186 - office hours			
	Spills & Repairs (MDC - ISD Fleet)	786-258-6778			
19	AIRCRAFT SERVICE COMPANIES				
	COMPANY NAME	OFFICE			
	American Sales & Management	305-269-2730 or 305-870-3704			
	G2 Secure Staff LLC	954-612-6759			
	Swissport USA	AOC - 786-838-4071 or Opr. Mgr. 786-471-1372			
	Triangle Services of Florida	305-871-8622 X 221			
	Ultra Aviation Services, Inc.	305-876-0091			
20	REMOVAL OF DISABLED AIRCRAFT				
	COMPANY NAME	OFFICE / AFTER HOURS			
	Signature Aviation - Light Aircraft	305-874-1477			
	Kauff's Towing	305-685-7593 or 305-889-1200			

ALERT II & III ON AIRPORT CHECKLISTⁱ

ALERT II

1. Establish CP with IC (Fire Commander)
2. Assign Agent(s) for sweep
3. Assign Agent to follow aircraft to parking
4. If debris/spill is found, close runway for clean-up
 - a. Issue NOTAM for closure exceeding 30 minutes
5. Inspecting Agent to notify ATCT when all vehicles are clear

ALERT III

1. Close Airport (Airfield)
2. Direct the AOC to notify the Blue and Green lists
3. Establish liaison with IC
4. Place "Cert Team" on standby with Station 5 (Maintenance 1 after hours)
5. Establish Air Rescue LZ if directed by IC
6. Establish Rendezvous point
7. Establish Outer perimeter
8. Cancel all delivery escorts
9. Open any unaffected areas provided Index "E" minimums are available
10. Issue NOTAM(s)

POST LIFE SAFETY ACTIVITIES

11. Establish Inner & Outer perimeter
12. Protect property & wreckage
13. Record all personnel who enter site
14. Allow only the following:
 - a. FAA
 - b. Police / Fire / EMS
 - c. Medical Examiner / Coroner
 - d. Other Emergency Services Agencies
15. Upon NTSB arrival – no access without NTSB authorization.

QUICK REFERENCE

INDEX E EQUIPMENT			
3 VEHICLES MINIMUM - one carrying 500 lbs sodium-based dry chemical, halon 1211, or clean agent, or 450 lbs potassium-based dry chemical and water with a commensurate quantity of AFFF to total 100 gallons for simultaneous dry chemical and AFFF application. Two vehicles carrying commensurate AFFF and water so the total quantity of water for foam production by all three vehicles is at least 6,000 gallons.			
Vehicle	Water (gal)	AFFF (gal)	Dry Chemical (lbs)
Foam 1	3000	400	450
Foam 2	3000	400	450
Foam 3	3000	400	450
Foam 4	1500	200	450
QRV 59	300	40	450
Engine 12	750		
Platform 59	500		

If Index "E" minimums are not met OR ARFF unable to maintain Index "E" to respond to a secondary event, Notify 1600 & 1601 Immediately!

HELO LANDING ZONE

Area clear of trees, high mast lights and aircraft operation.€

ⁱ This checklist represents quick reference data only. Complete information is detailed in section 2.5.3.2. Procedures, Aircraft Incidents and Accidents of the Airport Emergency Plan.